



LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

A PORTION OF TRACT 3A2 , NELLIE D. MUNDY
SURVEY NO. 240 , CITY OF EL PASO , EL PASO
COUNTY , TEXAS
CONTAINING 10.08± ACRES




VICINITY MAP
APPROXIMATE SCALE:
1" = 2 MILES


SHEET NUMBER	SHEET TITLE
CVR	COVER SHEET
C1.1	GENERAL INFORMATION
C2.1	FINAL PLAT
C3.1	GRADING PLAN
C4.1-C4.2	DRAINAGE PLAN
C5.1	GRADING SECTIONS
C6.1-C6.3	STREET PLAN & PROFILES
C7.1-C7.3	STORM SEWER PLAN & PROFILES
C7.4-C7.6	SEWER UTILITY CROSSINGS
C8.1-C8.2	STANDARD DETAILS
C9.1-C9.4	DRAINAGE DETAILS
S1	12'x5' REINFORCED CONCRETE BOX CULVERT
C10.1-C10.2	ILLUMINATION PLAN / DETAILS
C11.1	WATER INDEX / GENERAL INFORMATION
C11.2-C11.5	WATER DETAILS
C12.1	SANITARY SEWER INDEX / GENERAL INFORMATION
C12.2-C12.3	SANITARY SEWER PLAN & PROFILES
C12.4-C12.6	SANITARY SEWER DETAILS
C13.1-C13.3	STORM WATER POLLUTION PREVENTION PLAN




LOCATION MAP
APPROXIMATE SCALE: 1" = 600'



7/3/19
JORGE L. AZCARATE, P.E. PROJECT MANAGER



TEXAS REGISTERED ENGINEERING FIRM F-4564
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5232 | www.ceagroup.net



Reviewed For Conformance For Condition Related To:

- Erosion
- Grading Or Drainage
- Wetlands Range
- City Site Parking Layout
- Drainage
- Retaining Rock Walls
- City Site Parking of Storm Water

Contractor Must Call 24 Hours Prior To Construction for Inspections

07/10/2019

PRINCIPAL CONTACTS:

NAME	ADDRESS	CITY & ZIP	PHONE	FAX
OWNER:	TROPICANA DEVELOPMENT INC. 4712 WOODROW BEAN DR. STE. A	EL PASO, TX 79924	(915) 757-1802	(915) 757-1827
ENGINEER:	CEA GROUP 4712 WOODROW BEAN DR. STE. F	EL PASO, TX 79924	(915) 544-5232	(915) 544-5233
SURVEYOR:	BARRAGAN & ASSOCIATES 10950 PELLICANO DR. BUILDING F	EL PASO, TX 79936	(915) 591-5709	(915) 591-5706

GENERAL NOTES

1. THE CONTRACTOR SHALL VISIT AND FAMILIARIZE HIMSELF WITH THE PROJECT SITE PRIOR TO SUBMITTING BIDS.
2. CONTRACTOR SHALL WATER CONSTRUCTION AREA A MINIMUM OF TWICE A DAY TO KEEP DUST TO A MINIMUM - ONCE IN THE MORNING AND BEFORE QUITTING TIME. THIS SHALL ALSO BE DONE DURING WEEKENDS AND HOLIDAYS.
3. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE, PROTECT, AND REPLACE ALL UNDERGROUND UTILITY LINES AT NO EXTRA COST TO THE OWNER WHEN LINES ARE DISTURBED AS A RESULT OF THE WORK.
4. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO SCHEDULE AND PERFORM HIS WORK SO AS TO ASSURE PROPER PASSAGE OF STORM RUNOFF DURING THE COURSE OF HIS OPERATIONS. ALL LABOR, TOOLS, EQUIPMENT, AND SUPERVISION REQUIRED TO ASSURE SUCH PROPER PASSAGE OF RUNOFF WATER AND ANY REMOVAL OR HANDLING OF WATER IN ORDER TO MAINTAIN DRY CONDITIONS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE AT THE EXPENSE OF THE CONTRACTOR.
5. THE CONTRACTOR SHALL COORDINATE THE CONSTRUCTION SCHEDULE WITH THE USER, ALL UTILITIES, AND ALL OTHER AGENCIES WITH JURISDICTION OVER THE PROJECT.
6. ALL EXISTING PAVEMENT, ADJACENT UTILITIES, STRUCTURES, ETC., DISTURBED AS A RESULT OF THE NEW CONSTRUCTION, SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
7. THE OWNER WILL FURNISH HORIZONTAL AND VERTICAL CONTROL REFERENCED POINTS ONLY. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND GRADES BEFORE PROCEEDING WITH THE WORK. ANY DISCREPANCIES FOUND SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER, OTHERWISE THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR THEIR CORRECTNESS.
8. SEE REFERENCED BENCHMARK ON TITLE BLOCK FOR DATUM ELEVATIONS.
9. VIBRATORY ROLLERS WILL NOT BE PERMITTED ON ANY PHASE OF THIS PROJECT, UNLESS APPROVED IN WRITING BY THE CITY ENGINEER.
10. ALL WORK REQUIRED BY THESE PLANS SHALL BE CONDUCTED IN CONFORMANCE WITH CURRENT SAFETY CODES AND STANDARDS WITH JURISDICTION OVER THE PROJECT.
11. THE LOCATION OF THE INLETS SHALL BE AT THE FIELD LOW POINT AND APPROVED BY THE ENGINEER.

LEGEND

- SUBDIVISION BOUNDARY
- ROW LINE
- CURB LINE
- PROPERTY LINE
- STREET CENTERLINE
- EASEMENT LINE
- MATCH LINE
- STORM SEWER LINE
- HIGH WATER MARK
- CURB AND GUTTER DROP INLET
- STORM SEWER MANHOLE
- 4000 FINISHED GROUND CONTOUR ELEVATION (INDEX)
- FINISHED GROUND CONTOUR ELEVATION (INTERMEDIATE)
- 4000 EXISTING GROUND CONTOUR ELEVATION (INDEX)
- EXISTING GROUND CONTOUR ELEVATION (INTERMEDIATE)
- NEW RETAINING ROCKWALL (2'-3" IN HEIGHT)
- NEW RETAINING ROCKWALL (3'-9" IN HEIGHT)
- STANDARD DETAIL/SECTION NUMBER
- SHEET NUMBER WHERE STANDARD/SECTION DETAIL IS LOCATED
- 4000.00 FINISHED SPOT ELEVATION
- FG 4000.00 LOT FINISHED GROUND ELEVATION
- TC 4000.00 TOP OF CURB ELEVATION
- TP 4000.00 TOP OF PAVEMENT ELEVATION
- 1 ② SUBDIVISION LOT AND BLOCK NUMBER
- DRAINAGE FLOW
- ▲ HIGH POINT
- ▼ LOW POINT
- ◁ ▷ EXISTING HIGH POINT
- ◁ ▷ EXISTING LOW POINT
- ▣ HEADWALL WITH WINGWALLS
- DA-1 DRAINAGE AREA
- 3:1 SLOPE HORIZONTAL-VERTICAL SLOPE RATIO
- ♿ WHEELCHAIR RAMP

GRADING SPECIFICATIONS

1. CLEARING AND GRUBBING: CLEAR SITE OF TREES, SHRUBS AND OTHER VEGETATION; COMPLETELY REMOVE STUMPS, ROOTS AND OTHER DEBRIS PROTRUDING THROUGH GROUND SURFACE; FILL DEPRESSIONS CAUSED BY CLEARING AND GRUBBING OPERATIONS WITH SATISFACTORY FILL MATERIAL, UNLESS FURTHER EXCAVATION OF EARTHWORK IS INDICATED; REMOVE EXISTING ABOVE-GRADE AND BELOW-GRADE IMPROVEMENTS AS INDICATED AND AS NECESSARY TO FACILITATE NEW CONSTRUCTION. BURNING IS NOT PERMITTED ON OWNER'S PROPERTY. REMOVE WASTE MATERIALS FROM OWNER'S PROPERTY.
2. SATISFACTORY FILL MATERIALS: FILL MATERIALS SHALL BE FREE OF ANY ORGANIC OR DELETERIOUS SUBSTANCE AND SHALL NOT CONTAIN ROCKS OR LUMPS OVER 3 INCHES IN GREATEST DIMENSION AND SHALL BE DEFINED AS THOSE COMPLYING WITH ASTM D2487 SOIL CLASSIFICATION GROUPS GW, GP, GM, GC, SM, SP, SM, AND SC.
3. UNSATISFACTORY FILL MATERIAL: ARE DEFINED AS THOSE COMPLYING WITH ASTM D2487 SOIL CLASSIFICATION GROUPS ML, MH, CL, CH, OL, OH, AND PT, OR WHERE THE PLASTICITY INDEX EXCEEDS 12, UNLESS OTHERWISE APPROVED BY ENGINEER, OR CITY ENGINEER.
4. EXCAVATION: IS UNCLASSIFIED AND INCLUDES EXCAVATION TO ELEVATIONS INDICATED, REGARDLESS OF CHARACTER OF MATERIAL AND OBSTRUCTIONS ENCOUNTERED.
5. GROUND SURFACE PREPARATION FOR FILL: REMOVE VEGETATION, DEBRIS, UNSATISFACTORY SOIL MATERIAL, OBSTRUCTIONS, AND DELETERIOUS MATERIAL FROM GROUND SURFACE UPON WHICH THE FILL IS TO BE PLACED. THE SURFACE SHALL THEN BE SCARIFIED TO A DEPTH OF AT LEAST 6-INCHES, AND UNTIL THE SURFACE IS FREE FROM RUTS, HUMMOCKS OR OTHER UNEVEN FEATURES WHICH WOULD PREVENT UNIFORM COMPACTION. PLOW STRIP, OR BREAK UP SLOPED SURFACES STEEPER THAN 1 VERTICAL TO 4 HORIZONTAL SO THAT FILL MATERIAL WILL BOND WITH EXISTING SURFACE. AFTER PLOWING AND SCARIFYING FILL AREA, IT SHALL THEN BE DISCED OR BLADED UNTIL IT IS UNIFORM AND FREE FROM LARGE CLODS, BROUGHT TO OPTIMUM MOISTURE, AND COMPACTED TO 95% OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM D-1557.
6. PLACEMENT OF FILL: PLACE BACKFILL AND FILL MATERIALS IN LAYERS NOT MORE THAN 8 INCHES IN LOOSE DEPTH FOR MATERIAL COMPACTED BY HEAVY COMPACTION EQUIPMENT, AND NOT MORE THAN 4 INCHES IN LOOSE DEPTH FOR MATERIAL COMPACTED BY HAND-OPERATED TAMPERS. BEFORE COMPACTION, MOISTEN OR AERATE EACH LAYER AS NECESSARY TO PROVIDE OPTIMUM MOISTURE CONTENT. PLACE FILL MATERIALS EVENLY ADJACENT TO SITE APPURTENANCES, PIPING, OR CONDUIT TO REQUIRED ELEVATIONS. PREVENT WEDGING ACTION OF BACKFILL AGAINST SITE APPURTENANCES OR DISPLACEMENT OF PIPING OR CONDUIT BY CARRYING MATERIAL UNIFORMLY AROUND SITE APPURTENANCES, PIPING, OR CONDUIT TO APPROXIMATELY SAME ELEVATION IN EACH LIFT. COMPACT SOIL TO NOT LESS THAN 95% OF MAXIMUM DENSITY, IN ACCORDANCE WITH ASTM D-1557.
7. MOISTURE CONTROL: WHERE SUBGRADE OR LAYER OF SOIL MATERIAL MUST BE CONDITIONED FOR OPTIMUM MOISTURE BEFORE COMPACTION, UNIFORMLY APPLY WATER TO SURFACE OF SUBGRADE OR LAYER OF SOIL MATERIAL. APPLY WATER IN MINIMUM QUANTITY AS NECESSARY TO PREVENT FREE WATER FROM APPEARING ON SURFACE DURING OR SUBSEQUENT TO COMPACTION OPERATIONS. WATER CONTENT SHALL BE WITHIN 2 PERCENTAGE POINTS OF OPTIMUM MOISTURE CONTENT. REMOVE AND REPLACE OR SCARIFY AND AIR DRY SOIL MATERIAL THAT IS TOO WET TO PERMIT COMPACTION TO SPECIFIED DENSITY.
8. QUALITY CONTROL: THE OWNER SHALL PROVIDE A GEOTECHNICAL ENGINEER TO PERFORM FIELD DENSITY TEST OF THE COMPACTION OF EACH LAYER OF FILL. DENSITY TESTS SHALL BE TAKEN IN THE COMPACTED MATERIAL BELOW THE DISTURBED SURFACE. WHEN THESE TESTS INDICATE THAT THE DENSITY OF ANY LAYER OF FILL OR PORTION THEREOF IS BELOW THE REQUIRED DENSITY, THE PARTICULAR LAYER OR PORTION SHALL BE REWORKED UNTIL THE REQUIRED DENSITY HAS BEEN OBTAINED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ADDITIONAL TESTING AND WHEN REQUIRED DENSITIES ARE NOT MET, SUPERVISION BY THE GEOTECHNICAL ENGINEER DURING THE GRADING OPERATIONS TO ENSURE GRADING WORK IN ACCORDANCE WITH THIS PLAN AND SPECIFICATIONS.

ABBREVIATIONS

- LP LOW POINT
- HP HIGH POINT
- ELEV ELEVATION
- STA STATION
- VCS VERTICAL CURVE STATION
- VCE VERTICAL CURVE ELEVATION
- TC TOP OF CURB
- TM TOP OF MEDIAN
- TP TOP OF PAVEMENT
- TYP TYPICAL
- PVC POINT OF VERTICAL CURVE
- PVI POINT OF VERTICAL INTERSECTION
- PVT POINT OF VERTICAL TANGENT
- AD ALGEBRAIC DIFFERENCE
- CR CURVE RETURN
- ROW RIGHT OF WAY
- CL CENTER LINE
- PL PROPERTY LINE
- FG FINISH GRADE
- FF FINISH FLOOR
- EG EXISTING GRADE
- MIN. MINIMUM
- MAX. MAXIMUM
- ROP REINFORCED CONCRETE PIPE
- Q QUANTITY
- CAP CAPACITY
- EXP EXPECTED
- INV INVERT
- CFS CUBIC FEET PER SECOND
- A AREA
- DA DRAINAGE AREA
- LF LINEAR FEET
- STD STANDARD
- CONC CONCRETE
- PC POINT OF CURVATURE
- PI POINT OF INTERSECTION
- PT POINT OF TANGENT
- L LENGTH
- R RADIUS
- T TANGENT
- Δ DELTA ANGLE
- S SLOPE
- TEMP TEMPORARY
- V VELOCITY IN FEET PER SECOND
- HGL HYDRAULIC GRADE LINE
- HWE HIGH WATER ELEVATION

UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 945-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

INDEX OF DRAWINGS

DRAWING NAME	SHEET NO.
COVER	CVR
GENERAL INFORMATION	C1.1
FINAL PLAT	C2.1
GRADING PLAN	C3.1
DRAINAGE PLAN (SHEET 1 OF 2)	C4.1
DRAINAGE PLAN (SHEET 2 OF 2)	C4.2
GRADING SECTIONS	C5.1
PLAYA TRONONES DRIVE PLAN & PROFILE FROM STA. 0+00.00 TO STA. 7+50.00	C6.1
PLAYA TRONONES DRIVE PLAN & PROFILE FROM STA. 7+50.00 TO STA. 8+27.83	C6.2
IXTAPA STREET PLAN & PROFILE FROM STA. 0+00.00 TO STA. 5+00.00	C6.3
LINE A PLAN & PROFILE FROM STA. 0+00.00 TO STA. 6+00.00	C7.1
LINE A PLAN & PROFILE FROM STA. 6+00.00 TO STA. 12+99.51	C7.2
LINE B PLAN & PROFILE FROM STA. 0+00.00 TO STA. 1+35.37	C7.3
LINE C PLAN & PROFILE FROM STA. 0+00.00 TO STA. 0+57.24	C7.3
SEWER UTILITY CROSSING (SHEET 1 OF 3)	C7.4
SEWER UTILITY CROSSING (SHEET 2 OF 3)	C7.5
SEWER UTILITY CROSSING (SHEET 3 OF 3)	C7.6
STANDARD DETAILS (SHEET 1 OF 2)	C8.1
STANDARD DETAILS (SHEET 2 OF 2)	C8.2
DRAINAGE DETAILS (SHEET 1 OF 4)	C9.1
DRAINAGE DETAILS (SHEET 2 OF 4)	C9.2
DRAINAGE DETAILS (SHEET 3 OF 4)	C9.3
DRAINAGE DETAILS (SHEET 4 OF 4)	C9.4
12'x5' REINFORCED CONCRETE BOX CULVERT	S1
ILLUMINATION AND SIGNAGE PLAN	C10.1
ILLUMINATION AND SIGNAGE DETAILS	C10.2
WATER LINE INDEX	C11.1
WATER DETAILS (SHEET 1 OF 4)	C11.2
WATER DETAILS (SHEET 2 OF 4)	C11.3
WATER DETAILS (SHEET 3 OF 4)	C11.4
WATER DETAILS (SHEET 4 OF 4)	C11.5
SANITARY SEWER INDEX	C12.1
SANITARY SEWER PLAN & PROFILE: LINE A	C12.2
SANITARY SEWER PLAN & PROFILE: LINE B & C	C12.3
SANITARY SEWER DETAILS (SHEET 1 OF 3)	C12.4
SANITARY SEWER DETAILS (SHEET 2 OF 3)	C12.5
SANITARY SEWER DETAILS (SHEET 3 OF 3)	C12.6
STORM WATER POLLUTION PREVENTION PLAN: GENERAL NOTES	C13.1
STORM WATER POLLUTION PREVENTION PLAN: SITE PLAN	C13.2
STORM WATER POLLUTION PREVENTION PLAN: DETAILS	C13.3


REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL SOL AND WASHINGTON ELEVATION = 3827.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3835.48 (CITY DATUM)

DATE	REVISIONS	BY

ca

TEXAS REGISTERED ENGINEERING FIRM #484
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5232 | www.caengineering.com



SCALE

Horizontal: N/A
Vertical: N/A

Contour Interval: N/A

DATE: DECEMBER 2018

DESIGN BY: C.J.

DRAWN BY: M.R.G.

CHKD. BY: J.L.A.

APPROV. BY: J.L.A.

JOB NO. 2000-210

PROJECT TITLE

**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE

GENERAL INFORMATION

SHEET NO.



Final Approval

C1.1

PLAT NOTES AND RESTRICTIONS:

- THIS IS TO CERTIFY THAT WATER AND SEWER SERVICES WILL BE PROVIDED TO LA PUESTA DEL SOL UNIT FOUR SUBDIVISION BY THE EL PASO WATER UTILITIES/PUBLIC SERVICE BOARD IN ACCORDANCE WITH THEIR RULES AND REGULATIONS AND WITH SECTION 16.343 OF THE TEXAS WATER CODE. WATER AND SEWER SERVICES WILL BE EXTENDED TO THE SUBDIVISION FROM EXISTING FACILITIES LOCATED ON JOSE LEON DRIVE, AND ISELA RUBALCAVA STREET WILL BE CONSTRUCTED TO SERVE THE SUBDIVISION.
- TAX CERTIFICATE(S) FOR THIS SUBDIVISION ARE FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORD SECTION, INSTRUMENT NO. 20190091737, DATE 11-27-2019.
- RESTRICTIVE COVENANTS FOR THIS SUBDIVISION ARE FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORD SECTION, INSTRUMENT NO. 20190091738, DATE 11-27-2019.
- VEHICULAR ACCESS TO THOSE RESIDENTIAL LOTS ABUTTING ISELA RUBALCAVA STREET SHALL BE FROM OTHER DEDICATED STREET ONLY. THE INSTRUMENT ASSURING RELEASE OF ACCESS IS FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORD SECTION, INSTRUMENT NO. _____ DATE _____.
- SUBDIVISION IMPROVEMENTS AGREEMENT & GUARANTEE FOR THIS SUBDIVISION IS FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORD SECTION, INSTRUMENT NO. 20190091739, DATE 11-27-2019.
- INTERIOR LOT CORNERS WILL BE SET UP ON COMPLETION OF CONSTRUCTION OF ROADWAYS AND UTILITIES. (BY OTHERS) SET 1/2" REBAR WITH CAP STAMPED "B&A INC" AT ALL EXTERIOR BOUNDARY CORNERS UNLESS OTHERWISE SHOWN.
- "U.S. POSTAL SERVICE DELIVERY WILL BE PROVIDED THROUGH NEIGHBORHOOD DELIVERY AND COLLECTION BOX UNITS."
- THIS SUBDIVISION LIES WITHIN ZONE "X" AND REVISED TO REFLECT LOMR EFFECTIVE: JANUARY 21, 2015, AS DESIGNATED IN PANEL NO. 480212-0125B.
- ⊙ DENOTES PROPOSED MONUMENT. (FOR EXACT LOCATION CONTACT CITY OF EL PASO)
- ⊠ DENOTES A FOUND 5/8" REBAR WITH ALUMINUM CAP STAMPED "TX RPLS 2198" (DOC. NO. 20110035783, NOW OBLITERATED).
- △ DENOTES EXISTING MONUMENT.
- DEED REFERENCE: DOC. NO. 20070072034, DOC. NO. 201000029694, AND DOC. NO. 20170072947.

LA PUESTA DEL SOL UNIT FOUR

La Puesta Del Sol Unit Four Subdivision is subject to impact fees and they shall be calculated based on the table below.

Chapter 395 of the Texas Local Government Code authorizes the City of El Paso to adopt and impose water and wastewater impact fees. This plat note fulfills an obligation mandated by Chapter 395 and sets the assessment of the impact fees in accordance with the impact fee schedule adopted by City Council as set forth below. The collection of the impact fee for this subdivision shall be at the time of the meter connection if development is outside the city limits.

WESTSIDE SERVICE AREA

Meter Size	Meter Capacity Ratio	*Water (\$)	Wastewater (\$)
Less Than 1"	1.00	659.00	927.00
1"	1.67	1,101.00	1,548.00
1 1/2"	3.33	2,195.00	3,087.00
2"	5.33	3,514.00	4,941.00
3"	10.00	6,593.00	9,270.00
4"	16.67	10,990.00	15,453.00
6"	33.33	21,973.00	30,897.00
8"	53.33	35,158.00	49,437.00
10"	76.67	50,545.00	71,073.00
12"	143.33	94,490.00	132,867.00

* Fees do not apply to water meter or connections made for standby fire protection service.

SCHOOL DISTRICT

CANUTILLO INDEPENDENT SCHOOL DISTRICT
7965 ARTCRAFT RD, EL PASO, TX 79932

RESIDENTIAL	= 61
TOTAL	= 61

LOCATION MAP

SCALE: 1" = 600'



FOUND 1 1/2" PIPE IN CONCRETE MARKED "240-241" (NOW OBLITERATED)

FOUND 1" REBAR W/CAP "TX 2027"


LINE	BEARING	LENGTH
L1	S89°59'19"E	171.44'
L2	S89°59'19"E	9.53'
L3	S00°00'41"W	105.00'
L4	N00°00'41"E	59.15'
L5	S00°00'41"W	15.85'
L6	N00°00'41"E	56.00'
L7	S89°59'19"E	56.00'
L8	S00°00'41"W	15.85'
L9	S00°00'41"W	115.00'
L10	S00°00'41"W	1.00'

CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
C1	56.00'	87.96'	56.00'	79.20'	S45°00'41"W	090°00'00"
C2	20.00'	6.57'	3.31'	6.54'	N18°14'22"W	018°48'46"
C3	70.00'	44.00'	22.75'	43.27'	S08°08'06"E	036°00'39"
C4	70.00'	35.46'	18.12'	35.08'	S24°22'57"W	029°01'26"
C5	70.00'	37.68'	19.31'	37.23'	S54°18'55"W	030°50'31"
C6	70.00'	46.43'	24.11'	45.59'	S88°44'23"W	038°00'25"
C7	70.00'	10.29'	5.15'	10.28'	N68°02'49"W	008°25'11"
C8	20.00'	9.13'	4.65'	9.05'	S76°54'47"E	026°09'06"
C9	20.00'	31.37'	19.96'	28.26'	N45°04'14"E	089°52'53"
C10	20.00'	31.47'	20.05'	28.32'	N44°56'32"W	090°08'39"
C11	20.00'	31.37'	19.95'	28.25'	S45°03'28"W	089°51'21"
C12	20.00'	31.46'	20.04'	28.31'	S44°55'46"E	090°07'07"
C13	30.00'	47.12'	30.00'	42.43'	S45°00'41"W	090°00'00"

BENCHMARK:
CITY MONUMENT LOCATED AT THE CENTERLINE INTERSECTION OF BERRINGER STREET AND BENTRIDGE DRIVE.
ELEVATION: 3820.85' (CITY DATUM) (BY RTK OBSERVATION)

FLOOD ZONE:
THIS SUBDIVISION LIES WITHIN ZONE "X" AND REVISED TO REFLECT LOMR EFFECTIVE: JANUARY 21, 2015, AS DESIGNATED IN PANEL NO. 480212-0125B.

BEARING BASIS
BEARINGS SHOWN ARE BASED ON THE DEED FILED IN DOCUMENT NO. 20070072034, REAL PROPERTY RECORDS OF EL PASO COUNTY, TEXAS.



SURVEY 240 (BEARING BASIS)
SURVEY 241
N89°59'19"W 3380.08' - TOTAL

TRACT 1A,
NELLIE D. MUNDY SURVEY NO. 240
EL PASO COUNTY, TEXAS

LA PUESTA DEL SOL UNIT FOUR

A PORTION OF TRACT 3A2,
NELLIE D. MUNDY SURVEY NO. 240,
CITY OF EL PASO, EL PASO COUNTY, TEXAS
CONTAINING 10.10 ACRES ±

DEDICATION

Tropicana Development Inc., the owners of this land, do hereby present this map and dedicate their respective portions of property to the use of the public, the streets, utility easements and drainage right-of-ways as hereon laid down and designated, including easements for overhead of service wires for pole type utilities and the right for installation of service poles alongside lot lines as may be required, easements for buried service wires, conduits and pipes for underground utilities, and the right to ingress and egress for service and construction, and the right to trim interfering trees and shrubs.

Witness my signature this 31st day of October 2019.

Gregory B. Bowling
Gregory B. Bowling, Vice-President

ACKNOWLEDGEMENT

STATE OF TEXAS
COUNTY OF EL PASO
Before me, the undersigned authority, on this day personally appeared Gregory B. Bowling, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that he executed the same as the act and deed for the purpose and consideration herein expressed.

Given under my hand and seal of office this 31st day of October 2019.

Nami Palz
Notary Public in and for El Paso County My Commission Expires 10-13-2021

CITY PLANNING COMMISSION

This subdivision is hereby approved as to the platting and as to the condition of the dedication in accordance with Chapter 212 of the Local Government Code of Texas
this 24 day of September 2019.

Chairperson *Executive Secretary*

Approved for filing this 27 day of November 2019.

Planning and Inspections Director


FILING

Filed and recorded in the office of the County Clerk of El Paso County, Texas, this 27th day of November 2019, in File No. 20190091736 of the Plat Records.


County Clerk *by Deputy*

Subdivision improvement plans prepared by and under the supervision of CEA Group. This plat represents a survey made on the ground by me or under my supervision and complies with the current Texas Board of Professional Land Survey Professional and Technical Standards.

JORGE L. AZCARATE, P.E.
Licensed Professional Engineer
Texas License No. 85075




Benito Barragan TX, R.P.L.S. No. 5615



CONTACT: JORGE L. AZCARATE, P.E. CONTACT: BENITO BARRAGAN, R.P.L.S.

DATE OF PREPARATION: MAY 2019







UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811

FOR FIELD LOCATING EXISTING UTILITIES



18.44.090 - WARRANTY

ANY PERSON ISSUED A PERMIT SHALL AGREE WARRANT AND MAINTAIN THE AREA DESCRIBED IN THE PERMIT FOR A PERIOD OF TWO YEARS AFTER THE PERMIT IS CLOSED BY THE CITY PURSUANT TO SECTION 18.44.220, OR UNTIL A BUILDING PERMIT IS ISSUED FOR THE PURPOSE OF MAINTAINING A STABILIZED SITE IN ACCORDANCE WITH THE APPROVED GSP, WHICHEVER FIRST OCCURS (THE "WARRANTY" OR "WARRANTY PERIOD"). THE CITY MAY CONDUCT INSPECTIONS OF THE PERMITTED AREA THROUGHOUT THE WARRANTY PERIOD AND REQUIRE MAINTENANCE AND CORRECTION OF THE WORK BY THE PERMIT HOLDER. FAILURE OF THE PERMIT HOLDER TO CORRECT THE WORK SHALL CONSTITUTE A FAILURE TO COMPLY WITH THE PROVISIONS OF THIS CHAPTER.

(Ord. No. 17516, § 1, 3-29-2011)

18.44.220 - PERMIT CLOSEOUT PROCEDURE

AFTER THE PERMITTEE COMPLETES THE GRADING UNDER THE PERMIT, THE PERMIT SHALL BE CLOSED. AS PART OF THE CLOSEOUT PROCEDURE, THE APPLICANT MUST SUBMIT THE FOLLOWING TO THE CITY:

A. A STATEMENT FROM THE ENGINEER OF RECORD THAT STATES, "THE GRADING OPERATION HAS BEEN SUBSTANTIALLY COMPLETED AND GENERALLY CONFORMS TO THE APPROVED SET OF PLANS." THE PERMITTEE SHALL CALL THE PERMIT OFFICIAL TO ESTABLISH THE BEGINNING OF THE WARRANTY PERIOD AND TO NOTIFY THE PERMIT OFFICIAL THAT THE GSP HAS BEEN IMPLEMENTED.

A COPY OF THE NOTICE OF TERMINATION FILED WITH THE STATE OR DATED CONSTRUCTION SITE NOTICE, IF APPLICABLE, IN ACCORDANCE WITH CHAPTER 15. THE CITY WILL ISSUE A LETTER STATING GENERAL CONFORMANCE TO THE PERMIT HAS BEEN MET AND THAT THE WARRANTY PERIOD REQUIREMENTS WILL CONTINUE TO BE IN EFFECT.

(Ord. No. 17516, § 1, 3-29-2011)

18.44.200 - ENGINEERING CONTROLS FOR GRADING

CONSTRUCTION ACTIVITY REQUIREMENTS:

- NO ON-SITE PROCESSING OF MATERIAL FOR COMMERCIAL OR RETAIL SALE SHALL BE ALLOWED. ON-SITE PROCESSING OF MATERIALS TO BE USED FOR PREPARATION OR CONSTRUCTION OF IMPROVEMENTS WITHIN THE SITE COVERED BY THE GRADING PERMIT SHALL BE ALLOWED.
- WORK SHALL BE CONDUCTED IN A MANNER THAT PRESERVES AND DOES NOT OBSTRUCT, IMPEDE OR INTERFERE WITH THE FLOW OF STORMWATER IN NATURAL DRAINAGE WAYS, UNIMPROVED CHANNELS OR WATERCOURSES, OR IMPROVED DITCHES, CHANNELS OR CANALS IN SUCH A MANNER AS THE CAUSE FLOODING WHERE IT WOULD NOT OTHERWISE OCCUR.
- CONSTRUCTION EQUIPMENT AND FENCING SHALL BE KEPT OUT OF WATERCOURSES EXCEPT WHEN NECESSARY TO PERFORM WORK ON THE APPROVED PLANS. ADEQUATE BY-PASS MEASURES SHALL BE INSTALLED WHERE TEMPORARY DRAINAGE BLOCKAGES WILL OCCUR. WHERE WORK WITHIN A CHANNEL IS DESIGNATED ON APPROVED PLAN, PRECAUTIONS SHALL BE TAKEN TO STABILIZE THE WORK AREA DURING CONSTRUCTION TO MINIMIZE EROSION AS SHOWN ON THE PLANS. THE CHANNEL, INCLUDING BED AND BANKS, SHALL ALWAYS BE RESTORED/RESTABILIZED IMMEDIATELY AFTER WORK IN THE CHANNEL IS COMPLETED.

- WHERE A DRAINAGE WAY WILL BE CROSSED BY CONSTRUCTION VEHICLES REGULARLY DURING CONSTRUCTION, A TEMPORARY CROSSING SHALL BE CONSTRUCTED AS REQUIRED IN THE APPROVED GRADING PLANS.
- MATERIAL STOCKPILING SHALL NOT BE ALLOWED WHEN GRADING OPERATIONS ARE IDLE FOR MORE THAN SEVEN CONSECUTIVE CALENDAR DAYS. STOCKPILING SHALL BE LIMITED TO TEN FEET HIGH WHEN GRADING OPERATIONS ARE BEING CONDUCTED.
- A TRAFFIC CONTROL PERMIT SHALL BE REQUIRED IF THE GRADING OPERATION WILL IMPACT TRAFFIC.
- ANY USE OF VIBRATORY EQUIPMENT SHALL NOT BE ALLOWED, UNLESS APPROVED IN WRITING BY THE PERMIT OFFICIAL IN ADVANCE OF SUCH USE.
- THE PERMIT OFFICIAL MUST BE NOTIFIED NO LATER THAN 4:00 PM THE DAY IN ADVANCE OF ANY GRADING WORK. ADDITIONAL ACTIVITY REQUIREMENTS/RESTRICTIONS MAY BE SPECIFIED BY THE DESIGN ENGINEER OF RECORD.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN. ELEVATION = 3887.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

DATE: _____ REVISIONS: _____ BY: _____

ENGINEER'S SEAL

SCALE: 1" = 100'

Horizontal: N/A
Vertical: N/A
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB NO.: 2000-210

PROJECT TITLE


**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE

GRADING PLAN

SHEET NO.

C3.1



UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

STORM CALCULATIONS FOR WATERSHED AREAS

DRAINAGE AREA NO. (1)	DRAINAGE AREA (AC) (2)	DESIGN STORM INTENSITY (150) (3)	TIME OF CONCENTRATION (4)	RUNOFF COEFF. (C) (5)	Q50 (CFS) (6)	DESIGN STORM INTENSITY (1100) (3)	Q100 (CFS) (6)
DA-1	6.340	3.59	23.75	0.60	13.65	3.60	13.69
DA-2	4.057	3.76	22.00	0.60	9.15	3.77	9.18
DA-3	2.315	3.32	27.05	0.60	4.610	3.91	5.43
DA-4	8.962	3.36	26.64	0.60	18.06	3.37	18.12
DA-5	4.139	3.47	25.20	0.60	8.62	3.48	8.64
DA-6	2.210	3.42	25.80	0.60	4.53	3.43	4.54
DA-7	3.620	3.39	26.10	0.60	7.36	3.41	7.40
DA-8	2.220	3.50	24.60	0.60	4.62	3.53	4.70

STORM CALCULATIONS FOR WATERSHED AREAS WITH UNDEVELOPED RUNOFF COEFFICIENT

DRAINAGE AREA NO. (1)	DRAINAGE AREA (AC) (2)	DESIGN STORM INTENSITY (150) (3)	TIME OF CONCENTRATION (4)	RUNOFF COEFF. (C) (5)	Q50 (CFS) (6)	DESIGN STORM INTENSITY (1100) (3)	Q100 (CFS) (6)
**DA-1	6.340	3.32	24.10	0.48	10.10	3.57	10.88
**DA-3	2.315	3.82	21.40	0.48	4.245	3.83	4.256
**DA-9	2.210	3.81	21.50	0.48	4.04	3.82	4.05

- REFERENCE: CITY OF EL PASO SUBDIVISION STANDARDS (3-11-97)
- WATERSHED AREA IDENTIFICATION
 - AREA FROM DRAINAGE PLAN
 - RAINFALL INTENSITY, 50 YEAR STORM => PLATE NO. 2-14
 $I = \frac{B}{(C+D)^E}$ $50 \text{ } \epsilon = 0.90 \text{ } 100 \text{ } \epsilon = 0.825$
 $(C+D) \epsilon \Rightarrow B = 50 \Rightarrow B = 55$
 $D = 12.0 \Rightarrow D = 9.5$
 - TIME OF CONCENTRATION: $TC = T \text{ (OVERLAND)} + T \text{ (GUTTER)}$
 - RUNOFF COEFFICIENT => PLATE NO. 2-10 TABLE A
RESIDENTIAL AREA = 0.60
OPEN AREA = 0.48
 - $Q = C \times X \times I$

DROP INLETS

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd (CFS) FROM INLET #	CROWN O OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
3	7.360	0	0	7.360	19.267	0	2	I	SAG
4	4.530	0	0	4.530	19.267	0	2	I	SAG

FUTURE DROP INLETS (AS PER LA PUESTA DEL SOL UNIT THREE)

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd (CFS) FROM INLET #	CROWN O OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
1	13.656	0	3.656	10.00	19.267	0	2	I	SAG
2	4.620	3.656 (INLET #1)	0	8.276	17.749	0	2	III	SAG
3	4.610	0	0	4.610	5.836	0	2	I	ON GRADE

EXISTING DROP INLETS (AS PER LA PUESTA DEL SOL UNIT TWO)

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd (CFS) FROM INLET #	CROWN O OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
*1	13.388	1.902 FROM EX. INLET #1	0	15.290	17.695	0	4	I	ON GRADE
*2	17.193	0	1.902	15.291	17.695	0	4	I	ON GRADE
*5	8.620	4.720 FROM INLET #6	0	13.340	29.141	0	3	I	SAG
*6	18.060	0	0	13.340	29.141	4.720 TO INLET #5	3	I	SAG

* THE EXPECTED FLOWS FROM LA PUESTA DEL SOL UNIT TWO HAVE BEEN UPDATED TO SHOW PROPOSED CONDITIONS FOR LA PUESTA DEL SOL UNIT THREE AND FOUR. INLET NUMBERS, CAPACITY, NUMBER OF GRATES, TYPE AND LOCATION HAVE NOT CHANGED.

STREET CAPACITIES


Inlet #3	Width	cross slope	Depth	Area	P	R	n	S	Q	V	Total Q	Q actual	Actual Depth	spread width	Actual Velocity
16	2.00	0.32	2.56	16.3232	0.1568	0.013	0.0068	8.509	2.741		7.360		0.303	15.153	2.6437
32	0.00	0.18	5.76	32.36	0.1780	0.013	0.0068	17.180	2.983						

STREET CAPACITIES - FUTURE INLETS

Inlet #1	Width	cross slope	Depth	Area	P	R	n	S	Q	V	Total Q	Q actual	Actual Depth	spread width	Actual Velocity
16	2.00	0.32	2.56	16.3232	0.1568	0.013	0.009	9.789	3.154		10.000		0.323	16.129	3.1706
32	0.00	0.18	5.76	32.36	0.1780	0.013	0.009	19.765	3.431						



DRAINAGE PLAN
SCALE: 1" = 100'



REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN. ELEVATION = 3897.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3835.48 (CITY DATUM)

BY: _____ DATE: _____ REVISIONS: _____

ENGINEER'S SEAL

SCALE: 1" = 100'

Horizontal: N/A
Vertical: N/A
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APP'D. BY: J.L.A.
JOB NO.: 2000-210

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE

DRAINAGE PLAN


(SHEET 1 OF 2)

SHEET NO.

C4.1

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta del Sol Unit Four Improvements\C4.1 DRAINAGE PLAN.dwg, 7/9/2019 3:08:09 PM

S:\2003\2000-210-La Puesta del Sol Unit Three\DWG\Construction Drawings\La Puesta del Sol Unit Three\DWG\Construction Drawings\C4.1 DRAINAGE PLAN.dwg, 7/9/2019 3:05:52 PM



POND INFORMATION (ISELA RUBALCAVA)

AS PER ISELA RUBALCAVA DRIVE EXTENSION (CS: 0924-06-269, FEDERAL AID PROJECT: STP 2009 (419) MM, FILE NUMBER: 238513)

POND AREA #2
 TOTAL REQ. CAP. = 0.18 AC-FT
 AREA ADD. FROM LPU4 + LPU3(FUTURE) = 0.19 AC-FT
 TOTAL REQ. = 0.37 AC-FT
 TOTAL AVAILABLE CAP. = 3.64 AC-FT

INLET INFORMATION
 DROP INLET #1 = 12'-GRATE
 TOTAL REQ. FLOW CAP. = 5.56 CFS
 ADD. FLOW FROM LPU4 + LPU3(FUTURE) = 3.26 CFS
 TOTAL REQ. = 8.82 CFS
 TOTAL AVAILABLE FLOW CAP. = 19.72 CFS

UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY (915) 543-5720
 EL PASO ENERGY CORPORATION (915) 496-5244
 EL PASO WATER UTILITIES (915) 594-5500
 MCI SURVEILLANCE (800) MCI-WORK
 TIME WARNER COMMUNICATIONS (915) 772-1123
 TEXAS GAS SERVICE (915) 680-7200
 SBC (800) 545-6005
 AT&T (800) 852-3786
 U.S. SPRINT TELECOMM (800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
 FOR FIELD LOCATING EXISTING UTILITIES

LEGEND:

- DRAINAGE AREA BOUNDARY
- DRAINAGE FLOW
- ▲ HIGH POINT
- ▼ LOW POINT
- DROP INLET
- STORM SEWER MANHOLE (SD)
- RCP
- THRUST BLOCK STRUCTURE
- DRAINAGE AREA

STORM CALCULATIONS FOR WATERSHED AREAS

DRAINAGE AREA NO. (1)	DRAINAGE AREA (AC) (2)	DESIGN STORM INTENSITY (ISO) (3)	TIME OF CONCENTRATION (4)	RUNOFF COEFF. (C) (5)	Q50 (CFS) (6)	DESIGN STORM INTENSITY (1100) (3)	Q100 (CFS) (6)
DA-1	6.340	3.59	23.75	0.60	13.65	3.60	13.69
DA-2	4.057	3.76	22.00	0.60	9.15	3.77	9.18
DA-3	2.315	3.32	27.05	0.60	4.610	3.91	5.43
DA-4	8.962	3.36	26.64	0.60	18.06	3.37	18.12
DA-5	4.139	3.47	25.20	0.60	8.62	3.48	8.64
DA-6	2.210	3.42	25.80	0.60	4.53	3.43	4.54
DA-7	3.620	3.39	26.10	0.60	7.36	3.41	7.40
DA-8	2.220	3.50	24.60	0.60	4.62	3.53	4.70

STORM CALCULATIONS FOR WATERSHED AREAS WITH UNDEVELOPED RUNOFF COEFFICIENT

DRAINAGE AREA NO. (1)	DRAINAGE AREA (AC) (2)	DESIGN STORM INTENSITY (ISO) (3)	TIME OF CONCENTRATION (4)	RUNOFF COEFF. (C) (5)	Q50 (CFS) (6)	DESIGN STORM INTENSITY (1100) (3)	Q100 (CFS) (6)
**DA-1	6.340	3.32	24.10	0.48	10.10	3.57	10.88
**DA-3	2.315	3.82	21.40	0.48	4.245	3.83	4.256
**DA-9	2.210	3.81	21.50	0.48	4.04	3.82	4.05

- REFERENCE: CITY OF EL PASO SUBDIVISION STANDARDS (3-11-97)
- WATERSHED AREA IDENTIFICATION
 - AREA FROM DRAINAGE PLAN
 - RAINFALL INTENSITY, 50 YEAR STORM => PLATE NO. 2-14
 $I = \frac{B}{(T_c + D)^C} \times 50$ $E = \frac{0.900}{100} \times 100 = 0.925$
 $B = 12.0$ $C = 0.5$
 - TIME OF CONCENTRATION: $T_C = T$ (OVERLAND) + T (GUTTER)
 - RUNOFF COEFFICIENT => PLATE NO. 2-10 TABLE A
 RESIDENTIAL AREA = 0.60
 OPEN AREA = 0.48
 - $Q = C \times A \times I$

EXISTING MOMENTUM COMPUTATION

LOCATION @ INLET (1)	DEPTH (2)	VELOCITY (3)	PRODUCT NUMBER (4)
EX-1	0.402	3.120	1.254
EX-2	0.402	3.120	1.254
EX-3	0.303	2.643	0.801
EX-4	0.253	2.342	0.593
EX-5	0.377	3.101	1.169
EX-6	0.377	3.101	1.169

FUTURE MOMENTUM COMPUTATION

LOCATION @ INLET (1)	DEPTH (2)	VELOCITY (3)	PRODUCT NUMBER (4)
1	0.323	3.171	1.024
2	0.300	3.024	0.907
3	0.123	5.088	0.626

(1) LOCATION
 (2) DEPTH
 (3) VELOCITY
 (4) PRODUCT NUMBER = DEPTH X VELOCITY

EXISTING POND CALCULATIONS

QT = (ARC)/12
 QT = 6.371 AC-FT
 A = 32.452
 R = 4"
 Cw = 0.589
 QT X 25% = 1.593
 6.371 + 1.593 = 7.964

SILT VOLUME = 0.389
 0.012 AC-FT/AC
 7.964 + 0.389 = 8.354 AC-FT
TOTAL REQ = 8.354 AC-FT

LA PUESTA DEL SOL UNIT TWO STORM CALCULATIONS FOR WATERSHED AREAS

DRAINAGE AREA NO. (1)	DRAINAGE AREA (AC) (2)	DESIGN STORM INTENSITY (ISO) (3)	TIME OF CONCENTRATION (4)	RUNOFF COEFF. (C) (5)	Q50 (CFS) (6)
DA-1*	*6.312	3.535	24.48	0.60	13.888
DA-2*	*7.914	3.621	23.52	0.60	17.193

EXISTING POND

Basin No.	REQUIRED CAPACITY (AC.-FT.)	AVAILABLE CAPACITY (AC.-FT.)	PEAK INFLOW (CFS)	OUTLET TOWER FLOW (CFS)	HIGH WATER SURFACE ELEV. (FT.)	BOTTOM ELEVATION (FT.)	FREE BOARD (FT.)	TOP ELEVATION
1	8.354	11.546	76.050	0	3761.70	3753.00	2.30	3764.00

NOTE:
 THE HGL REFLECTS THE ELEVATION AS REQUIRED BY THE CITY OF EL PASO. THE HGL DOES NOT INCLUDE 25% FREEBOARD. HOWEVER, THE TOTAL POND CAPACITY SHALL HOLD TOTAL REQUIRED STORM WATER RUNOFF.
 HGL = QT
 HGL = 6.371 AC-FT
 CONTOUR 3760, ACCUMULATED VOLUME=6.265 AC-FT
 CONTOUR 3761, ACCUMULATED VOLUME=7.461 AC-FT
 HYDRAULIC GRADE LINE ELEVATION=3760.09

HWSE = QT+SILT VOLUME+25% EMERGENCY
 HWSE = 6.371+0.389+1.593=8.354 AC-FT
 CONTOUR 3762, ACCUMULATED VOLUME=8.738 AC-FT
 CONTOUR 3761, ACCUMULATED VOLUME=7.461 AC-FT
 HIGH WATER SURFACE ELEVATION=3761.70

* THE CAPACITY OF THE EXISTING POND HAS NOT BEEN CHANGED. THE REQUIRED CAPACITY AND RELATED CALCULATIONS HAVE BEEN UPDATED TO SHOW PROPOSED CONDITIONS FOR LA PUESTA DEL SOL UNIT THREE AND FOUR. POND CAPACITY AND CONTOURS ELEVATIONS HAVE NOT CHANGED.

DROP INLETS

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd. (CFS) FROM INLET #	CROWN Q OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL. FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
3	7.360	0	0	7.360	19.267	0	2	I	SAG
4	4.530	0	0	4.530	19.267	0	2	I	SAG

FUTURE DROP INLETS (AS PER LA PUESTA DEL SOL UNIT THREE)

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd. (CFS) FROM INLET #	CROWN Q OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL. FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
1	13.656	0	3.656	10.00	19.267	0	2	I	SAG
2	4.620	3.656 (INLET #1)	0	8.276	17.749	0	2	III	SAG
3	4.610	0	0	4.610	5.836	0	2	I	ON GRADE


EXISTING DROP INLETS (AS PER LA PUESTA DEL SOL UNIT TWO)

NO.	EXPECTED FLOW Qexp. (CFS)	ADDITIONAL FLOW Qadd. (CFS) FROM INLET #	CROWN Q OVERTOP (CFS)	Q REQUIRED Qactual (CFS)	AVAIL. FLOW CAPACITY Q AVAIL. (CFS)	FLOW BYPASS Qbyp (CFS) TO INLET #	# OF GRATES	TYPE OF INLET	INLET LOCATION
*1	13.388	1,902 FROM EX. INLET #1	0	15,290	17,695	0	4	I	ON GRADE
*2	17,193	0	1,902	15,291	17,695	0	4	I	ON GRADE
*5	8,620	4,720 FROM INLET #6	0	13,340	29,141	0	3	I	SAG
*6	18,060	0	0	13,340	29,141	4,720 TO INLET #5	3	I	SAG

* THE EXPECTED FLOWS FROM LA PUESTA DEL SOL UNIT TWO HAVE BEEN UPDATED TO SHOW PROPOSED CONDITIONS FOR LA PUESTA DEL SOL UNIT THREE AND FOUR. INLET NUMBERS, CAPACITY, NUMBER OF GRATES, TYPE AND LOCATION HAVE NOT CHANGED.



DRAINAGE PLAN
 SCALE: 1" = 150'



REFERENCES - BENCHMARKS
 CITY MONUMENT AT THE INTERSECTION OF PLASEO DEL NORTE & NORTHWESTERN. ELEVATION = 3867.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO". ELEVATION = 3835.48 (CITY DATUM)

BY: _____
 REVISIONS: _____
 DATE: _____

ENGINEER'S SEAL

 JORGE L. AZCARATE
 TEXAS REGISTERED ENGINEERING FIRM #464
 4712 Woodrow Bean St. El Paso, TX 79904
 915.544.5252 | www.oaegroup.net

SCALE: 1" = 150'
 Horizontal: N/A
 Vertical: N/A
 Contour Interval: 1/4'
 DATE: DECEMBER 2018
 DESIGN BY: C.J.G.
 DRAWN BY: M.R.G.
 CHKD. BY: J.L.A.
 APPVD. BY: J.L.A.
 JOB No. 2000-210


PROJECT TITLE
LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE
DRAINAGE PLAN
 (SHEET 2 OF 2)
 SHEET NO.
C4.2

GENERAL NOTES:

1. WHENEVER THE RETAINING HEIGHT OF A ROCKWALL/RETAINING WALL EXCEEDS FOUR (4) FEET OR MORE, THE DEVELOPER SHALL BUILD THE RETAINING PORTION OF THE WALL (INCLUDING NECESSARY REINFORCED CONCRETE FOOTING) TO HIGHEST FINISHED GROUND. THE BUILDER SHALL FINISH THE REMAINING OF THE STEM WALL. IF THE RETAINING HEIGHT DOES NOT EXCEED THE FOUR (4) FEET, THEN THE DEVELOPER SHALL CONSTRUCT A TEMPORARY SLOPE AT 3(H):1(V).

TRACT 1A
NELLIE D. MUNDY
SURVEY NO. 240
EL PASO COUNTY, TEXAS



UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 880-7200
SBC	(800) 545-6005
ATA&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579


WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN, ELEVATION = 3867.39 (CITY DATUM), THIS IS BASED ON NGS MONUMENT "CHINO"	ELEVATION = 3835.48 (CITY DATUM)
DATE	REVISIONS
BY	

CSA

TEXAS REGISTERED ENGINEERING FIRM #484
4712 Woodrow Bean, Ste F El Paso, TX 79904
915.544.5232 | www.csaeng.com



ENGINEER'S SEAL

SCALE: 1"=30'
Horizontal: 1"=5'
Vertical: 1"=5'
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPRD. BY: J.L.A.
JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR

SUBDIVISION IMPROVEMENTS

SHEET TITLE

GRADING SECTIONS

SHEET NO.


C5.1

S:\2000\2000-210-4a-Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C5.1-Grading Sections6-24-18.dwg, 7/9/2019 10:44:00 AM

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

LINE TABLE		
LINE	BEARING	LENGTH
L1	S00°00'41"W	15.85'




LEGEND
 WHEELCHAIR RAMP BY DEVELOPER (TYP.)
 PVI ELEVATIONS ARE SHOWN AT TOP OF CURB. REFER TO PLAN VIEW FOR TOP OF PAVEMENT ELEVATIONS.

DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
 CITY MONUMENT AT THE INTERSECTION OF PASEO DEL SOL AND WEST 15TH STREET BENCHMARK
 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
 ELEVATION = 3935.48 (CITY DATUM)

ENGINEER'S SEAL

 TEXAS REGISTERED ENGINEERING FIRM F-4684
 4712 Woodrow Bean Ste F El Paso, TX 79924
 915.544.5232 | www.caegroup.net



SCALE
 Horizontal: 1"=30'
 Vertical: 1"=5'
 Contour Interval: 1/4'
 DATE: DECEMBER 2018
 DESIGN BY: C.J.
 DRAWN BY: M.R.G.
 CHKD. BY: J.L.A.
 APPVD. BY: J.L.A.
 JOB No. 2000-210

PROJECT TITLE
 LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS

SHEET TITLE
 PLAYA TRONONES DRIVE
 PLAN & PROFILE FROM STA. 0+00.00 TO STA. 7+50.00

SHEET NO.

C6.1


S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C6.1-Playa Tronones Avenue P&P.dwg, 7/9/2018 11:30:37 AM

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3788
U.S. SPRINT TELECOMM	(800) 521-0579


WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASEO DEL SOL (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINA".
ELEVATION = 3935.48 (CITY DATUM)



Final Approval



ENGINEER'S SEAL
JAMES L. AZAROVITZ
REGISTERED PROFESSIONAL ENGINEER
NO. 13475
4712 Woodrow Bean Ste. F, El Paso, TX 79924
915.544.5232 | www.caegroup.net

SCALE
Horizontal: 1"=30'
Vertical: 1"=5'
Contour Interval: N/A
DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No.: 2000-210




PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**PLAYA TRONONES
PLAN & PROFILE FROM
STA. 7+50.00
TO STA. 8+27.83**


PLAYA TRONONES
PLAN & PROFILE FROM
STA. 0+00.00
TO STA. 5+00.00


SHEET NO.
C6.2


C6.2



LEGEND


 DIRECTIONAL WHEELCHAIR RAMP BY DEVELOPER (TYP.)

 PVI ELEVATIONS ARE SHOWN AT TOP OF CURB. REFER TO PLAN VIEW FOR TOP OF PAVEMENT ELEVATIONS.



S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta Ut Improvements\C6.2-C6.3-Ixtapa Drive P&P.dwg, 7/9/2019 11:31:30 AM

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\U4 Improvements\U4.2-06.3-ixtapa Drive P&P.dwg, 7/9/2019 11:35:13 AM



UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO WATER CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 860-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN ELEVATION = 3867.30 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"	ELEVATION = 3935.48 (CITY DATUM)
DATE	REVISIONS
BY	

DEVELOPER TO DEMOLISH AND PROPERLY DISPOSED OFF. RE-CONSTRUCT CURB GUTTER AND PAVEMENT IMPROVEMENTS.

LEGEND

DIRECTIONAL WHEELCHAIR RAMP BY DEVELOPER (TYP.)


PVI ELEVATIONS ARE SHOWN AT TOP OF CURB. REFER TO PLAN VIEW FOR TOP OF PAVEMENT ELEVATIONS.



TECHNICAL STAFF

ENGINEER'S SEAL

TEXAS REGISTERED ENGINEERING FIRM F-464
4712 Woodrow Bean St. El Paso, TX 79924
915.544.5232 | www.ceagroup.net



SCALE: 1"=30'

Horizontal: 1"=50'

Vertical: 1"=5'

Contour Interval: N/A

DATE: DECEMBER 2018

DESIGN BY: C.J.

DRAWN BY: M.R.G.

CHKD. BY: J.L.A.

APPVD. BY: J.L.A.

JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS


SHEET TITLE

IXTAPA STREET
PLAN & PROFILE
FROM STA. 5+00.00
TO STA. 9+04.69

SHEET NO.

C6.3

S:\2000\2000-210-La Puesta Del Sol Unit Improvements\Drawings\La Puesta Ul Improvements\C7.1-C7.2-Line A Storm P&S.dwg, 7/9/2019 1:30:22 PM




UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING I BEFORE YOU DIG CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

LINE TABLE

LINE	BEARING	LENGTH
L1	N89°59'14"W	20.74'
L2	N68°40'04"W	35.87'




STORM PIPE LINE A OUTPUT INFORMATION

PIPE	DOWNSTREAM INVERT ELEVATION (ft)	UPSTREAM INVERT ELEVATION (ft)	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)	Q(100) EXPECTED (cfs)	Q(100) CAPACITY (cfs)
A-1	3757.40	3757.70	3761.34	3762.09	626.637 CFS	729.708 CFS
A-2	3957.70	3960.35	3763.85	3764.62	600.528 CFS	906.548 CFS
A-3	3960.35	3963.00	3765.69	3767.27	600.773 CFS	906.548 CFS

STRUCTURE OUTPUT INFORMATION

STRUCTURE	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)
HEADWALL	3757.40	3757.40
JB-1	3762.09	3763.85
JB-2	3764.62	3765.69




REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASO DEL NORTE & NORTHWESTERN ELEVATION = 3877.30 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

ENGINEER'S SEAL

JARQUE L. AZCARRATE
TEXAS REGISTERED ENGINEERING FIRM #484
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.3532 | www.ceagroup.net



PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE

STORM SEWER PLAN & PROFILE LINE A FROM STA. 0+00.00 TO 6+00.00

SHEET NO.

C7.1

SCALE:
Horizontal: 1" = 30'
Vertical: 1" = 5'
Contour Interval: 1/4'

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.



JOB No.: 2000-210

STORM PIPE LINE A OUTPUT INFORMATION						
PIPE	DOWNSTREAM INVERT ELEVATION (ft)	UPSTREAM INVERT ELEVATION (ft)	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)	Q(50) EXPECTED (cfs)	Q(50) CAPACITY (cfs)
A-3	3960.35	3963.00	3765.69	3767.27	800.773 CFS	906.548 CFS
A-4	3963.00	3968.15	3768.77	3772.37	589.165 CFS	1394.54 CFS
A-5	3968.15	3971.49±	3774.47	3776.67	568.000 CFS	699.833 CFS

STRUCTURE OUTPUT INFORMATION		
STRUCTURE	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)
JB-3	3767.27	3768.77
JB-4	3772.37	3774.47


UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES




DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASO DEL SOL AND TRONONES DRIVE (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)



SCALE: Horizontal: 1"=50'
Vertical: 1"=5'
Contour Interval: N/A
DATE: DECEMBER 2018
DESIGN BY: C.J.L.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPROV. BY: J.L.A.
JOB No. 2000-210



PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**STORM SEWER PLAN
& PROFILE LINE A
FROM STA. 6+00.00
TO STA. 12+99.51**

SHEET NO.
C7.2

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C7.1-C7.2-Line A Storm P&P.dwg, 7/9/2019 1:28:03 PM

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C7.3-Line B & C Storm P&P.dwg, 7/9/2019 2:20:26 PM




UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 860-7200
SBC	(800) 545-0005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

STORM PIPE LINE B AND C OUTPUT INFORMATION						
PIPE	DOWNSTREAM INVERT ELEVATION (ft)	UPSTREAM INVERT ELEVATION (ft)	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)	Q(50) EXPECTED (cfs)	Q(50) CAPACITY (cfs)
B-1	3763.00	3764.50	3768.77	3768.88	11,969 CFS	43,174 CFS
B-2	3766.55	3766.78	3768.95	3768.98	4,530 CFS	12,594 CFS
B-3	3764.50	3765.40	3768.95	3769.03	7,360 CFS	24,912 CFS
C-1	3757.70	3760.25±	3767.27	3768.95	11,969 CFS	43,174 CFS

STRUCTURE OUTPUT INFORMATION		
STRUCTURE	HYDRAULIC GRADE DOWNSTREAM (ft)	HYDRAULIC GRADE UPSTREAM (ft)
SD-1	3768.88	3768.95
INLET 3	3769.03	3769.16
INLET 4	3768.98	3769.03


LINE TABLE		
LINE	BEARING	LENGTH
L1	N90°00'00"W	16.00'
L2	S89°52'13"E	16.00'



REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PLASEO DEL NORTE & NORTHWESTERN ELEVATION = 3872.90 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
ELEVATION = 3835.48 (CITY DATUM)

DATE: _____ REVISIONS: _____ BY: _____

ENGINEER'S SEAL
Jorge L. Azcarate
Professional Engineer
No. 18075
Texas Registered Engineering Firm F-4684
4712 Woodrow Bean St. El Paso, TX 79904
915.544.5232 | www.ceagroup.net



SCALE: Horizontal: 1"=30' Vertical: 1"=5'
Contour Interval: 1V/4'

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPD. BY: J.L.A.
JOB No. 2000-210

PROJECT TITLE
LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE
STORM SEWER PLAN & PROFILE LINE B FROM STA. 0+00.00 TO 1+35.37
STORM SEWER PLAN & PROFILE LINE C FROM STA. 0+00.00 TO 0+57.24

SHEET NO.
C7.3


NOTE:
FOR LOTS 43-57, BLOCK 17, LOTS 1-3, BLOCK 22
(FUTURE LA PUERTA DEL SOL UNIT THREE), AN 8"
STEEL CASING SHALL BE INSTALLED AT SEWER
SERVICE LINE UNDERNEATH THE CULVERT.

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3788
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASO DEL
CITY MONUMENT (CITY DATUM). THIS IS BASED ON MONUMENT
"CHNO"
ELEVATION = 3935.48 (CITY DATUM)









SCALE
Horizontal: 1"=5'
Vertical: 1"=5'
Contour Interval: N/A
DATE: DECEMBER 2018
DESIGN BY: C.J.L.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPRD. BY: J.L.A.
JOB No.: 2000-210

PROJECT TITLE
**LA PUERTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**UTILITY CROSSING
(SEWER)**
(SHEET 1 OF 3)
SHEET NO.



C7.4



S:\2000\2000-210-La Puerta Del Sol Unit Three\DWG3\Civil\Design Drawings\StormSewerCrossings.dwg, 7/9/2019 11:06:07 AM


UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
 FOR FIELD LOCATING EXISTING UTILITIES

NOTE:
 FOR LOTS 43-57, BLOCK 17, LOTS 1-3, BLOCK 22 (FUTURE LA PUESTA DEL SOL UNIT THREE), AN 8" STEEL CASING SHALL BE INSTALLED AT SEWER SERVICE LINE UNDERNEATH THE CULVERT.

DATE	REVISIONS	BY


REFERENCES - BENCHMARKS
 CITY MONUMENT AT THE INTERSECTION OF PASO DEL SOL AND WESTERN AVENUE
 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
 ELEVATION = 3935.48 (CITY DATUM)









SCALE
 Horizontal: 1"=5'
 Vertical: 1"=5'
 Contour Interval: N/A
 DATE: DECEMBER 2018
 DESIGN BY: C.J.
 DRAWN BY: M.R.G.
 CHKD. BY: J.L.A.
 APPVD. BY: J.L.A.
 JOB No.: 2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS**

SHEET TITLE
UTILITY CROSSING (SEWER)
 (SHEET 2 OF 3)
 SHEET NO.



C7.5



S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Civil\Design\StormSewerCrossings.dwg, 7/9/2019 11:11:00 AM

UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY (915) 543-5720
 EL PASO ENERGY CORPORATION (915) 496-5244
 EL PASO WATER UTILITIES (915) 594-5500
 MCI SURVEILLANCE (800) MCI-WORK
 TIME WARNER COMMUNICATIONS (915) 772-1123
 TEXAS GAS SERVICE (915) 680-7200
 SSC (800) 545-0005
 AT&T (800) 852-3786
 U.S. SPRINT TELECOMM (800) 521-0579


WARNING!
BEFORE YOU DIG
CALL 811
 FOR FIELD LOCATING EXISTING UTILITIES

NOTE:
 FOR LOTS 43-57, BLOCK 17, LOTS 1-3, BLOCK 22 (FUTURE LA PUESTA DEL SOL UNIT THREE), AN 8" STEEL CASING SHALL BE INSTALLED AT SEWER SERVICE LINE UNDERNEATH THE CULVERT.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASCO DEL NORTE & NORTHWESTERN ELEVATION = 3687.30	BY
"CHINO" ELEVATION = 3895.48 (CITY DATUM)	REVISIONS
DATE	

ca
 CIVIL ENGINEERS
 TEXAS REGISTERED ENGINEERING FIRM #4684
 4712 Woodrow Bean St. El Paso, TX 79924
 915.544.5232 | www.caegroup.net



SCALE
 Horizontal: 1" = 5'
 Vertical: 1" = 5'
 Contour Interval: N/A
 DATE: DECEMBER 2018
 DESIGN BY: C.J.G.
 DRAWN BY: M.R.G.
 CHKD. BY: J.L.A.
 APPVD. BY: J.L.A.
 JOB No. 2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS**



SHEET TITLE

UTILITY CROSSING (SEWER)


(SHEET 3 OF 3)

SHEET NO.


C7.6




S:\2000\2000-210-La Puesta del Sol Unit Three\DWG\Civil\Design Drawings\StormSewerCrossings.dwg, 7/9/2019 11:11:32 AM



PLAN



PLAN




SECTION


SIDEWALK NOTES:

1. CONCRETE SIDEWALK SHALL BE 3,000 P.S.I.
2. DUMMY JOINTS REQUIRED AT 5' O.C.
3. EXPANSION JOINTS SHALL BE AT 20' O.C. MAXIMUM. USE 1/2" PREMOLDED BITUMINOUS EXPANSION JOINTS (AASHTO M-33). EXPANSION JOINT FILLER SHALL BE PLACED WHEREVER SIDEWALK ABUTS ROCK OR MASONRY STRUCTURES SUCH AS CURBS OR BUILDINGS.
4. EXPANSION JOINT FILLER SHALL BE PLACED WHEREVER SIDEWALK ABUTS ROCK OR MASONRY STRUCTURES SUCH AS CURBS OR BUILDINGS.
5. SUBGRADE TO BE COMPACTED TO 95% ASTM D1557.

2 SECTION-SIDEWALK/SLAB
SCALE: N.T.S.



DRIVEWAY PLAN




SECTION AT CENTERLINE

3 TYPICAL DRIVEWAY DETAIL
SCALE: N.T.S.

NOTES:

1. DRIVEWAY SLOPES MUST BE 10% MAX. FROM GUTTER FOR FIRST 12 FEET AND 14% MAX. THEREAFTER (DRIVEWAY SHALL BE LOCATED @ HIGH SIDE OF LOT UNLESS OTHERWISE COORDINATED WITH CITY OF EL PASO)
2. RESIDENTIAL
6" CONCRETE WITHOUT W.W.F.
4" CONCRETE WITH 6X6-10/10
3. COMMERCIAL
6" CONCRETE WITH 6X6-6/6 W.W.F.




A SECTION

NOTES:

1. CONCRETE SHALL BE 3,000 P.S.I. MIN.
2. DUMMY JOINT REQUIRED AT 10' O.C. FOR CURB & GUTTER, AND 5' O.C. FOR SIDEWALK
3. EXPANSION MATERIAL REQUIRED AT CURB RETURNS AND AT 20' ON CENTER FOR SIDEWALKS WITH 1/2" PREMOLDED ASPHALT IMPREGNATED EXPANSION MATERIAL OR EQUAL.
4. EXPANSION JOINTS REQUIRED AT 50' O.C. WHEN FORMING FOR CURBS.


1 CURB & GUTTER DETAIL
SCALE: 1" = 1'-0"




NOTES:

1. CONCRETE TO BE 3000 PSI MIN.
2. DUMMY JOINTS REQUIRED AT 10' O.C. FOR HEADERS AND 5' O.C. FOR SIDEWALK.
3. EXPANSION MATERIAL REQUIRED AT CURB RETURNS WITH 1/2" PREMOLDED ASPHALT IMPREGNATED EXPANSION MATERIAL OR EQUAL.
4. EXPANSION JOINTS REQUIRED AT 50' O.C. WHEN FORMING FOR HEADERS.
5. EXPANSION JOINTS REQUIRED FOR SIDEWALK AT 20' O.C.
6. * FOR CUL-DE-SAC AND HEEL ONLY.

4 4" CONCRETE ROLLED CURB DETAIL
SCALE: 1" = 1'-0"




5 TYPICAL PAVEMENT JOINT SECTION
SCALE: N.T.S.




NOTE:

TERMINUS MUST BE CONSTRUCTED IN 4" LIFTS. FINAL LIFT MUST BE PLACED WITH FINAL PAVEMENT COURSE.

6 TERMINUS OF STREET
SCALE: 1" = 1'-0"




PLAN



A SECTION


NOTE: EXPANSION MATERIAL SHALL BE 1/2" PREMOLDED ASPHALT IMPREGNATED EXPANSION MATERIAL OR EQUAL.

7 HEEL (70' R) DRIVEWAY DETAIL
SCALE: N.T.S.



8 TYPICAL HEEL/CUL-DE-SAC SIDEWALK TRANSITION
SCALE: N.T.S.

REFERENCES - BENCHMARKS	
CITY MONUMENT AT THE INTERSECTION OF BASED DEL NORTE & NORTHWESTERN ELEVATION = 3897.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"	
ELEVATION = 3895.48 (CITY DATUM)	
DATE	REVISIONS
	BY



SCALE	N/A
Horizontal	N/A
Vertical	N/A
Contour Interval	N/A
DATE	DECEMBER 2018
DESIGN BY	C.J.
DRAWN BY	M.R.G.
CHKD. BY	J.L.A.
APPVD. BY	J.L.A.
JOB No.	2000-210


PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
STANDARD DETAILS
(SHEET 1 OF 2)
SHEET NO.



C8.1

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C8.1-C8.2-Standard Details.dwg, 7/9/2018 10:22:50 AM



1 TRUNCATED DOME SIZE AND SPACING
SCALE: N.T.S.


DOMES SIZE AND SPACING. TRUNCATED DOMES SHALL HAVE A DIAMETER OF NOMINAL 0.9 INCHES (23 mm) AT THE BOTTOM, A DIAMETER OF 0.4 INCH (10 mm) AT THE TOP, A HEIGHT OF NOMINAL 0.2 INCHES (5 mm), AND A CENTER-TO-CENTER SPACING OF NOMINAL 2.35 INCHES (60 mm) MEASURED ALONG ONE SIDE OF A SQUARE ARRANGEMENT.

DOMES ALIGNMENT. DOMES SHALL BE ALIGNED ON A SQUARE GRID IN THE PREDOMINANT DIRECTION OF TRAVEL TO PERMIT WHEELS TO ROLL BETWEEN DOMES. DETECTABLE WARNING SURFACES SHALL EXTEND 24 INCHES (610 mm) MINIMUM IN THE DIRECTION OF TRAVEL AND THE FULL WIDTH OF THE CURB RAMP, LANDING, OR BLENDED TRANSITION.

CONTRAST. THERE SHALL BE A MINIMUM OF 70 PERCENT CONTRAST IN LIGHT REFLECTANCE BETWEEN THE DETECTABLE WARNING AND AN ADJOINING SURFACE, OR THE DETECTABLE WARNING SHALL BE "RED BRICK" COLOR, UNLESS OTHERWISE DIRECTED BY THE OWNER. THE MATERIAL USED TO PROVIDE VISUAL CONTRAST SHALL BE AN INTEGRAL PART OF THE DETECTABLE WARNING SURFACE. CONTRAST SHALL BE PROVIDED BY PLACING AND MIXING TINT IN THE PLASTIC CONCRETE USED FOR THE DETECTABLE WARNING SURFACE. NO PAINTING OF SURFACE SHALL BE PERMITTED.


TRUNCATED DOME TILES, ADA CERTIFIED "ARMOR-TILE" TACTILE SYSTEMS OR APPROVED EQUAL.

- LEGEND**
- DETECTABLE WARNING SURFACE SHALL CONSIST OF RAISED TRUNCATED DOMES WITH A NOMINAL DIAMETER OF 0.9 IN., A NOMINAL HEIGHT OF 0.2 IN AND A CENTER TO CENTER NOMINAL SPACING OF 2.35 IN., AND SHALL NOT BE STAGGERED. THE SURFACE SHALL HAVE A COLOR CONTRAST VISUALLY WITH ADJOINING SURFACES.
- GENERAL NOTES:**
- ALL SLOPES ARE MAXIMUM ALLOWABLE. THE LEAST POSSIBLE SLOPE THAT WILL STILL DRAIN PROPERLY SHOULD BE USED. RAMP LENGTH OR GRADE OF APPROACH SIDEWALKS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.
 - THE MINIMUM SIDEWALK WIDTH IS 5'. WHERE A 5' SIDEWALK CAN NOT BE PROVIDED DUE TO SITE CONSTRAINTS, A MINIMUM 3' SIDEWALK WITH 5' X 5' PASSING AREAS AT INTERVALS NOT TO EXCEED 200 FT IS REQUIRED.
 - LANDINGS SHALL BE 5' X 5' MINIMUM WITH A MAXIMUM 2% SLOPE IN ANY DIRECTION.
 - MANEUVERING SPACE AT THE BOTTOM OF CURB RAMP SHALL BE A MINIMUM OF 4' X 4' WHOLLY CONTAINED WITHIN THE CROSSWALK AND WHOLLY OUTSIDE THE PARALLEL VEHICULAR TRAVEL PATH.
 - CURB RAMP WITH RETURNED CURBS MAY BE USED ONLY WHERE PEDESTRIANS WOULD NOT NORMALLY WALK ACROSS THE RAMP. OTHERWISE, FLARED SIDES SHALL BE PROVIDED.
 - ALL CONCRETE SIDEWALK SURFACES SHALL RECEIVE A LIGHT BROOM FINISH UNLESS NOTED OTHERWISE IN THE PLANS.
 - RAMP TEXTURES MUST CONSIST OF TRUNCATED DOME SURFACES. TEXTURES ARE REQUIRED TO BE DETECTABLE UNDERFOOT. SURFACES THAT WOULD ALLOW WATER TO ACCUMULATE ARE PROHIBITED. REFER TO TRUNCATED DOME DETAIL.
 - CROSSWALK DIMENSIONS, CROSSWALK MARKINGS AND STOP BAR LOCATIONS SHALL BE AS SHOWN ELSEWHERE IN THE PLANS. AT INTERSECTIONS WHERE CROSSWALK MARKINGS ARE NOT REQUIRED, RAMP SHALL BE ALIGNED WITH THEORETICAL CROSSWALKS, OR AS DIRECTED BY THE ENGINEER.
 - MAXIMUM ALLOWABLE CROSS SLOPE ON SIDEWALK AND RAMP SURFACES IS 2%.
 - ADDITIONAL INFORMATION ON CURB RAMP LOCATION, DESIGN, LIGHT REFLECTIVE VALUE AND TEXTURE MAY BE FOUND IN THE CURRENT EDITION OF THE TEXAS ACCESSIBILITY STANDARDS (TAS) PREPARED AND ADMINISTERED BY THE TEXAS DEPARTMENT OF LICENSING AND REGULATION (TDLR).




2 TYPICAL DIRECTIONAL RAMP @ INTERSECTION
SCALE: 1"=10'


- NOTES:**
- RAMPS MAY BE PLACED AS SUGGESTED, HOWEVER EXISTING LIGHT POLES, FIREHYDRANTS, DROP INLETS, ETC., MAY AFFECT PLACEMENT.
 - THE CONCRETE SURFACE SHALL HAVE A ROUGH, NONSKID TYPE FINISH.
 - CONSTRUCTION METHODS SHALL CONFORM WITH THE CITY OF EL PASO SPECIFICATIONS.
 - ALL PARKING AND PAVEMENT MARKINGS SHALL BE IN ACCORDANCE WITH CURRENT CITY OF EL PASO STANDARDS.




- ROCK WALL NOTES**
- STONE FOR ROCKWALL SHALL BE AS NEARLY UNIFORM IN SECTIONS AS IN PRACTICABLE THE STONE SHALL BE DENSE AND RESISTANT OF AIR AND WATER.
 - MORTAR MUST BE TYPE "S" 1800 P.S.I. AS PER ASTM C270.
 - MASONRY WALL OVER SIX (6) FEET IN HEIGHT AND THOSE USED FOR EARTH RETENTION OVER TWO (2) FEET MUST BE DESIGNED AS STRUCTURAL WALLS.
 - WALLS ADJACENT TO PONDING AREAS OR DRAINAGE DITCHES MAY BE CONSTRUCTED OF BRICK, ROCK, STONE, OR CONCRETE BLOCK AND SHALL NOT BE LESS THAN SIX (6) FEET HIGH.
 - ROCKWALL MORTAR JOINTS MUST NOT EXCEED TWO (2) INCHES.
 - PROVIDE ONE (1) INCH EXPANSION JOINTS AT EVERY 100 FEET.
 - ALL STONE SHALL BE THOROUGHLY SOAKED BEFORE BEING PLACED.
 - ALL STONE FOR ROCKWALLS SHALL BE FRACTURED QUARRIED ROCK OR ROUND ROCK, NO RIVER ROCK SHALL BE ALLOWED.
 - REINFORCING STEEL SHALL BE ASTM A615 GRADE 40.
 - ALLOWABLE SOIL BEARING PRESSURE = 2,500 PSI (MINIMUM).
 - BACKFILL MATERIALS SHALL CONSIST OF COARSE GRAINED, WELL-DRAINED SOILS (WITH NO CLAY CONTENT).



3 TYPICAL ROCKWALL DETAILS
SCALE: 1" = 2'-0"




4 TYPICAL 50' ROW STREET SECTION DETAIL
SCALE: N.T.S.




5 TYPICAL 52' ROW STREET SECTIONS DETAIL
SCALE: N.T.S.


- STREETS NOTES:**
- (*) STREET TRANSVERSE SLOPE AS SHOWN IN PLANS.
 - SIDEWALK WIDTH IS REQUIRED TO COMPLY WITH ADA/TAS REGULATIONS.
 - STREET IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH CURRENT CITY OF EL PASO PAVING CONSTRUCTION DETAILS AND STANDARD SPECIFICATIONS. CBR @ EVERY 500' RESULTS TO BE SUBMITTED TO THE CITY OF EL PASO FOR REVIEW AND APPROVAL PRIOR TO PLACEMENT OF PAVEMENT.




BRONZE MONUMENT CAP




B SECTION




COVER



6 CITY SURVEY MONUMENT DETAILS
SCALE: N.T.S.





MONUMENT BOX



SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN ELEVATION = 5887.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"	DATE	REVISIONS	BY
ELEVATION = 3935.48 (CITY DATUM)			



SCALE

Horizontal:	N/A
Vertical:	N/A
Contour Interval:	N/A
DATE:	DECEMBER 2018
DESIGN BY:	C.J.
DRAWN BY:	M.R.G.
CHKD. BY:	J.L.A.
APPVD. BY:	J.L.A.
JOB No.:	2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**STANDARD
DETAILS**

(SHEET 2 OF 2)
SHEET NO.



C8.2

S:\2000\2000-210-La Puente del Sol Unit Three\DWG\Construction Drawings\La Puente 04 Improvements\C9.1-Drainage Details-6-24-19.dwg, 7/9/2019 10:25:34 AM

NO. GRATES	CAPACITY	"L"	BEAM LENGTH	BEAM (MIN. SIZES)
2	19.83 CFS	5'-1 1/8"	4'-7 1/8"	W6x12, S8x12.5, MC6x15.1
3	29.69 CFS	7'-0 1/4"	6'-5 1/8"	W8x15, S7x15.3, MC7x17.6
4	39.10 CFS	8'-9 7/8"	8'-3 7/8"	W9x18, S8x18.4, MC10x21.9
5	48.72 CFS	10'-8"	10'-2"	W12x16, S8x21, MC10x21.9


* THESE CAPACITIES CORRESPOND TO A CLOGGING FACTOR OF 0.5

- NOTES:**
- GRATES TO BE PERPENDICULAR TO TRAFFIC
 - CONCRETE TO BE 3,000 PSI (MIN.) CORE TEST @ 28 DAYS.
 - H=20' MAXIMUM
 - SEE STORM SEWER PLAN & PROFILES FOR APPROVED PIPE DIAMETER.



- NOTES:**
- EXCAVATION PIPE TRENCHES SHALL BE EXCAVATED TO THE LINES AND GRADES SHOWN IN THE PLANS. WHEN ROCK OR OTHER UNYIELDING FOUNDATION MATERIAL IS ENCOUNTERED, IT SHALL BE REMOVED TO A DEPTH OF O.D./12 OR 6", WHICHEVER IS GREATER AND REPLACED WITH APPROVED MATERIAL AND COMPACTED TO AT LEAST THE STANDARD PROCTOR DENSITY SPECIFIED FOR THE BEDDING MATERIAL.
 - FOUNDATION THE FOUNDATION SHALL BE MODERATELY FIRM TO HARD SOIL, STABILIZED SOIL OR COMPACTED FILL MATERIAL. WHEN UNSUITABLE OR UNSTABLE MATERIAL IS ENCOUNTERED, THE FOUNDATION SHALL BE STABILIZED.
 - BEDDING THE BEDDING SHALL BE CONSTRUCTED UNIFORMLY OVER THE FULL LENGTH OF THE PIPE BY EXERTING FORCE ON THE BARREL TO DISTRIBUTE THE LOAD-BEARING REACTION UNIFORMLY ON THE PIPE BARREL OVER ITS FULL LENGTH AND TO MAINTAIN THE REQUIRED PIPE GRADE. IF PLACED IN LAYERS, THE THICKNESS OF THE LAYERS SHALL BE REQUIRED TO ACHIEVE THE SPECIFIED COMPACTION. IF THE PIPE BEING INSTALLED HAS A PROJECTING BELL, BELL HOLES SHALL BE PLACED TO BE AS UNIFORM AS POSSIBLE. THE MAXIMUM AGGREGATE SIZE SHALL BE 1-INCH WHEN THE BEDDING THICKNESS IS LESS THAN 6-INCHES AND 1 1/2" WHEN THE BEDDING IS 6-INCH OR GREATER.
 - PIPE LAYING PIPE SHALL BE INSTALLED TO THE LINE AND GRADE AS SHOWN ON THE PLANS. THE JOINT SHALL BE INSTALLED AS PER MANUFACTURER'S RECOMMENDATIONS. UNLESS APPROVED BY THE DESIGN ENGINEER, PIPE LAYING SHALL START AT THE LOWEST END OF THE PIPE LINE AND PIPE LAD WITH THE BELL END UPRIGHT. THE BEDDING GRADE UNDER THE MIDDLE THIRD OF THE PIPE OUTSIDE DIAMETER SHALL BE PREPARED BEFORE LAYING THE PIPE SECTION MAKING ADJUSTMENTS IN GRADE BY EXERTING FORCE ON THE BARREL OF THE PIPE WITH EXCAVATING EQUIPMENT. BY LIFTING AND DROPPING THE PIPE, OR BY LIFTING AND PACKING THE BEDDING MATERIAL UNDER IT SHALL BE PROHIBITED. IF THE INSTALLED PIPE SECTION IS NOT ON GRADE, THE PIPE SECTION SHALL BE COMPLETELY UNJOINED, THE GRADE CORRECTED, AND THE PIPE THEN REJOINED.
 - BEFORE ASSEMBLING THE PIPE JOINT, CLEAN ALL DIRT AND FOREIGN SUBSTANCE FROM THE BELL & SPIGOT OR TONGUE & GROOVE ENDS OF THE PIPE, FOR TONGUE & GROOVE JOINTS, PLACE THE PREFORMED FLEXIBLE JOINT SEALANT MATERIAL AROUND THE TOP HALF OF THE SPIGOT AND THE BOTTOM HALF OF THE BELL.
 - BACKFILLING ALL TRENCHES SHALL BE BACKFILLED AS PER PROJECT REQUIREMENTS. THE HAUNCH SHALL BE CONSTRUCTED USING THE SPECIFIED SOIL TYPE AND COMPACTION LEVEL. REQUIRED FOR THE DESIGNATED INSTALLATION. THE BACKFILL SHALL BE PLACED IN LAYERS. THE THICKNESS OF THE LAYERS SHALL BE 8-INCH LIFTS AD COMPACTED TO THE SPECIFIED REQUIREMENTS. THE BACKFILL SHALL BE MATERIAL CONFORMING TO THE PROJECT PLAN SAND CONTAINING NO DEBRIS, ORGANIC MATTER OR FROZEN MATERIAL.
 - MINIMUM COVER FOR CONSTRUCTION LOADS. IF PASSAGE OF CONSTRUCTION EQUIPMENT OVER AN INSTALLED PIPELINE IS NECESSARY DURING PROJECT CONSTRUCTION, COMPACTED OVERFILL IN THE FORM OF A RAMP SHALL BE CONSTRUCTED TO A MINIMUM ELEVATION OF 3- FEET OVER THE TOP OF THE PIPE OR TO A HEIGHT SUCH THAT THE EQUIPMENT LOADS ON THE PIPE DO NOT EXCEED THE PIPE DESIGN STRENGTH.
 - HORIZONTAL AND VERTICAL ALIGNMENTS THE HORIZONTAL ALIGNMENT OF THE FACILITIES WILL BE ALLOWED IF THE CENTER OF 36-INCH AND SMALLER DIAMETER PIPES SHALL NOT BE MORE THAN 6-INCHES OFF THE DESIGNATED ALIGNMENT. IN ADDITION FOR PIPE GREATER THAN 36-INCH DIAMETER, THE CENTER LINE SHALL NOT BE MORE THAN 2-INCHES PER 12-INCH OF DIAMETER FROM THE DESIGNATED ALIGNMENT. PIPELINE ALIGNMENT SHALL BE STRAIGHT FROM MANHOLE TO MANHOLE WITH A LINE OF SIGHT THROUGH THE PIPE SHALL EXIST. THE VERTICAL ALIGNMENT SHALL NOT DEVIATE FROM THE DESIGNATED GRADE BY AN AMOUNT GREATER THAN THE TOTAL OF 1/4 INCH PLUS 1 INCH PER YARD OF DIAMETER OF SEWER PIPE. NO VARIANCE FROM GRADE, VERTICALLY OR HORIZONTALLY, SHALL BE PERMITTED THAT RESULTS IN INDIVIDUAL JOINT DEFLECTIONS IN EXCESS OF MANUFACTURER'S RECOMMENDATIONS.

2 STORM SEWER BEDDING DETAIL
SCALE: N.T.S.




3 CONCRETE CHANNEL TYPE I DETAIL
SCALE: N.T.S.

- DROP INLET GENERAL NOTES:**
- WELDED STEEL OR CAST GRATES AS DETAILED ARE ALL ACCEPTABLE GRATES. MIXING OF ALTERNATE TYPES OF GRATES ON THE SAME PROJECT WILL BE PERMITTED WITH THE APPROVAL OF THE CITY ENGINEER.
 - ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE CURRENT STANDARD SPECIFICATIONS.
 - SHARP EDGES RESULTING FROM FABRICATION SHALL BE DULLED BY ANY ACCEPTABLE METHOD FOR SAFETY IN HANDLING.
 - GRATES SHALL BE INSTALLED IN FRAME WITH FLOW ARROW POINTING DOWNSTREAM OR TOWARD THE LOW POINT IN A SUMP.
 - WELDED GRATES SHALL BE STRUCTURAL STEEL CONFORMING TO THE REQUIREMENTS OF AASHTO M-183 OR OF CORROSION RESISTANT STRUCTURAL STEEL CONFORMING TO THE REQUIREMENTS OF AASHTO M-181 OR M-222 OR BE MADE OF OTHER APPROVED STEELS OF EQUAL QUALITY. MIXING GRADES OF STEEL ON THE SAME GRADE WILL NOT BE PERMITTED. GRATES MADE OF M-183 STEEL SHALL BE GALVANIZED IN ACCORDANCE WITH AASHTO M-111 SPECIFICATIONS OR SHALL BE PAINTED WITH INORGANIC ZINC PAINTS, MEETING THE REQUIREMENTS OF CURRENT STANDARD SPECIFICATIONS.
 - ALL WELDS SHALL HAVE A MINIMUM OF 1/4" FILLET AND SHALL CONFORM TO THE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION AND TO THE AWS STRUCTURAL WELDING CODE.


- ELECTRODES SHALL BE COMPATIBLE TO THE DIFFERENT GRADES OF STEEL THAT COMPRISE THE GRATE MEMBERS.
- CAST GRATES SHALL BE CAST STEEL CONFORMING TO THE REQUIREMENTS OF AASHTO M-103, GRADE 65-35 OR OF DUCTILE IRON CONFORMING TO THE REQUIREMENTS OF ASTM A-536 SPECIAL GRADE 60-45, OR OF GRAY IRON CONFORMING TO THE REQUIREMENTS OF AASHTO M-105, CLASS 35B OR ASTM A-48 CLASS 35B. THE SPECIFICATIONS OF GENERAL APPLICATION FOR CAST STEEL GRATES SHALL BE AASHTO M-103 SCOPE 1.2.1, GRADE N-1.
- FERROUS CASTINGS SHALL BE OF UNIFORM QUALITY, FREE OF BLOWHOLES, POROSITY, HARD SPOTS, SHRINKAGE DISTORTION OR OTHER DEFECTS. THEY SHALL BE SMOOTH AND WELL CLEANED BY SHOT BLASTING OR OTHER APPROVED CLEANING METHOD. AFTER CLEANING THEY SHALL BE COATED WITH ASPHALT BASE PAINT RESULTING IN A SMOOTH COATING, TOUGH AND TENACIOUS WHEN COLD, NOT TACKY OR BRITTLE.
- ALL CASTING SHALL BE MANUFACTURED TRUE TO PATTERN. COMPONENT PARTS SHALL FIT TOGETHER IN A SATISFACTORY MANNER.
- ALL CONCRETE TO BE 3000 P.S.I. CHAMFER ALL EXPOSED EDGES 3/4". ALL DIMENSIONS RELATING TO REINFORCING STEEL ARE TO CENTER OF BARS.
- MINIMUM CONCRETE COVER SHALL BE 1 1/2" FOR STEEL REINFORCING.

- EXPANSION MATERIAL TO BE 1/2" BITUMINOUS FIBER AND PLACED WHERE PROPOSED CONCRETE COMES IN CONTACT WITH ANY EXISTING OR PROPOSED CONCRETE OR MASONRY STRUCTURE.
- STRUCTURAL STEEL SHALL BE SHOP PAINTED IN ACCORDANCE WITH T&D. ITEM 446 "PAINT AND PAINTING"
- SURFACE OF ALL EXPOSED CONCRETE SHALL CONFORM IN LINE AND GRADE TO EXISTING OR PROPOSED CURB AND WALK ADJACENT TO INLETS.
- GRATES WILL BE DERESSED 1" BELOW PROPOSED OR EXISTING GRADE.
- ALL REINFORCING BARS TO BE #6 BARS AT 8" O.C. GRADE 60. BEND BARS AROUND PIPE OPENINGS.
- INLETS TO BE DESIGNATED IN PLANS BY NUMBER OF GRATES REQUIRED.
- LOCATION OF SEWER PIPES SHOWN ELSEWHERE IN PLANS.
- TWO 3/8"x4" LONG CONCRETE ANCHOR STUDS REQUIRED FOR EACH SIDE OF FRAME, WHERE RESTING ON CONCRETE, USE NELSON STUDS OR EQUAL.
- THE GRATES OF ALL INLETS WITHIN THE STREET PAVEMENT MUST BE CONSTRUCTED WITH THE GRATE BARS PERPENDICULAR TO THE CURB.

1 DROP INLET (TYPE I) DETAILS
SCALE: 1" = 2'-0"




4 MODIFIED CAST-IN PLACE JUNCTION MANHOLE DETAIL
SCALE: N.T.S.



- NOTE:**
- ALL CONCRETE SHALL HAVE 4000 PSI MIN. @ 28 DAYS.
 - STRUCTURE TO BE CONSTRUCTED AS PER H20 LOADING REQUIREMENTS.
 - REINFORCED STEEL SHALL BE A MINIMUM OF GRADE 40.

BENDING DETAIL



Final Approval

EQUIVALENT USCS AND AASHTO SOIL CONDITIONS FOR SOIL DESIGNATION

INSTALLATION TYPE	BEDDING THICKNESS	HAUNCH AND OUTER BEDDING	LOWER SIDE
TYPE 1	OD/24 MINIMUM; NOT LESS THAN 3-INCH. IF ROCK FOUNDATION =, USE OD/12 MINIMUM; NOT LESS THAN 6-INCH	95% CATEGORY I	95 90 85 80
TYPE 2	OD/24 MINIMUM; NOT LESS THAN 3-INCH. IF ROCK FOUNDATION =, USE OD/12 MINIMUM; NOT LESS THAN 6-INCH	95% CATEGORY I OR 95% CATEGORY II	95 90 85 80
TYPE 3	OD/24 MINIMUM; NOT LESS THAN 3-INCH. IF ROCK FOUNDATION =, USE OD/12 MINIMUM; NOT LESS THAN 6-INCH	100 95 90 85	90 85 80 75
TYPE 4	OD/24 MINIMUM; NOT LESS THAN 3-INCH. IF ROCK FOUNDATION =, USE OD/12 MINIMUM; NOT LESS THAN 6-INCH	100 95 90	90 85 80

SOIL	REPRESENTATIVE SOILS TYPE		PERCENT COMPACTION	
	USCS ASTM PRACTICE D2487	AASHTO M-145	SATNDARD PROCTOR	MODIFIED PROCTOR
CATEGORY I	CLEAN, COARSE GRAINED SOILS: SW, SP, GW, GP OR ANY SOIL BEGINNING WITH ONE OF THESE SYMBOLS WITH 12% OR LESS PASSING #200 SIEVE	A-1, A-3	100 95 90 85	95 90 85 80
		A-2-4, A-2-5, A-2-6, A-4 OR A-6 SOILS WITH 30% OR MORE RETAINED ON A #200 SIEVE	100 95 90 85	95 90 85 80
		A-2-7, A-4 OR A-6 WITH LESS THAN 30% RETAINED ON A #200 SIEVE	100 95 90 85	90 85 80 75
CATEGORY II	CLEAN, COARSE GRAINED SOILS WITH FINES; GM, GC, SM, SC OR ANY SOIL BEGINNING WITH ONE OF THESE SYMBOLS, CONTAINING MORE THAN 12% PASSING #200 SIEVE	A-2-4, A-2-5, A-2-6, A-4 OR A-6 SOILS WITH 30% OR MORE RETAINED ON A #200 SIEVE	100 95 90 85	95 90 85 80
		SANDY OR GRAVELLY FINE-GRAINED SOILS: CL, ML (OR CL-ML, CL/ML, ML/CL) ON A #200 SIEVE	100 95 90 85	90 85 80 75
CATEGORY III	FINE-GRAINED SOILS: CL, ML, OR (CL-ML, CL/ML) WITH LESS THAN 30% RETAINED ON A #200 SIEVE	A-2-7, A-4 OR A-6 WITH LESS THAN 30% RETAINED ON A #200 SIEVE	100 95 90 85	90 85 80 75
		MH, CH, OL, OH, PT	100 95 90	90 85 80

REFERENCES - BENCHMARKS


CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE AND WESTERN AVENUE, 1887350 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

DATE _____ REVISIONS _____ BY _____

CSA

CSA GROUP

TEXAS REGISTERED ENGINEERING FIRM F-4684
4712 Woodrow Branch St. F. El Paso, TX 79924
915.544.5232 www.csaengr.com



SCALE: N/A

Horizontal: N/A

Vertical: N/A

Contour Interval: N/A

DATE: DECEMBER 2018

DESIGN BY: C.J.G.

DRAWN BY: M.R.G.

CHECKED BY: J.L.A.

APPROVED BY: J.L.A.

JOB NO.: 2000-210

PROJECT TITLE

LA PUENTE DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS


SHEET TITLE

DRAINAGE DETAILS

(SHEET 1 OF 4)

SHEET NO.

C9.1




- GENERAL NOTES:**
1. MATCHING SURFACES MARKED "MF" TO BE FINISHED OF ANY IRREGULARITIES THAT WOULD PREVENT A SNUG FIT.
 2. CASTING TO BE SMOOTH & VOID OF AIR HOLES.
 3. CASTING MUST MEET REQUIREMENTS OF AASHTO M306-07.
 4. AS-CAST DIMENSIONS MAY VARY $\frac{1}{16}$ " \pm PER FOOT (AASHTO M306-07).
 5. WEIGHT MAY VARY 5% \pm (AASHTO M306-07).
 6. SHADED DIMENSIONS IN TABLE FOR REFERENCE ONLY. SOURCE: COUNTY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION, DETAIL 2-16.

SEE NOTE 6

MANHOLE RING	MANHOLE - ALL TYPES	MANHOLE TYPE 48	MANHOLE TYPE 72
A	33"	25 $\frac{1}{2}$ "	32 $\frac{1}{2}$ "
B	31 $\frac{1}{2}$ "	23 $\frac{1}{2}$ "	31 $\frac{1}{2}$ "
C	31 $\frac{1}{2}$ "	23 $\frac{1}{2}$ "	31 $\frac{1}{2}$ "
D	30"	22 $\frac{1}{2}$ "	30"
E	39 $\frac{1}{2}$ "	34 $\frac{1}{2}$ "	42"
F	5"	1 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "
G	5"	6"	6"
H	4 $\frac{1}{4}$ "	5 $\frac{1}{4}$ "	5 $\frac{1}{4}$ "
I	3 $\frac{1}{4}$ "	4 $\frac{1}{4}$ "	4 $\frac{1}{4}$ "
J	4 $\frac{3}{4}$ "	6"	6"
K	2 $\frac{3}{8}$ "	3 $\frac{1}{2}$ "	3 $\frac{1}{2}$ "
L	2 $\frac{1}{8}$ "	2 $\frac{1}{8}$ "	2 $\frac{1}{8}$ "
M	1 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "	1 $\frac{1}{2}$ "
WEIGHT	220 lbs.	185 lbs.	225 lbs.

STANDARD DETAIL DATE: 8/19/2009 REV: STORMWATER MANHOLE RING N.T.S. EL PASO WATER UTILITIES PUBLIC SERVICE BOARD DETAIL No. 916

1 C9.2 STORMWATER MANHOLE RING N.T.S.



- GENERAL NOTES:**
1. MATCHING SURFACES MARKED "MF" TO BE FINISHED OF ANY IRREGULARITIES THAT WOULD PREVENT A SNUG FIT.
 2. CASTING TO BE SMOOTH & VOID OF AIR HOLES.
 3. CASTING MUST MEET REQUIREMENTS OF AASHTO M306-07.
 4. AS-CAST DIMENSIONS MAY VARY $\frac{1}{16}$ " \pm PER FOOT (AASHTO M306-07).
 5. WEIGHT MAY VARY 5% \pm (AASHTO M306-07).
 6. SHADED DIMENSIONS IN TABLE FOR REFERENCE ONLY. SOURCE: COUNTY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION, DETAIL 2-17.

SEE NOTE 6

MANHOLE COVER	MANHOLE - ALL TYPES	MANHOLE TYPE 48	MANHOLE TYPE 72
A	31 $\frac{1}{2}$ "	23 $\frac{1}{2}$ "	31 $\frac{1}{2}$ "
B	28 $\frac{1}{2}$ "	20 $\frac{1}{2}$ "	28 $\frac{1}{2}$ "
C	24 $\frac{1}{2}$ "	16 $\frac{1}{2}$ "	24 $\frac{1}{2}$ "
D	21 $\frac{1}{2}$ "	14 $\frac{1}{2}$ "	21 $\frac{1}{2}$ "
E	2 $\frac{1}{2}$ "	3"	3"
F	1 $\frac{1}{4}$ "	1 $\frac{1}{4}$ "	1 $\frac{1}{4}$ "
G	3 $\frac{1}{2}$ "	3"	3"
H	1 $\frac{1}{8}$ "	1"	1"
WEIGHT	265 lbs.	195 lbs.	310 lbs.


STANDARD DETAIL DATE: 8/19/2009 REV: STORMWATER MANHOLE COVER N.T.S. EL PASO WATER UTILITIES PUBLIC SERVICE BOARD DETAIL No. 917

2 C9.2 STORMWATER MANHOLE COVER N.T.S.




- GENERAL NOTES:**
1. SIGN MATERIAL TO BE 16 GAUGE GALVANIZED SHEET METAL.
 2. TOP PART OF SIGN SHALL SHOW BLACK LETTERS ON A WHITE BACKGROUND.
 3. BOTTOM PART OF SIGN SHALL SHOW WHITE LETTERS ON A BLACK BACKGROUND.

3 C9.2 NO TRESPASSING WARNING SIGN SCALE: N.T.S.



- NOTES:**
1. A CONCRETE COLLAR IS REQUIRED WHERE PIPES CHANGE IN HORIZONTAL OR VERTICAL ALIGNMENT.
 2. FOR PIPES 24" OR LESS IN DIAMETER REINFORCE WITH W.W.M.

5 C9.2 CONCRETE PIPE COLLAR SCALE: N.T.S.



4 C9.2 GRATE AND FRAME DETAILS SCALE: 1" = 1'-0"

CONCRETE APRON FOR CIRCULAR PENETRATIONS IN ASPHALT PAVEMENTS


"D" DIAMETER OF PENETRATION (INCHES)	"A" CONCRETE HORIZONTAL DIMENSION FROM PENETRATION (INCHES)	NUMBER OF NO. 3 REINFORCING STEEL BARS (QUANTITY)	"B" MINIMUM CLEARANCE FROM EDGE OF CONCRETE APRON TO CENTER OF NEAREST REBAR (INCHES)	"C" MINIMUM CLEARANCE FROM PENETRATION EDGE TO CENTER OF NEAREST REBAR (INCHES)
0 TO 6.01	6	1	1 1/2	1 1/2
6.01 TO 18.01	8	2	1 1/2	1 1/2
18.01 AND OVER	12	3	1 1/2	1 1/2

CONSTRUCTION NOTES:


1. ANY DISTURBED SUBGRADE UNDER THE CONCRETE APRON SHALL BE COMPACTED TO 95% DENSITY \pm 3% OPTIMUM MOISTURE CONTENT IN ACCORDANCE WITH ASTM D-1557.
2. ANY DISTURBED COARSE UNDER THE CONCRETE APRON SHALL BE COMPACTED TO 100% DENSITY \pm 2% OPTIMUM MOISTURE CONTENT IN ACCORDANCE WITH ASTM D-1557.
3. PROVIDE A MINIMUM OF 1 1/2" OF CONCRETE COVER FOR ALL REINFORCEMENT STEEL.
4. REINFORCING SHALL MEET ASTM C-478 AND TRAFFIC LOADING (HS-20).
5. NO. 3 REINFORCING STEEL HOOPS SHALL BE SPACED EQUALLY.

GENERAL NOTES:

1. THE PENETRATION APRON SHOULD BE CAST IN-PLACE CONCRETE. (MINIMUM 28 DAY COMPRESSIVE STRENGTH 4000 P.S.I. HIGH EARLY CONCRETE IS REQUIRED).
2. TOPS OF PENETRATION APRON SHALL BE FLUSH WITH ROADWAY SURFACE OR FINISHED GRADE UNLESS OTHERWISE SPECIFIED BY THE CITY ENGINEER.



7 C9.2 PENETRATION APRON DETAILS SCALE: N.T.S.



6 C9.2 WROUGHT IRON GATE SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASO DEL COUNTY AND 12TH STREET, EL PASO, TEXAS (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO". ELEVATION = 3935.48 (CITY DATUM).

PROPERTY OF EL PASO WATER UTILITIES
Public Service Board
FACILITY NAME GOES HERE
1234567 STREET DRIVE
No Trespassing
Violators will be prosecuted.
In case of an emergency call:
594-5775

TECHNICAL DRAWING

SCALE: AS SHOWN
Horizontal: N/A
Vertical: N/A
Contour Interval: 1'/4"
DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No. 2000-210

ENGINEER'S SEAL

LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS

SHEET TITLE

DRAINAGE DETAILS


(SHEET 2 OF 4)
SHEET NO.

C9.2

Final Approval

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C9.2-Drainage Details-C9.2.dwg, 7/9/2019 10:26:10 AM

PP TRENCH INSTALLATION DETAIL FOR STORM APPLICATIONS



PIPE DIAM.	CLASS I		CLASS II		CLASS III	
	95%	90%	95%	90%	95%	90%
12" (300mm)	39 (11.9)	27 (8.2)	20 (6.1)	21 (6.4)	12 (3.7)	12 (3.7)
15" (375mm)	42 (12.8)	29 (8.6)	21 (6.4)	22 (6.7)	12 (3.7)	12 (3.7)
18" (450mm)	36 (11.0)	25 (7.6)	18 (5.5)	19 (5.6)	12 (3.7)	12 (3.7)
24" (600mm)	31 (9.5)	22 (6.7)	16 (4.9)	16 (4.9)	11 (3.7)	11 (3.7)
30" (750mm)	30 (8.1)	22 (6.7)	16 (4.9)	16 (4.9)	11 (3.7)	11 (3.7)
36" (900mm)	31 (9.5)	22 (6.7)	16 (4.9)	16 (4.9)	11 (3.7)	11 (3.7)
42" (1050mm)	34 (10.4)	23 (7.3)	17 (5.2)	17 (5.2)	11 (3.7)	11 (3.7)
48" (1200mm)	34 (10.4)	24 (7.3)	17 (5.2)	18 (5.3)	11 (3.7)	11 (3.7)
60" (1500mm)	32 (9.8)	22 (6.7)	15 (4.5)	16 (4.9)	11 (3.7)	11 (3.7)

FILL HEIGHT TABLE GENERATED USING AASHTO SECTION 12 LOAD RESISTANCE FACTOR DESIGN (LRFD) PROCEDURE WITH THE FOLLOWING ASSUMPTIONS:
NO HYDROSTATIC PRESSURE, UNIT WEIGHT OF SOIL (γ) = 120 PCF

TABLE 1. RECOMMENDED MINIMUM TRENCH WIDTHS

PIPE DIAM.	MIN TRENCH WIDTH
12" (300mm)	30" (750mm)
15" (375mm)	34" (860mm)
18" (450mm)	39" (990mm)
24" (600mm)	48" (1200mm)
30" (750mm)	56" (1420mm)
36" (900mm)	64" (1620mm)
42" (1050mm)	72" (1830mm)
48" (1200mm)	80" (2030mm)
60" (1500mm)	96" (2440mm)

TABLE 2. MINIMUM RECOMMENDED COVER BASED ON VEHICLE LOADING CONDITIONS

PIPE DIAM.	SURFACE LIVE LOADING CONDITION	
	H-20	HEAVY CONSTRUCTION (75T AXLE LOAD) *
12" - 48"	12" (300mm)	48" (1200mm)
300mm - 1200mm	12" (300mm)	48" (1200mm)
60" (1500mm)	24" (600mm)	60" (1500mm)


* VEHICLES IN EXCESS OF 75T MAY REQUIRE ADDITIONAL COVER

- NOTES:
- ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS," LATEST EDITION. WITH THE EXCEPTION THAT THE INITIAL BACKFILL MAY EXTEND TO THE CROWN OF THE PIPE. SOIL CLASSIFICATIONS ARE PER THE LATEST VERSION OF ASTM D2321.
 - MEASURES SHOULD BE TAKEN TO PREVENT MIGRATION OF NATIVE FINES INTO BACKFILL MATERIAL, WHEN REQUIRED.
 - FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER, AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
 - BEDDING: SUITABLE MATERIAL SHALL BE CLASS I, II, OR III. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. COMPACTION SHALL BE 90% OF MAXIMUM DENSITY PER ASTM D-1557 OR AS SHOWN ON THE PLANS. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 12"-24" (300mm-600mm) DIAMETER PIPE; 6" (150mm) FOR 30"-60" (750mm-1500mm) DIAMETER PIPE. THE MOOLE 10" BENEATH THE PIPE INVERT SHALL BE LOOSELY PLACED.
 - INITIAL BACKFILL: SUITABLE MATERIAL SHALL BE CLASS I, II, OR III IN THE PIPE ZONE EXTENDING TO THE CROWN OF THE PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION, FOR TRAFFIC APPLICATIONS; CLASS I, II, OR III MATERIAL SHALL BE COMPACTED TO A DENSITY OF NOT LESS THAN 95% PER THE CITY STANDARDS FOR BOTH COHESIVE AND COHESION LESS SOILS.
 - MINIMUM COVER: MINIMUM COVER, H, IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" (300mm) FROM THE TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOTATION. FOR TRAFFIC APPLICATIONS, MINIMUM COVER, H, IS 12" (300mm) UP TO 48" (1200mm) DIAMETER PIPE AND 24" (600mm) OF COVER FOR 60" (1500mm) DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF PAVEMENT OR TO TOP OF INCH PAVEMENT.

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

#1-POLYPROPYLENE PIPE DETAIL FOR STORM SEWER APPLICATIONS (INSTALLATION DETAIL)
SCALE: N.T.S.

12"-30" PP WATERSTOP GROUDED MANHOLE CONNECTION (DUAL WALL)




PIPE SIZE (N)	PIPE OD (N)	"A" MIN. HOLE Ø (N)	"B" MIN. DISTANCE PIPE INVERT TO STRUCTURE INVERT (N)
12	14.5	19.50	3.7
15	17.6	23.00	4.0
18	21.2	26.50	4.2
24	27.8	33.25	4.5
30	35.1	40.50	5.2
36	41.1	47.00	5.5
42	47.7	53.00	5.7
48	53.6	59.00	5.7
60	66.3	72.00	6.4

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

#4-WATERSTOP 12"-30" DUAL WALL POLYPROPYLENE STORM DETAIL (WATERSTOP GROUDED CONNECTION DETAIL FOR CAST-IN-PLACE STRUCTURES)
SCALE: N.T.S.

12"-30" PP WATERSTOP GROUDED MANHOLE CONNECTION (DUAL WALL)




PIPE SIZE (N)	PIPE OD (N)	"A" MIN. HOLE Ø (N)	"B" MIN. DISTANCE PIPE INVERT TO STRUCTURE INVERT (N)
12	14.5	19.50	3.7
15	17.6	23.00	4.0
18	21.2	26.50	4.2
24	27.8	33.25	4.5
30	35.1	40.50	5.2
36	41.1	47.00	5.5
42	47.7	53.00	5.7
48	53.6	59.00	5.7
60	66.3	72.00	6.4

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

#2-WATERSTOP 12"-30" DUAL WALL POLYPROPYLENE STORM DETAIL (WATERSTOP GROUDED CONNECTION DETAIL FOR PRECAST STRUCTURES)
SCALE: N.T.S.

30"-60" PP WATERSTOP GROUDED MANHOLE CONNECTION (TRIPLE WALL)




PIPE SIZE (N)	PIPE OD (N)	"A" MIN. HOLE Ø (N)
30	35.4	41.5
36	41.1	46.0
42	47.2	52.5
48	53.8	60.0
60	66.5	72.5

NOTES:
PERFORMANCE HIGHLY DEPENDENT ON INSTALLATION. CONTRACTOR MUST ENSURE MANHOLE GASKET IS UNIFORMLY SEATED AROUND STRUCTURE ADAPTER. EXTRA PRECAUTIONS MUST BE TAKEN TO PREVENT DIFFERENTIAL SETTLEMENT BETWEEN THE PIPE AND MANHOLE.

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

#3-WATERSTOP TRIPLE WALL 30"-60" POLYPROPYLENE STORM DETAIL (WATERSTOP GROUDED CONNECTION DETAIL FOR CAST-IN-PLACE STRUCTURES)
SCALE: N.T.S.

30"-60" PP WATERSTOP GROUDED MANHOLE CONNECTION (TRIPLE WALL)




PIPE SIZE (N)	PIPE OD (N)	"A" MIN. HOLE Ø (N)
30	35.4	41.5
36	41.1	46.0
42	47.2	52.5
48	53.8	60.0
60	66.5	72.5

NOTES:
PERFORMANCE HIGHLY DEPENDENT ON INSTALLATION. CONTRACTOR MUST ENSURE MANHOLE GASKET IS UNIFORMLY SEATED AROUND STRUCTURE ADAPTER. EXTRA PRECAUTIONS MUST BE TAKEN TO PREVENT DIFFERENTIAL SETTLEMENT BETWEEN THE PIPE AND MANHOLE.

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

#5-WATERSTOP TRIPLE WALL 30"-60" POLYPROPYLENE STORM DETAIL (WATERSTOP GROUDED CONNECTION DETAIL FOR PRECAST STRUCTURES)
SCALE: N.T.S.



- 95% COMPACTION AS PER ASTM D-1557
- KEY NOTES**
- 3" x 3" x 3/16" SQUARE STEEL TUBING
 - 2" x 1" x 14 GA. RECTANGULAR STEEL TUBING
 - 1 1/2" x 1/2" x 16 GA. RECTANGULAR STEEL TUBING
 - BOLT HOOK AND STRAP HINGE
 - FLAT TOP POLYVINYL CAP (TYP.)
 - 2" x 1" x 10 GA. RECTANGULAR STEEL TUBING
 - 1' x 3" DEEP 3,000 PSI CONCRETE POST FOOTING
 - 5" x 5" x 3/8" SQUARE STEEL SLEEVE W/7" x 7" x 3/8" BASE PLATE
- NOTE: REFER TO PLANS IF ROCKWALL IS DESIRED FOR A 2' ROCKWALL / 4' FENCE OR ONLY A 6' WROUGHT IRON FENCE.

#6-TYPICAL ROCKWALL W/ WROUGHT IRON FENCE DETAILS
SCALE: N.T.S.



POST

THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEET OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

REFERENCES - BENCHMARKS

CITY OF PASADENA, CALIFORNIA
CITY ENGINEER'S SEAL
ELEVATION = 3935.48 (CITY DATUM)
"CHINO"
THIS IS BASED ON NGS MONUMENT

DATE	REVISIONS	BY



SCALE: N/A

Horizontal: N/A
Vertical: N/A

Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.G.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPD. BY: J.L.A.

JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR

SUBDIVISION IMPROVEMENTS

SHEET TITLE

DRAINAGE DETAILS


(SHEET 3 OF 4)

SHEET NO.



Final Approval


C9.3




TOP VIEW
SCALE: N.T.S.

CULVERT	A	B	C	D	E	F	G	H	I	J	K	L	M	N
12'x5'	152'	164'	129'	25'	174'	192'	15'	10'	52'	144'	10'	82'	44'	120'


NOTE: APPROXIMATE DISTANCE SHOWN. ACTUAL DISTANCE WILL VARY ACCORDING TO PIPE WALL THICKNESS.




ENERGY DISSIPATER
SCALE: N.T.S.



FRONT VIEW
SCALE: N.T.S.




SIDE VIEW



TOP VIEW

2
C9.4
CULVERT CONNECTION DETAIL
SCALE: 1"=3'




1
C9.4
OUTLET STRUCTURE WITH ENERGY DISSIPATER
SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASO DEL CITY AND ... (CITY DATUM). THIS IS BASED ON MONUMENT "CHINO".
ELEVATION = 3935.48 (CITY DATUM)

DATE	REVISIONS	BY



SCALE: N/A

Horizontal: N/A
Vertical: N/A
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS

SHEET TITLE

DRAINAGE DETAILS

(SHEET 4 OF 4)

SHEET NO.






C9.4

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C9.1-Drainage Details-C9.4-19.dwg, 7/9/2019 10:27:14 AM

MATERIAL NOTES:

1. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS.
2. ALL REINFORCING STEEL SHALL BE GRADE 60 OR HIGHER.
3. PERMANENT METAL FORM DECK SHALL BE 3 C CONFORM GALVANIZED STEEL DECK BY VULCRAFT OR EQUIVALENT.



1
SI TYPICAL SECTION
1" = 1'-0"

RAUL MEZA, JR., P.E.
P.O. BOX 2322
FABENS, TEXAS 79838
PH. 915-765-7071
TBPE FIRM NO. F-12829



TEXAS

CEA ENGINEERING GROUP
LA PUESTA DEL SOL - UNIT FOUR


EL PASO

Final Approval

TITLE:
12' X 5' REINFORCED
CONCRETE BOX CULVERT
TYPICAL SECTION USING
PERMANENT METAL FORM
DECK.

DESIGNED BY: RM
DATE: MAR. 28, 2019

SHEET:
S1



NELLIE D. MUNDY SURVEY NO. 240
EL PASO COUNTY, TEXAS

A PORTION OF TRACT 3A,
NELLIE D. MUNDY SURVEY NO. 240
EL PASO COUNTY, TEXAS
BERNARD L. FENEBOCK
VOL: 4220 PG: 0984

CANUTILLO HIGH SCHOOL
A PORTION OF TRACT 3A1,
NELLIE D. MUNDY SURVEY
NO. 240
EL PASO COUNTY, TEXAS
VOL: 4403 PG: 713

CANUTILLO PALMS APARTMENTS

LA PUESTA DEL SOL UNIT ONE
INS. NO. 20110085925

ILLUMINATION AND SIGNAGE PLAN

SCALE: 1" = 100'

GRAPHIC SCALE




(IN FEET)
1 inch = 100 ft.

UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 890-7200
SSC	(800) 545-8005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

- LEGEND:**
- PROPOSED RESIDENTIAL STREET LIGHT
 - EXISTING RESIDENTIAL STREET LIGHT
 - PROPOSED 9" STREET NAME SIGN (TWO SIGNS) AND 30" STOP SIGN
 - NO OUTLET SIGN
 - PROPOSED N.D.B.C.U. MAIL BOX
 - PROPOSED TRAFFIC SIGN




NOTE:
SIGNS SHOULD COMPLY WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).

SIGNS DETAIL
SCALE: N.T.S.

NOTE:

- POSTS MUST BE BREAK-AWAY TYPE AS SHOWN ON THIS SHEET.
- TRAFFIC STREET SIGNS MUST BE OF HIGH INTENSITY REFLECTIVE SHEETING.

4 RESIDENTIAL STREET LIGHTS



RESIDENTIAL STREET LIGHT WOOD POLE
SCALE: N.T.S.

RESIDENTIAL STREET LIGHT WOOD POLE
SCALE: N.T.S.

ITEM NO.	DESCRIPTION	STOCK NO.	QTY.	
1	PHOTO CELL, 240 V-SEE NOTE 1	21-225	1	LCOBRAHD
2	HPS LAMP, 100W	21-085	1	
3	LUMINAIRE, 100W H.P.S.	21-335	1	
4	SLEEVES, #12-10	05-140	2	LSLV1210
5	MAST ARM, 6' X 1 1/4"	21-200	1	LBRKT1*6
6	MACHINE BOLT, 5/8" X 12"	02-470	1	
7	SQUARE GALV. WASHER, 2 1/4" X 2 1/4"	02-760	1	
8	COIL SPRING WASHER, 5/8"	02-786	1	LMB5/812
9	LOCK NUT, 5/8"	02-705	1	
10	SERVICE ENTRANCE CAP FOR 1" PVC CONDUIT	17-281	1	LSVCCAP1
11	LAG BOLT, 3/8" X 3"	02-343	1	LLAG38*3
12	CABLE, #10, 2 CONDUCTOR, 600V, UF	13-600	8'	L2C#10S
13	COPPER CABLE, #12, SOLID, 600V, GREEN	13-702	60'	LC#12CU
14	SCHEDULE 80 1" PVC CONDUIT	17-280	30'	LSCH80P
15	PIPE STRAP FOR 1" PVC CONDUIT, 2-HOLE	17-283	9'	LPVCSTRP
16	NAIL, STAINLESS STEEL SCREW 2.5 IN.	14-427	.25#	LNAL14*2
17	POLE, 35 FT. - CLASS 4	09-035	1	L354UG
18	1" PVC 90 DEGREE ELBOW	17-297	1	LEL901
19	1" PVC 45 DEGREE ELBOW	17-298	1	LEL451
20	1" PVC COUPLING	17-296	1	LCPLG1
21	1" PVC CONDUIT	17-299	AS REQ	LPVC1



REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF S. SEG. DEL NORTE & NORTHWESTERN ELEVATION = 5887.30 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

DATE: _____

REVISIONS: _____

BY: _____

SCALE: _____

Horizontal: _____

Vertical: Contour Interval: N/A

DATE: DECEMBER 2018

DESIGN BY: C.J.

DRAWN BY: M.R.G.

CHKD. BY: J.L.A.

APPVD. BY: J.L.A.

JOB NO.: 2000-210

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE


ILLUMINATION, SIGNAGE AND STRIPPING PLAN

(SHEET 1 OF 2)

SHEET NO.

C10.1

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C10.1-C10.2-Illumination Plan.dwg, 7/9/2019 1:46:07 PM



LINE TABLE


LINE	BEARING	LENGTH
L1	N89°59'59"W	122.00'
L2	N89°59'19"W	771.99'

WATER QUANTITIES

DESCRIPTION	QUANTITY	UNIT
8" PVC WATER LINE	893.99	LF
3/4" SERVICE CONNECTION	61	EA

WATER KEYED NOTES

①	8" X 8" X 8" TEE
②	FIRE HYDRANT



TYPICAL WATER LINE SEPARATION
SCALE: N.T.S.

CONTRACTOR SHALL VERIFY DEPTH AND LOCATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION.

WATER INDEX MAP

SCALE: 1" = 100'

INDEX

SHEET NO.	DESCRIPTION
C11.1	LA PUESTA DEL SOL UNIT FOUR WATER MAIN PIPE LAYOUT
C11.2	WATER DETAILS
C11.3	WATER DETAILS
C11.4	WATER DETAILS
C11.5	WATER DETAILS

- NOTES:**
- ALL LOTS SHALL BE PROVIDED WITH ONE SERVICE CONNECTION TO BE INSTALLED AT THE LOCATION AS SHOWN ON THE SERVICE LOCATION DETAIL.
 - ALL WATER LINES SHALL BE PVC C-900, CLASS 235 (DR18).
 - REFERENCE WATER DETAILS FOR TYPICAL VALVE AND WATER LOCATIONS AT STREET INTERSECTIONS.
 - REFERENCE WATER DETAILS FOR WATER LINE CROSSING STORM SEWER.
 - TO BE REMOVED BY EPWU UNDER SEPARATE CONTRACT.

LEGEND

SYMBOL	DESCRIPTION
8" WTR.	PROPOSED 8" C-900, CLASS 235 (DR18) P.V.C. PIPE
---	SUBDIVISION BOUNDARY LINE
---	PROPERTY LINE
---	STREET CENTER LINE
8" SWR	PROPOSED SEWER LINE (PLAN VIEW)
---	PROPOSED STORM SEWER
+	PROPOSED WATER CROSS CONNECTION
+	PROPOSED WATER TEE CONNECTION
+	PROPOSED WATER BEND CONNECTION
+	PROPOSED 3/4" SERVICE CONNECTION (PLAN VIEW)
+	PROPOSED FIRE HYDRANT, KENNEDY OR MUELLER MODEL
+	PROPOSED 8" PLUG
+	PROPOSED GATE VALVE
+	POINT OF TANGENCY
+	REDUCER
+	EXISTING GATE VALVE
+	EXISTING FIRE HYDRANT
+	EXISTING PLUG
---	EXISTING SEWER LINE
---	EXISTING WATER LINE

- GENERAL NOTES**
- UNLESS OTHERWISE SHOWN ON THE DRAWINGS, THE PROPOSED WATER MAINS SHALL BE INSTALLED NO LESS THAN TEN (10') FEET AWAY FROM EXISTING SEWER LINE. SEPARATIONS DISTANCES SHALL FOLLOW TCEQ STANDARD REQUIREMENTS (§290.44).
 - THE INTENT OF THE OWNER IS TO HAVE THE WATER MAINS INSTALLED TO SUCH A DEPTH THAT THEY WILL HAVE AT LEAST SIXTY (60") INCHES FROM INVERT OF PIPELINE TO PROPOSED ELEVATIONS AT ALL LOCATIONS. THE PIPELINES SHALL HAVE NO DIPS, ELEVATIONS AT ALL LOCATIONS. THE PIPELINES SHALL HAVE NO DIPS, SAGS OR HUMPS OR OTHER IRREGULARITIES IN VERTICAL ALIGNMENT. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES PRIOR TO INSTALLING THE WATER PIPELINE SO THAT AN ACCEPTABLE PROFILE CAN BE ESTABLISHED PRIOR TO INSTALLATION OF THE PIPELINE.
 - IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD LOCATE ALL UNDERGROUND UTILITIES, SHOWN OR NOT SHOWN IN THE PLANS, AND COORDINATE WORK WITH ALL UTILITY COMPANIES, EL PASO WATER UTILITIES AND CITY OF EL PASO.
 - TRENCH SAFETY REQUIREMENTS SHALL BE AS REQUIRED BY OSHA.
 - AS-BUILT STATIONING, OFFSET FROM R.O.W. AND INVERT ELEVATIONS SHALL BE ACCURATELY RECORDED BY THE CONTRACTOR ON A CLEAN SET OF PLANS FOR EACH VALVE, FIRE HYDRANT, ELBOW, SERVICE CONNECTION AND/OR STUB-OUT, WITH RESPECT TO THE APPROPRIATE CONTROL POINT.
 - THE EL PASO WATER UTILITIES AND CITY OF EL PASO MUST BE NOTIFIED FORTY-EIGHT (48) HOURS PRIOR TO COMMENCING ANY WORK IN AREAS WITHIN THEIR JURISDICTION.
 - EXISTING STREETS, DRIVEWAYS, PARKING LOTS, MAILBOXES, SIGNS, CHAIN-LINK FENCES, AND ALL OTHER MISCELLANEOUS STRUCTURES DAMAGE OR REMOVED BY CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO ORIGINAL OR BETTER THAN ORIGINAL CONDITION AT NO COST TO OWNER.
 - TRAFFIC CONTROL SHALL BE IN PLACE PRIOR TO INITIATING WORK.
 - ALL TIE-INS SHALL BE CLOSELY COORDINATED WITH THE EL PASO WATER UTILITIES AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO ACTUAL CONSTRUCTION.
 - CONTRACTOR SHALL PROVIDE THE REQUIRED COUPLINGS, ELBOWS AND NECESSARY PIPING APPURTENANCES FOR A COMPLETE AND OPERATIONAL WATER SYSTEM.
 - ALL NEW VALVES SHALL BE ALIGNED PERPENDICULAR TO PROPERTY LINES.
 - CONSTRUCTION OF THE PUBLIC WATER AND SEWER SYSTEM INCLUDING MATERIALS AND TESTING SHALL CONFORM EPWU-PSB SPECIFICATIONS FOR THE INSTALLATION OF WATER MAINS, SEWER MAINS AND RELATED APPURTENANCES.
 - FIRE HYDRANTS SHALL BE INSTALLED IN THE PARKWAY AREA.
 - THE WATER METERS FOR THE PROPOSED WATER SERVICE CONNECTIONS SHALL BE INSTALLED ON THE PARKWAYS. SYMBOLS ARE ONLY SHOWN FOR DEPICTION PURPOSES ONLY.

GENERAL UTILITIES:
TEXAS EXCAVATION SAFETY SERVICE
11884 GREENVILLE AVENUE,
DALLAS, TX 75243
(800) 344-8377

ENGINEER:
CEA GROUP
CASTNER CENTER @ TRANSMOUNTAIN
4712 WOODROW BEAN, STE. F
EL PASO, TX 79924
(915) 544-5232
MR. JORGE L. AZCARATE, P.E.

FIBER OPTICS:
U.S. SPRINT
151 N. BOONE ST.
EL PASO, TX 79905
(915) 534-7810

FIBER OPTICS:
MCI TELECOMMUNICATIONS CORP.
4045 DONIPHAN PARK CIRCLE
EL PASO, TX 79922
(915) 542-2770 EXT. 201

WATER & SEWER:
EL PASO WATER UTILITIES
1154 HAWKINS BOULEVARD
EL PASO, TX 79861
(915) 594-5530

ELECTRIC:
EL PASO ELECTRIC CO.
501 W. SAN ANTONIO ST.
EL PASO, TX 79902
(915) 543-2076

EL PASO STREETS
CITY OF EL PASO
STREET & MAINTENANCE
7969 SAN PAULO DRIVE
EL PASO, TX 79907
(915) 621-6750


CABLE TELEVISION:
TIME WARNER COMMUNICATIONS
7010 AIRPORT ROAD
EL PASO, TX 79906
(915) 772-1123

TELEPHONE:
SBC
11200 PELICANO
EL PASO, TX 79935
(915) 595-5151

FIBER OPTICS:
AT&T
P.O. BOX 1650
EL PASO, TX 79949
(800) 852-3786

RESIDENTIAL GAS LINES:
TEXAS GAS SERVICE
4700 POLLARD ST.
EL PASO, TX 79930
(915) 680-7218

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES



PLAN
SERVICE LOCATION DETAIL
SCALE: N.T.S.

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN ELEVATION = 3892.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3835.48 (CITY DATUM)

DATE: _____ REVISIONS: _____ BY: _____

oa
TEXAS REGISTERED ENGINEERING FIRM F-4584
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5232 | www.oaengr.com

ENGINEER'S SEAL
Jorge L. Azcarate
Professional Engineer
No. 10075

SCALE:
Horizontal: _____
Vertical: Contour Interval: 1' / 4'

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No.: 2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
WATER INDEX

SHEET NO.
C11.1

GENERAL NOTES:

- REFERENCE CENTERLINE SHALL BE CENTERLINE OF RIGHT OF WAY.
- WATER LINES SHALL BE LOCATED ON NORTH OR EAST SIDES OF DEDICATED STREETS OR ALLEYS.
- SEWER LINES SHALL BE LOCATED ON SOUTH OR WEST SIDES OF DEDICATED STREETS OR ALLEYS.
- RECLAIMED LINES SHALL BE LOCATED ON SOUTH OR WEST SIDES OF DEDICATED STREETS OR ALLEYS.

CONSTRUCTION KEY NOTES:

A. DISTANCES FROM CENTERLINE VARY AND SHALL BE ACCORDING TO THE FOLLOWING:

PIPELINE LOCATION WITHIN NEW RIGHT-OF-WAY			
RIGHT-OF-WAY WIDTH*	OFFSET FROM CENTERLINE**		
	WATER	SEWER	RECLAIMED
36 FT.	9 FT.	1 FT.	6 FT.
44 FT.	8 FT.	3 FT.	8 FT.
52 FT.	8 FT.	5 FT.	10 FT.
64 FT.	10 FT.	5 FT.	10 FT.
72 FT.	10 FT.	5 FT.	10 FT.
78 FT.	10 FT.	5 FT.	10 FT.
84 FT.	20 FT.	5 FT.	10 FT.
110 FT.	25 FT.	15 FT.	20 FT.

*RIGHT OF WAY WIDTH SUBJECT TO CHANGE. VERIFY WITH CITY SUBDIVISION ORDINANCE.
**DISTANCES MAY BE MODIFIED AS NEEDED TO MEET TCEQ SEPARATION REQUIREMENTS. REFER TO DETAILS 160 THRU 163 FOR ADDITIONAL INFORMATION.

STANDARD DETAIL DATE: 03/1994 REV: 3/28/2007 LOCATION FOR UTILITY LINES N.T.S. el paso WATER DETAIL No. 140

1 LOCATION FOR UTILITY LINES SCALE: N.T.S.

GENERAL NOTES:

- BEDDING FOR PRESSURE AND GRAVITY PIPE IN DRY CONDITIONS.
- PROVIDE TRENCH SAFETY SYSTEM FOR TRENCH DEPTHS GREATER THAN 5 FEET.
- IF THE NATIVE MATERIAL EXCAVATED FROM THE TRENCH IS UNSUITABLE AS BACKFILL MATERIAL, OR THE REQUIRED COMPACTION IS UNATTAINABLE, THE CONTRACTOR SHALL, AT HIS EXPENSE, IMPORT SELECT MATERIAL TO BE MIXED WITH OR USED IN PLACE OF THE NATIVE MATERIAL. SELECT MATERIAL MUST BE APPROVED BY EPWL. SUBSTITUTE SOIL CEMENT SLURRY (1-SACK) IF REQUIRED IN SPECS.

CONSTRUCTION KEY NOTES:

- APPROVED MARKING TAPE.
- UNDISTURBED STABLE MATERIAL.
- NATIVE MATERIAL BACKFILL.
- PAVED CONDITION: COMPACT TO 90% DENSITY PER ASTM D-1557 MODIFIED PROCTOR.
- UNPAVED CONDITION: COMPACT TO 85% DENSITY PER ASTM D-1557 MODIFIED PROCTOR.
- SLOPE TRENCH IN SANDY SOIL CONDITIONS. (*SEE NOTE #3 IF THESE PREVIOUS CONDITIONS CANNOT BE MET.)
- USE CLASS II OR CLASS III SAND PER ASTM D-2487. NATIVE MATERIAL OR IMPORTED SELECT MATERIAL MEETING OR EXCEEDING THIS REQUIREMENT MAY BE USED. COMPACT TO 85% DENSITY PER ASTM D-1557 MODIFIED PROCTOR (OR 90% D-698 STANDARD PROCTOR).
- APPROVED PIPE.
- TRENCH DIMENSIONS AS FOLLOWS:

PIPE DIAMETER	"H"
6" - 30"	4"
GREATER THAN 30"	6"

PIPE DIAMETER	"W"
6" - 30"	6"
GREATER THAN 30"	12"

STANDARD DETAIL DATE: 4/24/2007 REV: 2/21/2011 EMBEDDING CLASS "A" FOR PRESSURE PIPE AND GRAVITY PIPE DRY CONDITIONS N.T.S. el paso WATER DETAIL No. 171

2 BEDDING CLASS DETAILS FOR P.V.C. PRESSURE PIPE SCALE: N.T.S.

GENERAL NOTES:

- ALL ASPHALT CUTS MUST BE SAW CUT.
- SOIL CEMENT SLURRY SHALL BE ALLOWED TO CURE BEFORE PAVING OR OPENING TO ALL TRAFFIC.

CONSTRUCTION KEY NOTES:

- REFER TO SPECS FOR LIMIT OF PAVING WIDTH.
- DIMENSION VARIES, WHERE GUTTER FACE, ETC. IS WITHIN 3' OF SAW CUT EDGE, CONTRACTOR SHALL REMOVE & REPLACE EXISTING HMA IN THIS AREA.
- 2" ASPHALT MIN.
- 12" THICK SOIL CEMENT BACKFILL (2 SACK PER C.Y. OF SOIL).
- EXISTING HMA-C-THICKNESS MAY VARY.
- EXISTING BASE COURSE-THICKNESS MAY VARY.
- EXISTING GUTTER FACE, EDGE OF PAVEMENT OR BEGINNING OF SHOULDER.
- BACKFILL DEPTH VARIES, REFER TO REQUIREMENTS LISTED IN EMBEDMENT DETAILS (DETAIL 171 THRU DETAIL 173).
- PIPE BEDDING AS SPECIFIED, REFER TO APPROPRIATE EMBEDMENT DETAIL (DETAIL 171 THRU DETAIL 173).
- APPROVED PIPE.

STANDARD DETAIL DATE: 10/1992 REV: 5/9/2011 PAVEMENT REPLACEMENT N.T.S. el paso WATER DETAIL No. 179

3 PAVEMENT REPLACEMENT SCALE: N.T.S.

GENERAL NOTES:

- REFER TO UTILITY DETAIL FOR PAVEMENT REPLACEMENT AND BACKFILL REQUIREMENTS.
- TRENCH SAFETY SYSTEMS SHALL BE USED WHEN TRENCH DEPTH EXCEEDS 5 FEET.

CONSTRUCTION KEY NOTES:

A. COVER FOR WATER MAINS SHALL DEPEND ON THE PIPE SIZE AND THE FOLLOWING INSTALLATION CONDITIONS.

CONDITION A - NORMAL LINE INSTALLATION, STREET AND DRAINAGE PROJECTS, WATERLINE RELOCATION

CONDITION B - NEW SUBDIVISIONS, NON-PAVED AREA AND SHALL BE AS FOLLOWS.

PIPE SIZE	CONDITION	DIMENSION
6", 8"	A	D1 = 4"
6", 8"	B	D1 = 4"
12" & LARGER	A OR B	D1 = 5"

STANDARD DETAIL FEB. 1994 REV: 8/3/2006 COVER FOR WATER MAINS N.T.S. el paso WATER DETAIL No. 250

4 COVER FOR WATER MAINS SCALE: N.T.S.

GENERAL NOTES:

- VALVE TYPE AND VALVE ENDS SHALL BE AS SHOWN ON THE PLANS.
- ALL BURIED VALVES 8" AND DEEPER SHALL BE PROVIDED WITH SOLID STEEL EXTENSION STEM OPERATOR WITH 2" SQUARE ANWU NUT WITHIN 36" OF VALVE BOX COVER. NUT IS TO INDICATE DIRECTION OF ROTATION TO OPEN VALVE.
- 8" DIA. MINIMUM VITRIFIED CLAY OR SDR 35 P.V.C. PIPE, PIPE SHALL NOT REST ON VALVE BODY.
- 1/2" THICK STEEL TRASH RING VALVE BOX INSIDE DIAMETER MINUS 1/4".
- MINIMUM 2" CONCRETE OR BRICK ALL AROUND.
- CLEAN BONNET BOX OF ALL DEBRIS AND SOIL.
- COAT BURIED PIPE AND BONNET BOX PER SPECIFICATIONS. VALVE SHALL BE WRAPPED IN POLYETHYLENE IN ACCORDANCE WITH SPECIFICATIONS.

CONSTRUCTION KEY NOTES:

- BONNET BOX (SEE DETAIL 269).
- BONNET BOX COVER (SEE DETAILS 269-1 & 269-2).
- FINAL EXTENSION TO BONNET BOX SHALL BE WITH BELL AND SPIGOT ENDS (CLAY OR SDR 35 P.V.C. SPOOL).
- CONCRETE VALVE ANCHOR (SEE DETAIL 271).
- CONCRETE COLLAR (SEE DET 184-1) FLUSH WITH TOP OF H.M.A.C.
- BONNET BOX FLUSH WITH TOP OF CONCRETE, CONCRETE COLLAR NOT NEEDED.
- CONCRETE APRON (SEE DETAIL 184-2) FLUSH WITH BONNET BOX AND 2" ABOVE NATURAL GROUND.

STANDARD DETAIL DATE: 5/1994 REV: 6/22/2009 GATE VALVE INSTALLATION N.T.S. el paso WATER DETAIL No. 260

5 GATE VALVE INSTALLATION SCALE: N.T.S.

GENERAL NOTES:

- TABLE IS BASED ON 2000#/SQ. FT. SOIL. IF CONDITIONS ARE FOUND TO INDICATE SOIL BEARING IS LESS, THE AREAS SHALL BE INCREASED ACCORDINGLY.
- AREAS FOR PIPE LARGER THAN 18" SHALL BE CALCULATED.
- CONCRETE SHALL HAVE A MINIMUM COMPRESSION STRENGTH OF 2500 PSI.
- THRUST BLOCK IS TO EXTEND TO UNDISTURBED SOIL.
- SIZE MAY BE DECREASED FOR LESSER DEGREE BENDS AS DETERMINED BY ENGINEER.
- KEEP CONCRETE CLEAR OF M.J. OR BELL AND SPIGOT JOINTS.
- BLOCK IN A SIMILAR MANNER AT TEES, HYDRANTS, PLUG OR OTHER LOCATIONS AS REQUIRED.
- WHEN NECESSARY ADDITIONAL THRUST RESTRAINT METHODS MAY BE USED, SUCH AS MECHANICAL JOINT RESTRAINTS, TIE-RODS (INSTALLED PER MANUFACTURERS' RECOMMENDATIONS) OR OTHER APPROVED METHODS.

CONSTRUCTION KEY NOTES:

- LENGTH "Y" & "W" AS REQUIRED TO OBTAIN BEARING AREA AGAINST UNDISTURBED SOIL.
- ADDITIONAL EXCAVATION IF NECESSARY TO OBTAIN REQUIRED BEARING AREA.
- MINIMUM THRUST BLOCK AREA REQUIREMENTS FOR (Y & W) AS FOLLOWS:

PIPE SIZE	WATER PIPE	
	TEE, DEAD END 90° BEND	45° AND 1 1/2° BENDS
4" & LESS	3 SQ. FEET	3 SQ. FEET
6"	4 SQ. FEET	3 SQ. FEET
8"	6 SQ. FEET	3 SQ. FEET
10"	9 SQ. FEET	5 SQ. FEET
12"	13 SQ. FEET	7 SQ. FEET
16"	23 SQ. FEET	12 SQ. FEET
18"	29 SQ. FEET	15 SQ. FEET

STANDARD DETAIL DATE: 2/1994 REV: 8/7/2006 CONCRETE THRUST BLOCKING N.T.S. el paso WATER DETAIL No. 270

6 CONCRETE THRUST BLOCKING SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASSED DEL CORRAL MOUNT (WEST) AND EL PASO MONUMENT (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"

ELEVATION = 3935.48 (CITY DATUM)

DATE REVISIONS BY

el paso WATER

TEXAS REGISTERED ENGINEERING FIRM F-4684
4712 Woodrow Bean St. F. El Paso, TX 79924
915.544.5232 | www.eapgroup.net

ENGINEER'S SEAL

SCALE: N/A
Horizontal: N/A
Vertical: N/A
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No. - 2000-210

PROJECT TITLE

LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS


SHEET TITLE

WATER DETAILS


(SHEET 1 OF 4)
SHEET NO.

C11.2


S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta 04 Improvements\C11.2-C11.5-Water Details.dwg, 7/9/2019 10:35:32 AM




1 BONNET BOX
 SCALE: N.T.S.




2 BONNET BOX COVER
 SCALE: N.T.S.



3 CONCRETE COLLAR INSTALLATION IN PAVED AREAS
 SCALE: N.T.S.



4 VALVE ANCHOR
 SCALE: N.T.S.




5 FIRE HYDRANT INSTALLATION
 SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL SOL & WINTERMIST DRIVE	3867.239
(CITY DATUM)	THIS IS BASED ON NGS MONUMENT "CHINO"
ELEVATION = 3935.48	(CITY DATUM)


DATE	REVISIONS	BY




SCALE	N/A
Horizontal:	N/A
Vertical:	N/A
Contour Interval:	N/A
DATE:	DECEMBER 2018
DESIGN BY:	C.J.
DRAWN BY:	M.R.G.
CHKD. BY:	J.L.A.
APPVD. BY:	J.L.A.
JOB No.	2000-210

PROJECT TITLE
 LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS


SHEET TITLE
 WATER DETAILS
 (SHEET 2 OF 4)
 SHEET NO.




C11.3




1 FIRE HYDRANT CAP
SCALE: N.T.S.




2 FIRE HYDRANT LOCATIONS
SCALE: N.T.S.




3 SERVICE LINE 3/4" AND 1" INSTALLATION
SCALE: N.T.S.



4 METER BOX TYPE "A" FOR 3/4" SERVICE INSTALLATION
SCALE: N.T.S.



5 METER BOX RING FOR TYPE "A" & "B" METER BOXES
SCALE: N.T.S.



6 METER BOX COVER FOR TYPE "A" & "B" METER BOXES
SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF BASEO DEL CURBE AND THE PROPERTY LINE

CITY DATUM

"CHINO"

ELEVATION = 3935.48 (CITY DATUM)

DATE

REVISIONS

BY

www.caagroup.net

TEXAS REGISTERED ENGINEERING FIRM F-4684
4712 Woodrow Branch, Ste. F, El Paso, TX 79924
915.544.5232

ENGINEER'S SEAL

SCALE

Horizontal: N/A

Vertical: N/A

Contour Interval: N/A

DATE: DECEMBER 2018

DESIGN BY: C.J.

DRAWN BY: M.R.G.

CHKD. BY: J.L.A.

APPVD. BY: J.L.A.

JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS

SHEET TITLE


WATER
DETAILS

(SHEET 3 OF 4)


SHEET NO.

C11.4



S:\2000-210-04 Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C11.4-C11.5-Water Details.dwg, 7/9/2019 10:34:28 AM



1 SEPARATION DISTANCE POTABLE WATER, SANITARY SEWER AND RECLAIMED WATER
 SCALE: N.T.S.



2 SEPARATION DISTANCE SANITARY SEWER AND POTABLE WATER (SPECIAL CONDITIONS)
 SCALE: N.T.S.



REFERENCES - BENCHMARKS
 CITY MONUMENT AT THE INTERSECTION OF PLASEO DEL NORTE & NORTHWESTERN. ELEVATION = 3867.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
 ELEVATION = 3935.48 (CITY DATUM)

DATE: _____ REVISIONS: _____ BY: _____

TEXAS REGISTERED ENGINEERING FIRM F-4684
 4712 Woodrow Behm, Ste. F El Paso, TX 79924
 915.544.5252 www.osagroup.net

ENGINEER'S SEAL


SCALE: N/A
 Horizontal: N/A
 Vertical: N/A
 Contour Interval: N/A
 DATE: DECEMBER 2018
 DESIGN BY: C.J.G.
 DRAWN BY: M.R.G.
 CHKD. BY: J.L.A.
 APPVD. BY: J.L.A.
 JOB No. - 2000-210

PROJECT TITLE
 LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS

SHEET TITLE
 WATER DETAILS
 (SHEET 4 OF 4)
 SHEET NO.
 C11.5

Final Approval

S:\2000\2000-210-4a Puesta Del Sol Unit Three\DWG\Construction Drawings\4a Puesta Del Sol Unit Three\Water Details.dwg, 7/9/2019 10:34:45 AM



NELLIE D. MUNDY
SURVEY NO. 240
EL PASO COUNTY,
TEXAS

A PORTION OF TRACT 3A,
NELLIE D. MUNDY SURVEY NO. 240
EL PASO COUNTY, TEXAS
BERNARD L. FENEBOCK
VOL: 4220 PG: 0984

CANUTILLO HIGH SCHOOL
A PORTION OF TRACT 341,
NELLIE D. MUNDY SURVEY
NO. 240
EL PASO COUNTY, TEXAS
VOL: 4403 PG: 713

WASTEWATER QUANTITIES			
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
1	8" PVC SDR35 GRAVITY LINE	926	LF
2	8" PVC C-900, CL150	815	LF
3	STANDARD WASTEWATER MANHOLE	5	EA
4	4" WASTEWATER SERVICE CONNECTION	61	EA
5	8" STEEL CASING	270	LF

CONTRACTOR SHALL VERIFY DEPTH AND LOCATION OF ALL EXISTING UTILITIES PRIOR TO COMMENCING CONSTRUCTION.

SANITARY SEWER INDEX MAP
SCALE: 1" = 100'

GENERAL NOTES

- UNLESS OTHERWISE SHOWN ON THE DRAWINGS, THE PROPOSED SEWER MAINS AND SEWER MANHOLES SHALL BE INSTALLED NO LESS THAN TEN (10) FEET AWAY FROM EXISTING WATER LINE. SEPARATIONS DISTANCES SHALL FOLLOW TCEQ STANDARD REQUIREMENTS (§290.44).
- THE INTENT OF THE OWNER IS TO HAVE THE SANITARY SEWER PIPELINES INSTALLED TO SUCH A DEPTH THAT THEY WILL HAVE AT LEAST FORTY-EIGHT (48") INCHES OF COVER BELOW PROPOSED GROUND AT ALL LOCATIONS. THE PIPELINES SHALL HAVE NO DIPS, SAGS OR HUMPS OR OTHER IRREGULARITIES IN VERTICAL ALIGNMENT. CONSIDERING UTILITIES AND OTHER CONDITIONS, VARIANCE FROM GRADE PROFILE IS NOT RECOMMENDED IF OTHER EXISTING UTILITIES OR OBSTRUCTIONS ARE ENCOUNTERED DURING THE WORK. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF ALL EXISTING UTILITIES PRIOR TO INSTALLING THE SEWER PIPELINE SO THAT AN ACCEPTABLE PROFILE CAN BE ESTABLISHED PRIOR TO INSTALLATION OF THE PIPELINE.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO FIELD LOCATE ALL UNDERGROUND UTILITIES, SHOWN OR NOT SHOWN IN THE PLANS, AND COORDINATE HIS WORK WITH ALL UTILITY COMPANIES, EL PASO WATER UTILITIES AND CITY OF EL PASO PRIOR TO CONSTRUCTION. ALL EXISTING UTILITY DEPTHS ARE UNKNOWN. THE CONTRACTOR SHALL BE ULTIMATELY RESPONSIBLE FOR ACQUIRING FIELD DEPTHS OF ALL UTILITIES WITH THE PROJECT AREAS.
- TRENCH SAFETY REQUIREMENTS SHALL COMPLY WITH CURRENT OSHA REGULATIONS.
- AS-BUILT STATIONING, OFFSET FROM R.O.W. AND INVERT ELEVATIONS SHALL BE ACCURATELY RECORDED BY THE CONTRACTOR ON A CLEAN SET OF PLANS FOR EACH MANHOLE, SERVICE CONNECTION AND/OR STUB-OUT, WITH RESPECT TO THE APPROPRIATE PROJECT CONTROL POINT.
- THE EL PASO WATER UTILITIES AND CITY OF EL PASO MUST BE NOTIFIED FORTY-EIGHT (48) HOURS PRIOR TO COMMENCING ANY WORK IN AREAS WITHIN THEIR JURISDICTION. A COPY OF ALL FIELD SOIL DENSITY TESTS WITHIN THEIR RESPECTIVE R.O.W. SHALL BE FORWARDED TO THE DEVELOPER'S ENGINEER AND THE DEVELOPER BY THE CONTRACTOR.
- EXISTING STREETS, DRIVEWAYS AND ALL OTHER MISCELLANEOUS STRUCTURES DAMAGE OR REMOVED BY CONSTRUCTION ACTIVITIES SHALL BE RESTORED TO ORIGINAL OR BETTER THAN ORIGINAL CONDITION.
- CONSTRUCTION OF THE PUBLIC WATER AND SEWER SYSTEM INCLUDING MATERIALS AND TESTING SHALL CONFIRM TO EPWU-PSB STANDARD SPECIFICATIONS FOR THE INSTALLATION OF WATER MAINS, SEWER MAINS AND RELATED APPURTENANCES.

GENERAL UTILITIES:
TEXAS EXCAVATION SAFETY SERVICE
11884 GREENVILLE AVENUE
DALLAS, TX 75243
(800) 344-8377

ENGINEER:
CEA GROUP
CASTNER CENTER @ TRANSMOUNTAIN
4712 WOODROW BEAN, STE. F
EL PASO, TX 79902
(915) 544-5232
MR. JORGE L. AZCARATE, P.E.

FIBER OPTICS:
U.S. SPRINT
151 N. BOONE ST.
EL PASO, TX 79905
(915) 534-7910

FIBER OPTICS:
MCI TELECOMMUNICATIONS CORP.
4045 DONIPHAN PARK CIRCLE
EL PASO, TX 79922
(915) 542-2770 EXT. 201

WATER & SEWER:
EL PASO WATER UTILITIES
1154 HAWKINS BOULEVARD
EL PASO, TX 79961
(915) 594-5530

ELECTRIC:
EL PASO ELECTRIC CO.
501 W. SAN ANTONIO ST.
EL PASO, TX 79902
(915) 543-2076

EL PASO STREETS
CITY OF EL PASO
STREET & MAINTENANCE
7969 SAN PAULINO DRIVE
EL PASO, TX 79907
(915) 621-6750

CABLE TELEVISION:
TIME WARNER COMMUNICATIONS
7010 AIRPORT ROAD
EL PASO, TX 79906
(915) 772-1123

TELEPHONE:
SBC
11200 PELICANO
EL PASO, TX 79935
(915) 595-5151

FIBER OPTICS:
AT&T
P.O. BOX 1650
EL PASO, TX 79949
(800) 852-3786

RESIDENTIAL GAS LINES:
TEXAS GAS SERVICE
4700 POLLARD ST.
EL PASO, TX 79930
(915) 680-7218

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES



INDEX

SHEET NO.	DESCRIPTION
C12.1	LA PUESTA DEL SOL UNIT THREE LEGEND INDEX / GENERAL INFORMATION LINE A
C12.2	LINE B & C
C12.3	SANITARY SEWER DETAILS
C12.4	SANITARY SEWER DETAILS
C12.5	SANITARY SEWER DETAILS
C12.6	SANITARY SEWER DETAILS

NOTES:

- ALL LOTS SHALL BE PROVIDED WITH ONE SERVICE CONNECTION TO BE INSTALLED AT THE LOCATION AS SHOWN ON THE SERVICE LOCATION DETAIL.
- ALL SANITARY SEWER PIPES SHALL BE PVC, SDR 35, (D 3034), UNLESS OTHERWISE SHOWN, AS REQUIRED BY THE EPWU/PSB RULES AND REGULATIONS AND DESIGN STANDARDS.
- REFERENCE SANITARY SEWER DETAILS FOR SEWER CROSSINGS AT STORM SEWER.
- FOR LOTS 43-57, BLOCK 17, LOTS 4-6, BLOCK 22 (FUTURE LA PUESTA DEL SOL UNIT THREE), AN 8" STEEL CASING SHALL BE INSTALLED AT SEWER SERVICE LINE UNDERNEATH THE CULVERT.

LEGEND



REFERENCES - BENCHMARKS

DATE	REVISIONS	BY

CITY MONUMENT AT THE INTERSECTION OF PASO DEL NORTE & NORTHWESTERN; ELEVATION = 3987.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

TECHNICAL DRAFTER

JORGE L. AZCARATE
REGISTERED PROFESSIONAL ENGINEER
STATE OF TEXAS
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5232 | www.ceagroup.net

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SCALE

Vertical: Contour Interval: N/A

Horizontal: DATE: DECEMBER 2018

DESIGN BY: C.J. M.R.G.

DRAWN BY: J.L.A.

CHKD. BY: J.L.A.

APPD. BY: J.L.A.

JOB NO. 2000-210

SHEET TITLE


SEWER INDEX

SHEET NO.

C12.1

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\C12.1-Sewer Index-1.dwg, 7/9/2019 2:28:34 PM


S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG5\Construction Drawings\La Puesta U4 Improvements\12.2-line A Sewer P&P.dwg, 7/9/2019 2:42:11 PM



UTILITY LOCATOR SERVICES

EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES







REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL SOL AND PLAYA TRONONES DRIVE
(CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
ELEVATION = 3935.48 (CITY DATUM)

DATE	REVISIONS	BY

ENGINEER'S SEAL

TEXAS REGISTERED ENGINEERING FIRM F-454
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5222 | www.cesagroup.net



SCALE
Horizontal: 1"=40'
Vertical: 1"=5'

Contour Interval: N/A
DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APPVD. BY: J.L.A.
JOB No. 2000-210

PROJECT TITLE
LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS

SHEET TITLE
LINE A
SANITARY SEWER
PLAN & PROFILE

SHEET NO.
C12.2

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASO DEL SOL AND IXTAPA STREETS ON NGS MONUMENT "CHINO"
ELEVATION = 3935.48 (CITY DATUM)

ca
TEXAS REGISTERED ENGINEERING FIRM F-4684
4712 Woodrow Bean Ste F El Paso, TX 79924
915.544.5232 | www.caengr.com






ENGINEER'S SEAL
Jorge L. Azcarate
Professional Engineer
No. 1075
State of Texas

SCALE: 1"=40'
Horizontal: 1"=5'
Vertical: 1"=5'
Contour Interval: N/A
DATE: DECEMBER 2018
DESIGN BY: C.J.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APP'D. BY: J.L.A.
JOB No.: 2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**SANITARY SEWER
PLAN & PROFILE
LINE B & C**

SHEET NO.
C12.3



S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG3\Construction Drawings\La Puesta U4 Improvements\C12.3-Line B & C Sewer Pkg-1.dwg, 7/9/2019 11:55:22 AM

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

DATE	REVISIONS	BY

GENERAL NOTES:

- MATCHING SURFACES MARKED "MF" TO BE FINISHED OF ANY IRREGULARITIES THAT WOULD PREVENT A SNUG FIT.
- CASTING TO BE SMOOTH & VOID OF AIR HOLES.
- CASTING MUST MEET REQUIREMENTS OF AASHTO M306-07.
- AS-CAST DIMENSIONS MAY VARY $\frac{1}{8}$ " ± / PER FOOT (AASHTO M306-07).
- WEIGHT MAY VARY 5% ± (AASHTO M306-07).

MANHOLE RING	MANHOLE - ALL TYPES	*MANHOLE TYPE A, A1, A2 & C
A	33"	25 $\frac{1}{2}$ "
B	31 $\frac{3}{4}$ "	24 $\frac{1}{8}$ "
C	31 $\frac{1}{2}$ "	23 $\frac{3}{8}$ "
D	30"	22 $\frac{1}{2}$ "
E	30 $\frac{1}{2}$ "	32"
F	5 $\frac{1}{8}$ "	1 $\frac{1}{8}$ "
WEIGHT	205 lbs.	170 lbs.

*OBsolete - DO NOT USE (FOR REFERENCE ONLY)

STANDARD DETAIL DATE: 11/1992 REV: 2/21/2011 SEWER MANHOLE RING N.T.S. el paso WATER DETAIL No. 377

1 STANDARD MANHOLE RING SCALE: N.T.S.

GENERAL NOTES:

- MATCHING SURFACES MARKED "MF" TO BE FINISHED OF ANY IRREGULARITIES THAT WOULD PREVENT A SNUG FIT.
- CASTING TO BE SMOOTH & VOID OF AIR HOLES.
- CASTING MUST MEET REQUIREMENTS OF AASHTO M306-07.
- AS-CAST DIMENSIONS MAY VARY $\frac{1}{8}$ " ± / PER FOOT (AASHTO M306-07).
- WEIGHT MAY VARY 5% ± (AASHTO M306-07).

CONSTRUCTION KEY NOTES:

- LIFTING NOTCH.
- $\frac{3}{8}$ " RAISED LETTERING.
- 1" SQUARES ($\frac{1}{4}$ " TALL) WITH $\frac{5}{8}$ " SPACE BETWEEN.
- REINFORCING RIBS.
- SLOT.

MANHOLE COVER	MANHOLE - ALL TYPES	*MANHOLE TYPE A, A1, A2 & C
A	31 $\frac{3}{8}$ "	23 $\frac{3}{8}$ "
B	28 $\frac{1}{8}$ "	20 $\frac{3}{8}$ "
C	24 $\frac{3}{8}$ "	16 $\frac{3}{8}$ "
D	21 $\frac{3}{8}$ "	14 $\frac{3}{8}$ "
WEIGHT	200 lbs.	165 lbs.

*OBsolete - DO NOT USE (FOR REFERENCE ONLY)

STANDARD DETAIL DATE: 11/1992 REV: 2/21/2011 SEWER MANHOLE COVER N.T.S. el paso WATER DETAIL No. 378

2 STANDARD COVER DETAIL SCALE: N.T.S.

GENERAL NOTES:

- IN GROUNDWATER CONDITIONS ONLY, P.V.C. SADDLES OR TEES ARE TO BE ENCASED WITH CLASS B CONCRETE.
- UNDER CERTAIN CONDITIONS FIELD INVESTIGATIONS WILL BE REQUIRED TO DETERMINE THE ADEQUACY OF THE DEPTH ON THE LATERAL.
- WHEN GROUND WATER IS ENCOUNTERED SERVICE RISER SHALL BE EXTENDED ABOVE ANTICIPATED WATER TABLE LEVEL.

CONSTRUCTION KEY NOTES:

- CONTRACTOR TO INSTALL SEWER SERVICE LINE FROM THE MAIN TO A LOCATION 6" BEHIND THE CURB OR 18" BEYOND THE EDGE OF PAVEMENT, UNLESS CONDITIONS REQUIRE OTHERWISE.
- 18" FOR STANDARD SUBDIVISION, 3.5' FOR SUBDIVISIONS WITH ON-SITE PONDING OR FLAT TERRAIN.
- RISERS OR LATERALS EXTENDING BEYOND EXISTING PAVING SHALL BE INSTALLED TO 3.5' MINIMUM TOP OF GROUND OR PAVEMENT, UNLESS CONDITIONS REQUIRE OTHERWISE.
- PLASTIC METALLIC MARKING TAPE RISING TO WITHIN 6" OF GROUND SURFACE OR METALLIC DISK.
- WOODEN STAKE (1"x2"x36") VERTICALLY PLACED AT PLUGGED END OF PROPOSED SERVICE LINE.

STANDARD DETAIL DATE: 11/1992 REV: 1/23/2009 SEWER SERVICE RISER AND SERVICE LINE CONNECTION N.T.S. el paso WATER DETAIL No. 391

3 SEWER SERVICE RISER AND SERVICE LINE CONNECTION SCALE: N.T.S.

GENERAL NOTES:

- MANHOLE CONNECTOR SHALL BE KOR-N-SEAL OR EQUAL MEETING THE REQUIREMENTS OF ASTM C-923. CONNECTOR SHALL BE FURNISHED BY CONTRACTOR.

CONSTRUCTION KEY NOTES:

- PRECAST MANHOLE BARREL.
- FLEXIBLE CONNECTOR.
- PIPE CLAMP SS 316.
- APPROVED PIPE.
- PRECAST MANHOLE BASE.
- GROUT AS REQUIRED TO FORM SMOOTH CHANNEL TO MANHOLE INVERT.
- PIPE OPENINGS/KNOCKOUTS AS REQUIRED TO FIT PIPE SIZE.
- EXPANSION BAND SS 316.
- FILL SPACE WITH GROUT.


STANDARD DETAIL DATE: 11/1992 REV: 8/13/2009 PIPE CONNECTION TO MANHOLE N.T.S. el paso WATER DETAIL No. 376

4 PIPE CONNECTION TO MANHOLE SCALE: N.T.S.

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASCO DEL NORTE & NORTHWESTERN. ELEVATION = 3987.39
CHINO ELEVATION = 3935.48 (CITY DATUM)

TECHNICAL SERVICES GROUP
TEXAS REGISTERED ENGINEERING FIRM #484
4712 Woodrow Bean, Ste. F El Paso, TX 79924
915.544.5232 | www.cesgroup.net



SCALE	N/A
Horizontal:	N/A
Vertical:	N/A
Contour Interval:	N/A
DATE:	DECEMBER 2018
DESIGN BY:	C.J.
DRAWN BY:	M.R.G.
CHKD. BY:	J.L.A.
APPRD. BY:	J.L.A.
JOB No.	2000-210

PROJECT TITLE

**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE

**SANITARY SEWER
DETAILS**

(SHEET 1 OF 3)

SHEET NO.



Final Approval


C12.4

UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 498-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3788
U.S. SPRINT TELECOMM	(800) 521-0579




WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES

DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASO DEL SOL (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO"
ELEVATION = 3935.48 (CITY DATUM)



SCALE	N/A
Horizontal:	N/A
Vertical:	N/A
Contour Interval:	N/A
DATE:	DECEMBER 2018
DESIGN BY:	C.J.
DRAWN BY:	M.R.G.
CHKD. BY:	J.L.A.
APPVD. BY:	J.L.A.
JOB No.	2000-210






1 C12.5 SEPARATION DISTANCE-POTABLE WATER, SANITARY SEWER AND RECLAIMED WATER SCALE: N.T.S.

2 C12.5 STANDARD MANHOLE TYPE "A1" SCALE: N.T.S.

3 C12.5 BEDDING CLASS DETAILS FOR FOR P.V.C. PRESSURE PIPE SCALE: N.T.S.



Final Approval



4 C12.5 SEPARATION DISTANCE SANITARY SEWER AND POTABLE WATER (SPECIAL CONDITIONS) SCALE: N.T.S.

5 C12.5 STANDARD MANHOLE RING AND COVER INSTALLATION DETAIL SCALE: N.T.S.

6 C12.5 PAVEMENT REPAIR DETAIL SCALE: N.T.S.

PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**SANITARY SEWER
DETAILS**
(SHEET 2 OF 3)
SHEET NO.

C12.5

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta 04 Improvements\C12.5-Sanitary Sewer Details.dwg, 7/9/2019 10:38:49 AM


UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 660-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES


DATE	REVISIONS	BY

REFERENCES - BENCHMARKS
CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTERN ELEVATION = 3867.39 (CITY DATUM). THIS IS BASED ON NOS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)


TECHNICAL SERVICES GROUP
TEXAS REGISTERED ENGINEERING FIRM F-4694
4712 Woodrow Bean St. El Paso, TX 79924
915.544.5232 | www.cesgroup.net



1 STORM SEWER CROSSING UNDER SANITARY LINE DETAIL
C12.6 SCALE: N.T.S.



2 STORM SEWER CROSSING OVER SANITARY LINE DETAIL
C12.6 SCALE: N.T.S.




- GENERAL NOTES:**
- DROP CONNECTION SHOWN MAY BE USED ON ALL MANHOLE TYPES (NOT RECOMMENDED IN GROUND WATER CONDITIONS).
 - DROP CONNECTION TO BE CONSTRUCTED WHEN INVERT ELEVATION OF INFLUENT PIPE IS 3 FEET (OR GREATER) ABOVE THE MANHOLE INVERT.
- CONSTRUCTION KEY NOTES:**
- PIPE OPENINGS IN MANHOLE RISERS SHALL HAVE COMPRESSION TYPE FLEXIBLE PIPE TO MANHOLE CONNECTORS (A.S.T.M. - C923) "KOR-N-SEAL" OR APPROVED EQUAL.
 - MANHOLE WALL
 - INFLUENT SEWER PIPE
 - 90° BEND (P.V.C.)
 - P.V.C. PIPE (SDR 35)
 - P.V.C. TEE
 - CONCRETE FLOWABLE FILL
 - 2500 PSI CONCRETE
 - USE GROUT TO FORM A SMOOTH CHANNEL TO MANHOLE INVERT

STANDARD DATE: 3/18/1998
DETAIL REV: 6/19/2009

DROP CONNECTION - EXTERNAL
MANHOLE INSTALLATION


N.T.S. **el paso WATER** DETAIL No. 375-1

3 DROP CONNECTION MANHOLE
C12.6 SCALE: N.T.S.



- NOTES:**
- CONTRACTOR TO FORM SMOOTH CHANNEL WITH GROUT TO CONTINUE PIPE SLOPE IN THE DIRECTION OF FLOW.
 - WIDTH OF CHANNEL TO MATCH INSIDE DIAMETER OF PIPE.
 - WHEN DIFFERENT SIZES OF PIPE ARE CONNECTING TO MANHOLE, TAPER WIDTH OF CHANNEL TO TOTAL LENGTH OF INSIDE DIAMETER OF MANHOLE.
 - GROUT TO BE USED FOR BOTH MANHOLES AND DROP MANHOLES. NO P.V.C. PIPE SHALL BE INSTALLED IN MANHOLE.
 - REFER TO PLAN & PROFILE SHEETS FOR SIZE OF PIPES AND MANHOLES.

4 TYPICAL MANHOLE INVERT PLANS
C12.6 SCALE: N.T.S.



SCALE	N/A
Horizontal:	N/A
Vertical:	N/A
Contour Interval:	N/A
DATE:	DECEMBER 2018
DESIGN BY:	C.J.
DRAWN BY:	M.R.G.
CHKD. BY:	J.L.A.
APPVD. BY:	J.L.A.
JOB No.	2000-210

PROJECT TITLE
**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**SANITARY SEWER
DETAILS**

(SHEET 3 OF 3)

SHEET NO.

C12.6

S:\2000\2000-210-La Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta U4 Improvements\C12.6-Sanitary Sewer Details.dwg, 7/19/2019 10:37:07 AM

SITE DESCRIPTION

PROJECT NAME AND LIMITS: LA PUESTA DEL SOL UNIT FOUR IS BORDERED BY A PORTION OF TRACT 1A, NELLIE D. MUNDY SURVEY NO. 240 TO THE NORTH, CANUTILLO HIGH SCHOOL, LA PUESTA DEL SOL UNIT FOUR TO THE EAST, LA PUESTA DEL SOL UNIT TWO TO THE SOUTH, AND A PORTION OF 3A NELLIE D. MUNDY SURVEY NO. 240 TO THE WEST.

PROJECT DESCRIPTION: THE SITE FOR THE NEW SUBDIVISION WILL ENCOMPASS APPROXIMATELY 10.08± ACRES, AND WILL CONTAIN A TOTAL OF 61 RESIDENTIAL LOTS

EXISTING CONDITIONS: THE SITE IS CLEAR OF SITE IMPROVEMENTS AND IS COVERED WITH ITS NATURAL SURROUNDINGS. EXISTING RUNOFF IS TO THE WEST.

MAJOR SOIL DISTURBING ACTIVITIES: MAJOR SOIL DISTURBING ACTIVITIES WILL CONSIST OF CLEARING AND GRUBBING, GRADING FOR BUILDING PAD ELEVATIONS, CONSTRUCTION OF STREETS AND EXCAVATION FOR UTILITIES.

TOTAL PROJECT AREA: 10.08±

TOTAL AREA TO BE DISTURBED: 10.08±

WEIGHTED RUNOFF COEFFICIENT (AFTER CONSTRUCTION): 0.684

EXISTING CONDITION OF SOIL AND VEGETATIVE COVER AND % OF EXISTING VEGETATIVE COVER: THE PROJECT SITE IS LOCATED IN THE VICINITY OF THE DELNORTE-CANUTIO ASSOCIATION. THE SOIL IS NEARLY LEVEL TO STEEP SOILS THAT ARE SHALLOW OR VERY SHALLOW OVER CALICHE OR THAT ARE DEEP AND GRAVELLY THROUGHOUT; MAINLY ON AND NEAR FOOT SLOPES OF THE FRANKLIN MOUNTAINS.

NAME OF RECEIVING WATERS: LA PUESTA DEL SOL UNIT FOUR SUBDIVISION WILL DISCHARGE INTO STORM SEWER.

EROSION AND SEDIMENT CONTROL

SOIL STABILIZATION PRACTICES

- TEMPORARY SEEDING
- PERMANENT PLANTING, SODDING, OR SEEDING
- MULCHING
- SOIL RETENTION BLANKET
- BUFFER ZONES
- PRESERVATION OF NATURAL RESOURCES

OTHER: _____

STRUCTURAL PRACTICES:

- SILT FENCES
- HAY BALES
- ROCK BERMS
- DIVERSION, INTERCEPTOR, OR PERIMETER DIKES
- DIVERSION, INTERCEPTOR, OR PERIMETER SWALES
- DIVERSION DIKE AND SWALE COMBINATION
- PIPE SLOPE DRAINS
- CONCRETE FLUMES
- ROCK BEDDING AT CONSTRUCTION EXIT
- TIMBER MATTING AT CONSTRUCTION EXIT
- CHANNEL LINERS
- SEDIMENT TRAPS
- SEDIMENT BASINS
- STORM INLET SEDIMENT TRAP
- STONE OUTLET STRUCTURES
- CURBS AND GUTTERS
- STORM DRAINS
- VELOCITY CONTROL DEVICES
- VEGETATED SWALES & NATURAL DEPRESSIONS

OTHER: _____

NARRATIVE - SEQUENCE OF CONSTRUCTION (STORM WATER MANAGEMENT) ACTIVITIES:

1. INSTALL TEMPORARY EROSION AND SEDIMENT CONTROLS (e.g. SILT FENCE AND/OR EARTHEN BERM, AND STABILIZED CONSTRUCTION ENTRANCE) ;
2. PERFORM CLEARING AND GRUBBING;
3. EXCAVATION FOR UTILITIES;
4. COMPLETE STREET AND LOT GRADING;
5. CONSTRUCTION OF SUBDIVISION IMPROVEMENTS; AND,
6. WHEN ALL CONSTRUCTION ACTIVITY RELATED IN DEVELOPMENT OF THE SITE IS COMPLETE, REMOVE TEMPORARY CONTROLS IN 1. ABOVE.

SWPPP GENERAL NOTES:

1. PLACEMENT OF SILT FENCE SHALL BE ADJUSTED AS NECESSARY TO PREVENT THE BLOCKING OF DRIVEWAYS OR DRIVING LANES.
2. THE SWPPP MANUAL IDENTIFIES THE DUTIES AND RESPONSIBILITIES OF THE GENERAL CONTRACTOR IN COMPLIANCE WITH FEDERAL, STATE AND LOCAL REGULATIONS. THIS ITEM SHALL BE SUBSIDIARY TO THE SWPPP BEST MANAGEMENT PRACTICES (COMPLETE IN PLACE) ITEMS. THE SWPPP PROJECT MANUAL IS AVAILABLE FOR REVIEWING AT THE CITY OF EL PASO-ENGINEERING DEPARTMENT. UPON SELECTION, THE CONTRACTOR WILL BE PROVIDED AN SWPPP MANUAL. THE CONTRACTOR SHALL MAINTAIN THIS MANUAL AT THE CONSTRUCTION SITE AT ALL TIMES THROUGHOUT THE CONSTRUCTION PERIOD.
3. THE CONTRACTOR SHALL COMPLETE AND SUBMIT ALL REGULATORY FORMS AND APPLICATIONS, AS PROVIDED IN THE SWPPP MANUAL, INCLUDING, BUT NOT LIMITED TO; NOI, NOT, SDPCP, AND ANY OTHER FORM REQUIRED BY THE CITY OF EL PASO AND TCEQ.
4. ALLOWABLE STORM WATER AND NON-STORMWATER DISCHARGE SHALL COMPLY WITH 15.20.080 (GENERAL PROHIBITION) AND 15.20.090 (SPECIFIC PROHIBITIONS AND REQUIREMENTS) OF THE CITY OF EL PASO STORM DRAIN POLLUTION CONTROL PLAN ORDINANCE. NON-STORMWATER DISCHARGES MAY CONSIST OF, BUT ARE NOT LIMITED TO, THE DISCHARGE RESULTING FROM FIREFIGHTING, LAWN WATERING, LANDSCAPE IRRIGATION, NATURAL SPRING, AND/OR AGRICULTURAL STORM WATER RUNOFF.
5. REFER TO DRAINAGE PLAN SHEET, FOR DETAILED INFORMATION ON WATERSHED AREAS AND RUNOFF QUANTITIES (Q).
6. THE FOLLOWING HAVE BEEN IDENTIFIED AS POTENTIAL CONTAMINATION SOURCES: CLEARED AND GRADED AREAS; CONSTRUCTION SITE ENTRANCE AND ASPHALT PARKING AREA CONSTRUCTION; ASPHALT LOADING/UNLOADING AREAS; CONCRETE LOADING/UNLOADING AREAS; AND, ALL UNDISTURBED AREAS.
7. THE FOLLOWING IS A LIST OF POTENTIAL CONSTRUCTION SITE STORM WATER POLLUTANTS: ASPHALT; CONCRETE; GLUE/ADHESIVE; PAINTS; CURING COMPOUNDS; WASTEWATER FROM CONSTRUCTION EQUIPMENT WASHING; HYDRAULIC OIL/FLUIDS; ;GASOLINE; DIESEL FUEL; KEROSENE; ANTIFREEZE/COOLANT; AND EROSION.

BEST MANAGEMENT PRACTICES CONTROLS



1. STRUCTURAL MEASURES SHALL BE MAINTAINED THROUGHOUT THE LIFE OF THE PROJECT IN EFFECTIVE OPERATING CONDITION.
2. DOCUMENTATION OF MAINTENANCE ACTIVITIES INCLUDING FREQUENCY, LOT DESIGNATION, STRUCTURAL CONTROLS, MATERIAL; STORAGE AREAS, VEHICLES ENTRANCE AND EXIST: ACTIONS TAKEN AND INSPECTOR'S NAME.
3. CONSTRUCTIONS SITE NOTICE WILL BE MAINTAINED ON SITE.
4. COPY OF SWPPP SHALL BE KEPT ON SITE.
5. PERMITEE MUST RETAIN THE SWPPPS NOI AND INSPECTION LOG FOR A MINIMUM OF 3 YEARS FROM THE TERMINATION AND FINAL STABILIZATION OF PROJECT

- I. **WASTE MATERIALS:**
ALL WASTE MATERIALS, INCLUDING CONSTRUCTION DEBRIS, SHALL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER. NO CONSTRUCTION WASTE MATERIAL SHALL BE BURIED ON SITE. THE TRANSIT DUMPSTER SHALL COMPLY WITH ORDINANCE 18.52.010 (ENCLOSURE AND REMOVAL OF WASTE MATERIALS DURING CONSTRUCTION). THE DUMPSTER SHALL BE EMPTIED AS NECESSARY OR AS REQUIRED BY ORDINANCE 9.04 (SOLID WASTE MANAGEMENT) AND THE TRASH SHALL BE HAULED TO A LICENSED LANDFILL.
- II. **HAZARDOUS WASTE:**
AT A MINIMUM, ANY PRODUCTS IN THE FOLLOWING CATEGORIES SHALL BE CONSIDERED HAZARDOUS: PAINT, ACIDS FOR CLEANING MASONRY SURFACES, CLEANING SOLVENTS, ASPHALT PRODUCTS, CHEMICAL ADDITIVES FOR SPILL STABILIZATION, CURING COMPOUNDS AND ADDITIVES. IN THE EVENT OF A SPILL WHICH MAY BE HAZARDOUS, THE CONTRACTOR SHALL TAKE IMMEDIATE ACTION AND CONTACT THE FIRE DEPT. AND TNRC.
- III. **SANITARY WASTE:**
ALL SANITARY WASTE SHALL BE COLLECTED FROM THE CONSTRUCTION PORTABLE UNITS AS NECESSARY OR AS REQUIRED, CHAPTER 18.08 (BUILDING CODE), BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR. ALL WASTE MATERIAL SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- IV. **SPILL PREVENTION:**
THE FOLLOWING PRACTICES SHALL BE USED TO REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURES OF MATERIALS TO STORM WATER RUNOFF.
- V. **GOOD HOUSEKEEPING:**
 - A. STORE ONLY ENOUGH PRODUCTS REQUIRED TO DO THE JOB
 - B. NEATLY STORE MATERIALS ON-SITE IN AN ORDERLY MANNER
 - C. KEEP PRODUCTS IN THEIR ORIGINAL CONTAINER
 - D. DO NOT MIX SUBSTANCES WITH ONE ANOTHER, UNLESS OTHERWISE RECOMMENDED BY THE MANUFACTURER
 - E. USE ENTIRE CONTENTS OF A PRODUCT BEFORE DISPOSING THE CONTAINER
 - F. FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL
- VI. **HAZARDOUS PRODUCTS:**
PRACTICES USED TO REDUCE RISKS:
 - A. KEEP PRODUCTS IN THEIR ORIGINAL CONTAINER IF AT ALL POSSIBLE
 - B. RETAIN ORIGINAL LABELS, PRODUCT INFORMATION AND MATERIAL SAFETY DATA SHEETS (MSDS)
 - C. DISPOSE SURPLUS PRODUCT IN ACCORDANCE WITH MANUFACTURER'S OR LOCAL & STATE RECOMMENDED METHODS
- VII. **PETROLEUM PRODUCTS:**
ALL ON-SITE VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ON-SITE SHALL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATION.
- VIII. **SPILL CONTROL PRACTICES:**
 - A. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY POSTED AND SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES:
 - B. MATERIALS AND EQUIPMENT NECESSARY FOR CLEANUP SHALL BE KEPT IN THE MATERIAL STORAGE AREA ON-SITE:
 - C. ALL SPILLS SHALL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY
 - D. SPILL AREA SHALL BE WELL VENTILATED AND APPROPRIATE CLOTHING WILL BE WORN:
 - E. ANY SPILL SHALL BE REPORTED TO THE APPROPRIATE GOVERNMENTAL AGENCY
 - F. MEASURES SHALL BE TAKEN TO PREVENT A SPILL FROM REOCCURRING
- IX. **MAINTENANCE AND INSPECTION PROCEDURES:**
ALL POLLUTION PREVENTION MEASURES SHALL BE INSPECTED AT LEAST ONCE A MONTH OR WITHIN 24-HOURS PRIOR TO ANTICIPATED STORM EVENT AND FOLLOWING A STORM EVENT OF 0.5 INCHES OR MORE. INSPECTION IN FINAL STABILIZED AREAS OR DURING ARID PERIODS WILL BE CONDUCTED MONTHLY, BEST MANAGEMENT PRACTICES AND POLLUTION CONTROL PROCEDURES SHALL BE INSPECTED FOR ADEQUACY.
- X. **REMARKS:**
DISPOSAL AREAS, STOCKPILES, AND HAUL ROADS SHALL BE CONSTRUCTED IN A MANNER THAT WILL MINIMIZE AND CONTROL THE AMOUNT OF SEDIMENT THAT MAY ENTER RECEIVING WATERS. DISPOSAL AREAS SHALL NOT BE LOCATED IN ANY WETLAND, WATERBODY OR STREAMBED. CONSTRUCTION STAGING AREAS AND VEHICLE MAINTENANCE AREAS SHALL BE CONSTRUCTED BY THE CONTRACTOR IN A MANNER TO MINIMIZE THE RUNOFF OF POLLUTANTS. ALL WATERWAYS SHALL BE CLEANED AS SOON AS PRACTICABLE OF TEMPORARY EMBANKMENT, TEMPORARY BRIDGES, MATTING, FALSEWORK, PILING DEBRIS OR OTHER OBSTRUCTIONS PLACED DURING CONSTRUCTION OPERATIONS THAT ARE NOT A PART OF THE FINISHED WORK.
- XI. **OFFSITE VEHICLE TRACKING:**
IN ADDITION TO THE STABILIZED CONSTRUCTION ENTRANCES, THE FOLLOWING MEASURES SHALL BE OBSERVED DURING CONSTRUCTION:
 - HAUL ROADS SHALL BE DAMPENED FOR DUST CONTROL
 - LOADED HAUL TRUCKS SHALL BE COVERED WITH TARPULIN
 - EXCESS DIRT ON ROAD SHALL BE REMOVED IMMEDIATELY
 - STABILIZED CONSTRUCTION ENTRANCE
 - OTHER: _____



REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASEO DEL NORTE & NORTHWESTER. ELEVATION = 3887.39 (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO".	ELEVATION = 3835.48 (CITY DATUM)
DATE	REVISIONS
BY	



SCALE

Horizontal:	Vertical:
Contour Interval: N/A	Contour Interval: N/A
DATE: DECEMBER 2018	DESIGN BY: C.J.
DRAWN BY: M.R.G.	CHKD. BY: J.L.A.
APPVD. BY: J.L.A.	JOB No. 2000-210

PROJECT TITLE

LA PUESTA DEL SOL UNIT FOUR SUBDIVISION IMPROVEMENTS

SHEET TITLE

STORM SEWER POLLUTION PREVENTION PLAN: NOTES

SHEET NO.


C13.1

S:\2000\2000-210-Lo Puesta Del Sol Unit Three\DWG\Construction Drawings\La Puesta Ut Improvements\C13.2-SWPS Site Plan.dwg, 7/9/2019 10:40:08 AM

TRACT 1A,
CITY OF EL PASO
VOL. 1272 PG. 555

A PORTION OF TRACT 3A,
NELLE D. MUNDY SURVEY NO. 240
EL PASO COUNTY, TEXAS
BERNARD L. FENEBOCK
VOL. 4220 PG. 0984

NELLE D. MUNDY
SURVEY NO. 240
EL PASO COUNTY,
TEXAS



UTILITY LOCATOR SERVICES	
EL PASO ELECTRIC COMPANY	(915) 543-5720
EL PASO ENERGY CORPORATION	(915) 496-5244
EL PASO WATER UTILITIES	(915) 594-5500
MCI SURVEILLANCE	(800) MCI-WORK
TIME WARNER COMMUNICATIONS	(915) 772-1123
TEXAS GAS SERVICE	(915) 680-7200
SBC	(800) 545-6005
AT&T	(800) 852-3786
U.S. SPRINT TELECOMM	(800) 521-0579

WARNING!
BEFORE YOU DIG
CALL 811
FOR FIELD LOCATING EXISTING UTILITIES


- LEGEND:**
- SILT FENCE OR EARTHEN BERM
 - STABILIZED CONSTRUCTION ENTRANCE
 - STAGING AREA
 - PORTABLE TOILETS
 - WASH OUT
 - NOTICE OF INTENT

REFERENCES - BENCHMARKS

CITY MONUMENT AT THE INTERSECTION OF PASO DEL SOL AND ISELE RUBALCAVA STREET (CITY DATUM). THIS IS BASED ON NGS MONUMENT "CHINO" ELEVATION = 3935.48 (CITY DATUM)

DATE	REVISIONS	BY

CEA GROUP, INC.
TEXAS REGISTERED ENGINEERING FIRM F-4664
4712 Woodrow Bean, Ste. F, El Paso, TX 79904
915.544.5232 | www.ceagroup.net



SCALE: 1" = 100'

Horizontal: N/A
Vertical: N/A
Contour Interval: N/A

DATE: DECEMBER 2018
DESIGN BY: C.J.G.
DRAWN BY: M.R.G.
CHKD. BY: J.L.A.
APP'D. BY: J.L.A.
JOB NO.: 2000-210

PROJECT TITLE

**LA PUESTA DEL SOL
UNIT FOUR
SUBDIVISION IMPROVEMENTS**

SHEET TITLE

**STORM SEWER
POLLUTION
PREVENTION PLAN:
SITE PLAN**


SHEET NO.

SITE PLAN
SCALE: 1" = 100'



C13.2

4' MIN. STEEL OR WOOD POSTS SPACED AT 6' TO 8' O.C.
 SOFTWOOD POSTS SHALL BE 3" MIN. DIA. OR NOMINAL 2"x4".
 HARDWOOD POSTS SHALL HAVE A MIN. CROSS SECTION OF 1.5" X 1.5".



SECTION A-A

CONNECT THE ENDS OF SUCCESSIVE REINFORCEMENT SHEETS OR ROLLS A MIN. OF 6 TIMES WITH HOG RINGS.


GALV. W.W.M. (12.5 GA. MIN.)
 MAX. OPENING SIZE SHALL BE 2" X 4".

ATTACH THE W.W.M. & FABRIC ON END POSTS USING 4 EVENLY SPACED STAPLES FOR WOODEN POSTS (OR 4 T-CLIPS OR SEWN VERTICAL POCKETS FOR STEEL POSTS).


FASTEN FABRIC TO TOP STRAND OF WELDED WIRE MESH (W.W.M.) BY HOG RINGS OR CORD AT A MAX. SPACING OF 15".

PLACE 4" TO 6" OF FABRIC AGAINST THE TRENCH SIDE AND APPROX. 4" ACROSS TRENCH BOTTOM IN UPSTREAM DIRECTION. MINIMUM TRENCH SIZE SHALL BE 6" SQUARE. BACKFILL AND HAND TAMP.

TEMPORARY SEDIMENT CONTROL FENCE



PLAN




PROFILE

GENERAL NOTES

1. THE LENGTH OF THE TYPE 1 CONSTRUCTION EXIT SHALL BE AS INDICATED ON THE PLANS, BUT NOT LESS THAN 50'.
2. THE COARSE AGGREGATE SHOULD BE OPEN GRADED WITH A SIZE OF 4" TO 8".
3. THE APPROACH TRANSITIONS SHOULD BE NO STEEPER THAN 6:1 AND CONSTRUCTED AS DIRECTED BY THE ENGINEER.
4. THE CONSTRUCTION EXIT FOUNDATION COURSE SHALL BE FLEXIBLE BASE, BITUMINOUS CONCRETE, PORTLAND CEMENT CONCRETE OR OTHER MATERIAL AS APPROVED BY THE ENGINEER.
5. THE CONSTRUCTION EXIT SHALL BE GRADED TO ALLOW DRAINAGE TO A SEDIMENT TRAPPING DEVICE.
6. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.


CONSTRUCTION EXIT (TYPE 1)



GENERAL NOTES:

1. SOIL USED IN BERM CONSTRUCTION SHALL BE MACHINE COMPACTED.
2. TOP WIDTH AND HEIGHT OF BERM MAY BE MODIFIED WITH PRIOR APPROVAL OF THE ENGINEER.
3. SIDE SLOPES WITHIN THE SAFETY CLEAR ZONE OF A ROADWAY SHALL BE 6:1 OR FLATTER.
4. GRADING SHALL BE SHOWN ELSEWHERE IN THE PLANS OR AS DIRECTED BY THE ENGINEER.
5. THE ENGINEER RESERVES THE RIGHT TO MODIFY THE DIMENSIONS SHOWN FOR THE BERM DEPENDENT ON RUNOFF VOLUME CHARACTERISTICS.
6. BERM THAT ARE IN PLACE FOR MORE THAN 14 CALENDAR DAYS SHOULD BE STABILIZED TO PREVENT SEDIMENT RUNOFF.
7. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

TYPICAL BERM CONFIGURATION



NOTE:
 WOOD CHIP FILLED MESH BAGS SHALL CONSIST OF 30-40% WEED FREE COMPOST AND 60-70% PARTIALLY DECOMPOSED WOOD CHIPS.

GENERAL NOTES:

1. PLACE CURB TYPE SEDIMENT BARRIERS ON GENTLY SLOPING STREET SEGMENTS, WHERE WATER CAN POND AND ALLOW SEDIMENT TO SEPARATE FROM RUNOFF.
2. INSPECT BARRIERS AND REMOVE SEDIMENT AFTER EACH STORM EVENT. SEDIMENT AND GRAVEL MUST BE REMOVED FROM THE TRAVELED WAY IMMEDIATELY.

TEMPORARY INLET PROTECTION

REFERENCES - BENCHMARKS	
CITY MONUMENT AT THE INTERSECTION OF PASO DEL RIO AND 10TH ST. (CITY DATUM)	
"CHINO" MONUMENT (CITY DATUM)	
ELEVATION = 3935.48 (CITY DATUM)	
DATE	REVISIONS
BY	

ca
 CONSULTANTS
 TEXAS REGISTERED ENGINEERING FIRM F-4664
 4712 Woodrow Bean, Ste. F El Paso, TX 79924
 915.544.5232 | www.caegroup.net

ENGINEER'S SEAL

SCALE	Horizontal: 1" = 10'
Vertical: 1" = 4'	
DATE: DECEMBER 2018	
DESIGN BY: C.J.	
DRAWN BY: M.R.G.	
CHKD. BY: J.L.A.	
APPVD. BY: J.L.A.	
JOB NO. 2000-210	

PROJECT TITLE
**LA PUESTA DEL SOL
 UNIT FOUR
 SUBDIVISION IMPROVEMENTS**

SHEET TITLE
**STORM SEWER
 PREVENTION PLAN:
 DETAILS**

SHEET NO.
C13.3

