


VALLEY CREEK UNIT FIVE

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS,
CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS
CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or Less.

STREET IMPROVEMENT PACKAGE


VICINITY MAP



INDEX OF SHEETS

SHEET TITLE	SHEET NO.
COVER SHEET.....	1
PLAT.....	2
GRADING PLAN.....	3
DRAINAGE PLAN.....	4
GRADING SECTIONS.....	5
TYPICAL GRADING LOT LAYOUTS.....	6
ALTERNATE UNDERGROUND STORAGE CHAMBERS.....	7
VALLEY PINE DRIVE 0+00.00 TO 3+87.51.....	8
TYPICAL DETAILS AND SECTIONS.....	9
TYPICAL DETAILS AND SECTIONS.....	10
ILLUMINATION PLAN.....	11
ILLUMINATION DETAILS.....	12
TRAFFIC SIGN DETAILS.....	13
STORM DRAIN POLLUTION CONTROL PLAN.....	14
STORM DRAIN POLLUTION CONTROL NOTES.....	15

LOCATION MAP



OWNER / DEVELOPER
HAM MANAGEMENT, LLC., THE GENERAL PARTNER
OF UPPER VALLEY CREEK L.P.
RUSSELL HANSON MANAGING PARTNER
 5812 CROMO DRIVE, EL PASO, TEXAS 79912
 P.O. BOX 220630 EL PASO, TEXAS 79913
 (915)-842-0111


bmr **Roe Engineering, L.C.**
 601 N. Cotton St. Suite No.6 El Paso, Tx, 79902
 (915) 533-1418 FAX: (915) 533-4972
 e-mail: roeeng@swbell.net
 ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING

CITY DEVELOPMENT DEPARTMENT

Reviewed For Conformance For Condition Related To:


- Sidewalks
- Grading & Drainage
- Wheelchair Ramps
- On Site Parking Layout
- Driveways
- Retaining Bank Walls
- On Site Ponding of Storm Waters

Contractor Must Call 24 Hours Prior To Construction for Inspections
 12/16/2013



BRADLEY ROE, R.P.L.S. 2449

12/11/2013
DATE:




BRADLEY ROE, P.E. 31886
 ROE ENGINEERING, L.C.
 TEXAS REGISTERED
 ENGINEERING FIRM F-2103

12/11/2013
DATE:


VALLEY CREEK UNIT FIVE

BEING ALL OF TRACT 10 BLOCK 7,
UPPER VALLEY SURVEYS,
CITY OF EL PASO, EL PASO COUNTY, TEXAS

CONTAINING IN ALL 163,753.62 SQUARE FEET
OR 3.7592 ACRES MORE OR LESS



GRAPHIC SCALE



OWNER'S DEDICATION, CERTIFICATION

STATE OF TEXAS
COUNTY OF EL PASO

I, RUSSELL HANSON, MANAGER OF HAM MANAGEMENT, L.L.C., THE GENERAL PARTNER OF UPPER VALLEY CREEK, L.P., PROPERTY OWNER(S) OF THIS LAND HEREBY PRESENT THIS MAP AND DEDICATE TO THE USE OF THE PUBLIC THE STREET RIGHT-OF-WAYS AND UTILITY EASEMENTS AS HEREON LAID DOWN AND DESIGNATED, INCLUDING EASEMENTS FOR OVERHANG OF SERVICE WIRES FOR POLE TYPE UTILITIES, AND BURIED SERVICE WIRES CONDUITS AND PIPES FOR UNDERGROUND UTILITIES AND THE RIGHT TO INGRESS AND EGRESS FOR SERVICE AND CONSTRUCTION AND THE RIGHT TO TRIM INTERFERING TREES AND SHRUBS.

UPPER VALLEY CREEK, L.P.,
BY: HAM MANAGEMENT, L.L.C. ITS GENERAL PARTNER


BY: *Russell Hanson*
RUSSELL HANSON, MANAGER

ACKNOWLEDGMENT

STATE OF TEXAS
COUNTY OF EL PASO

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED RUSSELL HANSON, MANAGER OF HAM MANAGEMENT, L.L.C., THE GENERAL PARTNER OF UPPER VALLEY CREEK, L.P., KNOWN BY ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL THIS 13 DAY OF DECEMBER, 2013 A.D.



BY: *Lilia M. Bueno*
NOTARY PUBLIC IN AND FOR EL PASO COUNTY, TEXAS
MY COMMISSION EXPIRES 7/31/16

CITY PLAN COMMISSION

THIS SUBDIVISION IS HEREBY APPROVED AS TO THE PLATTING AND AS TO THE CONDITIONS OF THE DEDICATION IN ACCORDANCE WITH CHAPTER 212 OF THE LOCAL GOVERNMENT CODE OF TEXAS THIS 13th DAY OF December, 2013 A.D.

EXECUTIVE SECRETARY

CHAIRPERSON

APPROVED FOR FILING THIS 19th DAY OF December, 2013 A.D.

DATE

CITY DEVELOPMENT DIRECTOR

COUNTY CLERK'S RECORDING CERTIFICATE

I, DELIA BRIONES, COUNTY CLERK OF EL PASO COUNTY, CERTIFY THAT THE PLAT BEARING THIS CERTIFICATE WAS FILED AND RECORDED UNDER THE INSTRUMENT NO. 20140001102 IN THE PLAT RECORDS OF THE EL PASO COUNTY.

BY: *Delia Briones* 1/7/14 DATE BY: *Bradley Roe* 1/7/14 DATE
COUNTY CLERK DEPUTY COUNTY CLERK

I HEREBY CERTIFY THAT THIS PLAT REPRESENTS A SURVEY MADE ON THE GROUND UNDER MY SUPERVISION AND IS IN COMPLIANCE WITH THE CURRENT TEXAS BOARD OF PROFESSIONAL LAND SURVEYING, PROFESSIONAL AND TECHNICAL STANDARDS, REGISTERED PUBLIC LAND SURVEYOR No. 2449

Bradley Roe 13 Dec 2013
BRADLEY ROE, R.P.L.S. 2449 DATE




PREPARED BY AND UNDER THE SUPERVISION OF BRADLEY ROE,
REGISTERED PROFESSIONAL ENGINEER No. 31886

Bradley Roe 13 Dec 2013
BRADLEY ROE, P.E. 31886
ROE ENGINEERING, L.C.
TEXAS REGISTERED
ENGINEERING FIRM F-2103

"THIS IS TO CERTIFY THAT WATER AND SEWER SERVICES WILL BE PROVIDED TO VALLEY CREEK UNIT FIVE BY THE EL PASO WATER UTILITIES SERVICE BOARD IN ACCORDANCE WITH THEIR RULES AND REGULATIONS AND WITH SECTION 16.343 OF THE TEXAS WATER CODE. WATER AND SEWER SERVICES WILL BE EXTENDED TO THE SUBDIVISION FROM EXISTING FACILITIES LOCATED ON GOMEZ ROAD AND WILL BE CONSTRUCTED TO SERVE THE SUBDIVISION ON (DATE) 02/20/2014"

"TAX CERTIFICATE(S) FOR THIS SUBDIVISION ARE FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORDS SECTION.

INSTRUMENT NO. 20140001102/4 DATE 1/7/14



- LEGEND
- PROPOSED CITY MONUMENT
 - EXISTING CITY MONUMENT
 - PROPOSED NDCBU
 - DENOTES SET 5/8" Ø REBAR WITH YELLOW PLASTIC CAP STAMPED TX 2449, ROE ENGR, L.C. UNLESS OTHERWISE NOTED.

SCHOOL DISTRICT:
EL PASO INDEPENDENT SCHOOL DISTRICT
6531 BOEING DRIVE, EL PASO, TEXAS 79925
PHONE (915) 230-2000

CURVE TABLE						
CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
C1	56.00	87.72'	55.76'	79.02'	S 44°54'59" E	89°45'00"
C2	20.00	31.33'	19.91'	28.22'	S 44°54'59" E	89°45'00"
C3	300.56	169.02'	86.81'	166.80'	N 24°44'03" E	32°13'14"
C4	30.00	18.28'	9.43'	18.00'	S 17°24'58" W	34°54'55"
C5	70.00	17.02'	8.55'	16.98'	S 27°54'26" W	33°55'59"
C6	70.00	68.05'	36.98'	65.40'	S 26°54'26" E	55°41'45"
C7	70.00	65.97'	35.67'	63.56'	S 61°45'15" E	53°59'54"
C8	70.00	43.93'	22.71'	43.21'	N 73°16'12" E	35°57'12"
C9	30.00	18.28'	9.43'	18.00'	S 72°45'04" W	34°54'55"
C10	30.00	23.86'	12.60'	23.24'	N 67°00'18" W	45°34'23"
C11	50.00	66.53'	39.23'	61.73'	S 82°20'27" E	76°14'22"
C12	50.00	52.00'	28.63'	49.88'	N 29°45'01" E	59°35'01"
C13	50.00	51.99'	28.62'	49.68'	N 28°49'54" W	59°34'51"
C14	50.00	66.10'	38.88'	61.39'	S 82°30'24" W	75°44'32"
C15	30.00	23.86'	12.60'	23.24'	N 67°25'20" E	45°34'23"
C16	30.00	46.99'	29.87'	42.33'	S 44°54'59" E	89°45'00"
C17	20.00	31.50'	20.09'	28.35'	S 45°05'01" W	90°15'00"

LINE TABLE		
LINE	BEARING	LENGTH
L1	N 21°50'31" E	67.91'
L2	N 00°02'29" W	30.00'
L3	N 89°47'29" W	32.99'
L4	N 81°22'34" E	40.00'

GENERAL NOTES:

- POSTAL DELIVERY SERVICE WITHIN VALLEY CREEK UNIT FIVE SUBDIVISION WILL BE PROVIDED USING NEIGHBORHOOD DELIVERY SERVICE AND COLLECTION BOX UNITS.
- SIDEWALKS FOR ALL STREETS WITHIN AND ABUTTING THIS SUBDIVISION WILL BE PROVIDED.
- RESTRICTIVE COVENANTS FOR THIS SUBDIVISION ARE FILED IN THE OFFICE OF THE COUNTY CLERK, DEED AND RECORDS SECTION, INSTRUMENT NO. 20140001102, DATE 1/7/14.
- ALL LOTS WITHIN THIS SUBDIVISION ARE SUBJECT TO ON-SITE PONDING OF STORM WATER AS PER THE EL PASO MUNICIPAL CODE. THE TYPICAL STREET AND LOT DRAINAGE SECTION MUST BE ADHERED TO AND IS SHOWN ON THE DRAINAGE PLANS ON FILE IN THE CITY OF EL PASO DEVELOPMENT SERVICES DEPARTMENT.
- TEN FOOT UTILITY AND PRIVATE IRRIGATION EASEMENT ALONG THE FRONT OF ALL PROPERTY LINES UNLESS OTHERWISE NOTED.
- VEHICULAR ACCESS TO LOT 5 AND 8-11, BLOCK 1, AS THEY ABUTT GOMEZ ROAD, SHALL BE FROM OTHER DEDICATED STREET ONLY. THE INSTRUMENT ASSURING RELEASE OF ACCESS IS FILED IN THE OFFICE OF THE COUNTY CLERK, DEEDS AND RECORDS SECTION, INSTRUMENT NO. _____, DATE _____.
- THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X" (EXPLANATION: AREAS OF 500-YEAR FLOOD AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 48022 0125 B, DATED SEPTEMBER 4, 1991.

ON-SITE PONDING NOTES:

- All lots in the subdivision are subject to on-site ponding. Lot owners are responsible for maintaining adequate provisions to accommodate all stormwater runoff generated from their respective lots plus one-half the runoff generated from all abutting street right-of-ways directly bordering the lot. The pond depth and lot grading requirements are as per approved Grading and Drainage plan for the Subdivision.
- The Site / Grading plan will show that the ponding will have sufficient capacity for a 4 inch 100 year storm. The ponding provided will not be more than 12 inches in depth and will percolate in 72 hours or less based on the test results. If the design criteria for ponding and percolation cannot be achieved then alternate methods may be part of the site plan. Dry Wells and storm water infiltration wells with silted sides for percolation discharge are a few of the methods that can be reviewed for approval.
- Walls constructed abutting street right-of-ways shall be constructed with a series of drain pipes allowing the street runoff to be conveyed to the subject property.
- On-site ponding areas shall have maximum one (vertical) to three (horizontal) side slopes and a maximum depth of twelve (12) inches based on a one hundred year storm.
- Permanent elevation markers shall be installed to define the levels to be maintained to ensure the effectiveness of on-site ponding. Permanent elevation markers shall not be moved, covered, or altered without written permission from the City Engineer.
- The City and/or its Representative is granting permanent right of access to inspect the ponding areas and permanent elevation markers.
- Filling or changing the pond, or allowing the pond to be filled or changed to an elevation greater than established by the permanent elevation markers, is prohibited.
- On-site ponding areas and permanent elevation markers shall be constructed and inspected prior to building occupancy. Permanent Certificate of Occupancy, required to obtain utility services, will be issued only after the City of El Paso has performed the inspection.
- No person shall be permitted to impair the functionality of an on-site pond. No more than fifty-percent (50%) of the area of any residential lot conveyed by deed shall be covered by improvements, either temporary or permanent, which shed stormwater, including but not limited to, buildings, driveways, patios, decks or landscaping underlaid with plastic sheeting or other impermeable material.
- In the event that the functionality of an on-site pond becomes impaired whether by act of man or nature, the owner of the lot on which the impaired pond is located shall perform all corrective actions required to restore that functionality.
- Any owner notified in writing by the City Engineer of corrective actions required to restore the functionality of an on-site pond or drainage problem on the lot shall comply within forty-five calendar days of receipt of such notice, provided, however, that nothing herein shall prevent the City from mandating an earlier time for commencement of completion during times of emergency, where there is imminent danger of loss of life, limb or property.
- Owner of property utilizing on-site ponding waives any claim or cause of action against the City, EPWU-PSB, officials or employees, for any death, injury or property damage resulting from alteration of the ponding capacity for that lot, including lack of maintenance.
- These on-site ponding requirements shall be enforced by injunctive relief without the requirement for bond or other security.
- The conveyance of property permitting on-site ponding shall declare in conspicuous language in the deed that the property is subject to on-site ponding requirements, maintenance of elevation markers, standing water on lot, and ingress and egress for inspection as stated on the plat.

This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and an instrument of services in respect to the project for which it was prepared. This document is not intended or authorized for reuse by any party on extensions of such project or any other project. Any reuse, including copying and/or modifying the document, without written permission from Roe Engineering, L.C. for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.

W:\011411-3
P.L.S. NAME: C-02 VCA_PLAT.DWG
PREPARATION DATE: APRIL 12, 2013
REVISED DATE: DECEMBER 11, 2013

Roe Engineering, L.C.
EL PASO, TEXAS

ON-SITE PONDING NOTES:

- All lots in the subdivision are subject to on-site ponding. Lot owners are responsible for maintaining adequate provisions to accommodate all conveyed by deed generated from their respective lot plus one-half the runoff generated from all abutting street right-of-ways directly fronting the lot. The pond depth and lot grading requirements are as per approved Grading and Drainage plan for the Subdivision.
- The Site / Grading plan will show that the ponding will have sufficient capacity for a 4 inch 100 year storm. The ponding provided will not be more than 12 inches in depth and will percolate in 72 hours or less based on the test results. If the design criteria for ponding and percolation cannot be achieved then alternate methods may be part of the site plan. Dry Wells and storm water infiltration walls with slotted sides for percolation discharge are a few of the methods that can be reviewed for approval.
- Walls constructed abutting street right-of-ways shall be constructed with a series of drain pipes allowing the street runoff to be conveyed to the subject property.
- On-site ponding areas shall have maximum one (vertical) to three (horizontal) side slopes and a maximum depth of twelve (12) inches based on a one hundred year storm.
- Permanent elevation markers shall be installed to define the levels to be maintained to ensure the effectiveness of on-site ponding. Permanent elevation markers shall not be moved, covered, or altered without written permission from the City Engineer.
- The City and/or its Representative is granted permanent right of access to inspect the ponding areas and permanent elevation markers.
- Filling or changing the pond, or allowing the pond to be filled or changed to an elevation greater than established by the permanent elevation markers, is prohibited.
- On-site ponding areas and permanent elevation markers shall be constructed and inspected prior to building occupancy. Permanent Certificate of Occupancy, required to obtain utility services, will be issued only after the City of El Paso has performed the inspection.
- No person shall be permitted to impair the functionality of an on-site pond. No more than fifty-percent (50%) of the area of any residential lot covered by deed shall be covered by improvements, either temporary or permanent, which shed stormwater, including but not limited to, buildings, driveways, patios, decks or landscaping underlaid with plastic sheeting or other impermeable material.
- In the event that the functionality of an on-site pond becomes impaired whether by act of man or nature, the owner of the lot on which the impaired pond is located shall perform all corrective actions required to restore that functionality.
- Any owner notified in writing by the City Engineer of corrective actions required to restore the functionality of an on-site pond or drainage problem on the lot shall comply within forty-five calendar days of receipt of such notice; provided, however, that nothing herein shall prevent the City from mandating an earlier time for commencement of completion during times of emergency, where there is imminent danger of loss of life, limb or property.
- Owner of property utilizing on-site ponding waives any claim or cause of action against the City, EPWU-PSB, officials or employees, for any death, injury or property damage resulting from alteration of the ponding capacity for that lot, including lack of maintenance.
- These on-site ponding requirements shall be enforced by injunctive relief without the requirement for bond or other security.
- The conveyance of property permitting on-site ponding shall declare in conspicuous language in the deed that the property is subject to on-site ponding requirements, maintenance of elevation markers, standing water on lot, and ingress and egress for inspection as stated on the plat.

GENERAL GRADING NOTES:

- This grading plan shall be coordinated with other applicable construction drawings for dimensions and layout.
 - Contractor shall be responsible for the protection of all existing improvements in the project area and it's vicinity. Any damages resulting from contractor's construction work shall be restricted to its original condition by the contractor.
 - Contractor shall be responsible for the protection of existing utilities in the project area. contractor shall contract utility locator service for field location of all prior to commencing work. Any damages shall be repaired in accordance with the requirements of the utility owner by the contractor.
- The following notes (4-11) is for the construction of streets only.
- Fill materials for site grading and backfill materials may consist of on-site and/or imported materials in compliance with the following specifications.
 - Fill materials for site grading and backfill materials shall be free of any organic or deleterious substance and shall not contain rocks or lumps over 4 inches in greatest dimension.
 - Fill materials shall be classified in accordance with ASTM d-2487. Soils will be considered satisfactory for fill material when classified as follows: GW, GP, GC, GM, GC-GM, GP-GC, SW, SP, SC, SM, SC-SM, SP-SM, SP-SC. Soils will be considered unsatisfactory for fill material when classified as follows: PT, OL, OH, ML, CL, AND CH or where the plasticity index exceeds 12.
 - The surface on which fill material is to be placed shall be scarified to a depth of 6 inches, watered to add the amount of moisture required for optimum compaction, and then compacted to the required density. Fill material shall be placed in lifts not exceeding 6 inches in depth and then compacted, moisture content of fill materials shall be uniform and within plus or minus two percent of the optimum value as determined by ASTM d-1557.
 - Each lift of fill shall be compacted to 95 percent (85 percent on slope only) of maximum density. maximum density shall be determined in accordance with ASTM d-1557 field density shall determined in accordance with ASTM d-1556 or d-2922.
 - Contractor shall water down grading area daily (minimum, so as to limit the distribution of dust from the work site in compliance with the city approved grading ordinance.
 - Contractor shall co-ordinate with all utility companies prior to any excavation and/or possible relocation of utilities encountered.
 - Contractor shall comply with section 13.08.070, 13.08.080, 13.08.090 and 13.08.100 of the El Paso municipal code for "excessive paving cuts".

GENERAL NOTES:

See sheet C14 & C15 of C15 for details on Storm Water Pollution Control Plan.

Developer will comply with Section 19.16.050 Storm Water Design of the El Paso municipal code.





The above referenced property is within zone "X". (explanation: areas of 500-year flood; areas of 100-year flood with average depths of less than 1 foot or with drainage areas less than 1 square mile; and areas protected by levees from 100-year flood.) according to the federal emergency management agency flood insurance rate maps, as per the UNINCORPORATED AREAS Community Panel No. 480212.0125 b. Dated September 4, 1995.

Any future grading related to new expansion or renovation of home improvements within this approved development shall be reviewed and approved by building services and must comply with items outlined in section 19.16.060 residential onsite ponding of the city of El Paso subdivision design ordinance.

All driveways shall not exceed -2% (negative) within the street right-of-way.

Each lot within Valley Creek Unit Five will be subject to site-specific grading and drainage design at the time of issuance of building permit (grading permit required). Finish floor elevations are to be equal to or above suggested elevation indicated on plans. It will be the responsibility of the contractor to import suitable fill under the building footprint to the finish grades that are in the approved set of drawings on file at the engineering department of the City of El Paso, Texas. expansive soils have been encounter at the site and pad preparation and slab design should be coordinated with the builders engineer and geotechnical consultant. To comply with existing and modified soils conditions.

LINE TABLE		
LINE	BEARING	LENGTH
LI	N 21°50'31" E	67.91'



ALL LOTS WITHIN VALLEY CREEK UNIT FIVE WILL REQUIRE TWO (1 EACH) PERMANENT ELEVATION MARKERS TO BE PLACED AT THE LOWEST POINT OF FRONT AND BACK YARDS. TO BE INSTALLED BY BUILDER / CONTRACTOR AND COORDINATED WITH ENGINEER / SURVEYOR.

TYPICAL PERMANENT ELEVATION MARKER

SCALE 1" = 1'

LEGEND

- ▲ PROPOSED CITY MONUMENT
- EXISTING CITY MONUMENT
- DENOTES SET 5/8" REBAR WITH YELLOW PLASTIC CAP STAMPED TX 2448, ROE ENGR., L.C. UNLESS OTHERWISE NOTED.
- 3711.14 FF FINISHED FLOOR ELEVATION
- 3710.64 FG FINISHED GROUND ELEVATION
- 10.44 THC TOP OF HEADER CURB ELEVATION
- 10.88 PV PAVEMENT ELEVATION
- PROPOSED DRAINAGE FLOW
- ⇨ EXISTING DRAINAGE FLOW
- PROPOSED POND CONTOUR
- PROPOSED HIGH WATER LINE
- EXISTING CONTOUR LINE

UTILITY COMPANIES

TEXAS GAS SERVICE
(NATURAL GAS)
4700 POLLARD STREET
EL PASO, TEXAS 79930
EMERGENCY 562-2003

SOUTHWESTERN BELL TELEPHONE
(TELEPHONE)
11200 PELLICANO DRIVE
EL PASO, TEXAS 79935
828-5127


EL PASO PUBLIC SERVICE BOARD
(WATER, SEWER)
1154 HAWKINS BOULEVARD
EL PASO, TEXAS 79925
MR. ALFONSO ORTIZ 594-5527

TIME WARNER COMMUNICATIONS
(CABLE)
7010 AIRPORT ROAD
EL PASO, TEXAS 79906
775-7414

EL PASO ELECTRIC COMPANY
(ELECTRIC)
501 WEST SAN ANTONIO STREET
EL PASO, TEXAS 79901
MR. PAT KEITH, 543-2917

WARNING! BEFORE YOU DIG
TEXAS LAW REQUIRES TWO (2) WORKING DAYS NOTICE PRIOR TO ANY EXCAVATION
CALL TEXAS EXCAVATION SAFETY SYSTEM ANYWHERE IN TEXAS 1-800-344-8377

TEXAS EXCAVATION SAFETY SYSTEM DIG CONFIRMATION NUMBER (#XXX-XXX-XXX) TO BE UPDATED EVERY 10 DAYS




CITY DEVELOPMENT DEPARTMENT

REVIEWED

SEE SHEET C-5 OF C-15 FOR TYPICAL LOT GRADING LAYOUTS

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES
ELEVATION: 3708.40 CITY DATUM)
(ELEVATION: 3751.05 NAVD 88)
STATE PLANE COORDINATES:
N 10693708.719 E 349632.2

SCALE
HOR: _____ VER: _____
FILE NAME: C03-VC_3_GPDWG
W.O. 111411-3_VCS
DATE: DECEMBER, 2013
DESIGN BY: LAJ/HP
DRAWN BY: L.A.J./S.R.
CHKD. BY: H.P.
APPD. BY: BR

VALLEY CREEK UNIT FIVE GRADING PLAN

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

RoE Engineering, L.C.
601 N. Cotton St. Suite No. 6 El Paso, TX, 79902
(915) 633-1418 - FAX: (915) 633-4972
e-mail: roeeng@webell.net

ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING

SHEET **C-3** OF **C-15**

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE

FLOOD NOTE:
NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X". (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD.) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212.0125 B. DATED SEPTEMBER 4, 1995.

VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID C60442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHING 10700302.694, EASTING 384501.733)

C:\Projects\11411-3 VALLEY CREEK UNIT 5 AND 5 VALLEY CREEK UNIT 4 AND 5\Map\VC3 Eng Package\C-03_C04_VCS_REVIEWE GRADING PLAN.DWG 12/12/13 8:00PM

LOTS 1-10, BLOCK 1
PERCOLATION RATE 10.91
PONDS 12" HIGH WATER LEVEL
12" HIGH WATER X 10.91 MIN PER
INCH = $\frac{12}{10.91} = 2.2$ HOURS < 72 hours

LOT 11, BLOCK 1
PERCOLATION RATE 10.91
PONDS 18" HIGH WATER LEVEL
18" HIGH WATER X 10.91 MIN PER
INCH = $\frac{18}{10.91} = 3.3$ HOURS < 72 hours

LINE	BEARING	LENGTH
L1	N 21°50'31" E	67.91'

WATERSHED DESIGNATION	WATERSHED AREAS (ACRES)	RAINFALL (in)	AVERAGE RUNOFF COEF.	REQUIRED CAPACITY (AC-FT)
LOT 1 WS	0.4109	4.0	0.60	0.0822
LOT 2 WS	0.3719	4.0	0.60	0.0744
LOT 3 WS	0.3825	4.0	0.60	0.0785
LOT 4 WS	0.3401	4.0	0.60	0.0680
LOT 5 WS	0.2856	4.0	0.60	0.0571
LOT 6 WS	0.2837	4.0	0.60	0.0567
LOT 7 WS	0.4200	4.0	0.60	0.0840
LOT 8 WS	0.4614	4.0	0.60	0.0923
LOT 9 WS	0.3859	4.0	0.60	0.0772
LOT 10 WS	0.3461	4.0	0.60	0.0692
LOT 11 WS	0.4439	4.0	0.60	0.0888

- LEGEND**
- ▲ PROPOSED CITY MONUMENT
 - ◆ EXISTING CITY MONUMENT
 - DENOTES SET 5/8" REBAR WITH YELLOW PLASTIC CAP STAMPED TX 2449, ROE ENGR, L.C. UNLESS OTHERWISE NOTED.
 - 3711.14 FF FINISHED FLOOR ELEVATION
 - 3710.64 FG FINISHED GROUND ELEVATION
 - 10.44 THC TOP OF HEADER CURB ELEVATION
 - 10.98 PV PAVEMENT ELEVATION
 - PROPOSED DRAINAGE FLOW
 - ⇨ EXISTING DRAINAGE FLOW
 - PROPOSED POND CONTOUR
 - PROPOSED HIGH WATER LINE
 - EXISTING CONTOUR LINE
 - WATERSHED LIMITS

Speersoll Inc

SPG11209-P

PERCOLATION TEST P-4

(PERCOLATION RATE: 10.91 minutes per inch in silty sand)


Project Name: Valley Creek Unit Three, Four and Five, El Paso, Texas
Date of Test: November 29, 2011
Test Completed By: RF
Test Location: Valley Creek Unit Five, Block 1, Lot 5
Test Hole Diameter: 8-inches (2-ft deep)
Soil Classification: SAND, fine, silty, brown, SM
PERCOLATION RATE: 10.91 minutes per inch in silty sand

Run No.	Time (min)			Water Level (in)			Percolation Rate (Min per in)
	Start	End	Change	Start	End	Change	
1	1:50	2:45	0:55	20	12	8	6.88
2	2:45	3:15	0:30	19	15 3/4	3 3/4	9.23
3	3:15	3:45	0:30	19 3/4	16 3/4	3 3/4	9.23
4	3:45	4:15	0:30	16 3/4	14	2 3/4	13.33
5	4:15	4:45	0:30	19	16 3/4	2 3/4	12.00
6	4:45	5:15	0:30	16 3/4	14	2 3/4	12.00
7	5:15	5:45	0:30	18 3/4	15 3/4	2 3/4	10.91

Remarks: Test was conducted in accordance with percolation Test procedure of "Construction Standards for On-site Sewerage Facilities" by Texas Department of Health.

Patrick L. Shing, P.E.
Principal

Date: December 15, 2011



- ON-SITE PONDING NOTES:**
- All lots in the subdivision are subject to on-site ponding. Lot owners are responsible for maintaining adequate provisions to accommodate all stormwater runoff generated from their respective lot plus one-half the runoff generated from all abutting street right-of-ways directly fronting the lot. The pond depth and lot grading requirements are as per approved Grading and Drainage plan for the Subdivision.
 - The Site / Grading plan will show that the ponding will have sufficient capacity for a 4 inch 100 year storm. The ponding provided will not be more than 12 inches in depth and will percolate in 72 hours or less based on the test results. If the design criteria for ponding and percolation cannot be achieved then alternate methods may be part of the site plan. Dry Wells and storm water infiltration wells with slotted sides for percolation discharge are a few of the methods that can be reviewed for approval.
 - Walls constructed abutting street right-of-ways shall be constructed with a series of drain pipes allowing the street runoff to be conveyed to the subject property.
 - On-site ponding areas shall have maximum one (vertical) to three (horizontal) side slopes and a maximum depth of twelve (12) inches based on a one hundred year storm.
 - Permanent elevation markers shall be installed to define the levels to be maintained to ensure the effectiveness of on-site ponding. Permanent elevation markers shall not be moved, covered, or altered without written permission from the City Engineer.
 - The City and/or its Representative is granted permanent right of access to inspect the ponding areas and permanent elevation markers.
 - Filling or changing the pond, or allowing the pond to be filled or changed to an elevation greater than established by the permanent elevation markers, is prohibited.
 - On-site ponding areas and permanent elevation markers shall be constructed and inspected prior to building occupancy. Permanent Certificate of Occupancy, required to obtain utility services, will be issued only after the City of El Paso has performed the inspection.
 - No person shall be permitted to impair the functionality of an on-site pond. No more than fifty-percent (50%) of the area of any residential lot conveyed by deed shall be covered by improvements, either temporary or permanent, which shed stormwater, including but not limited to, buildings, driveways, patios, decks or landscaping underlaid with plastic sheeting or other impermeable material.
 - In the event that the functionality of an on-site pond becomes impaired whether by act of man or nature, the owner of the lot on which the impaired pond is located shall perform all corrective actions required to restore that functionality.
 - Any owner notified in writing by the City Engineer of corrective actions required to restore the functionality of an on-site pond or drainage problem on the lot shall comply within forty-five calendar days of receipt of such notice; provided, however, that nothing herein shall prevent the City from mandating an earlier time for commencement of completion during times of emergency, where there is imminent danger of loss of life, limb or property.
 - Owner of property utilizing on-site ponding waives any claim or cause of action against the City, EPWU-PSB, officials or employees, for any death, injury or property damage resulting from alteration of the ponding capacity for that lot, including lack of maintenance.
 - These on-site ponding requirements shall be enforced by injunctive relief without the requirement for bond or other security.
 - The conveyance of property permitting on-site ponding shall declare in conspicuous language in the deed that the property is subject to on-site ponding requirements, maintenance of elevation markers, standing water on lot, and ingress and egress for inspection as stated on the plat.


UTILITY COMPANIES

- TEXAS GAS SERVICE (NATURAL GAS)**
4700 POLLARD STREET
EL PASO, TEXAS 79930
EMERGENCY 562-2003
- SOUTHWESTERN BELL TELEPHONE (TELEPHONE)**
11200 PELLICANO DRIVE
EL PASO, TEXAS 79935
828-5127
- EL PASO PUBLIC SERVICE BOARD (WATER, SEWER)**
1154 HAWKINS BOULEVARD
EL PASO, TEXAS 79925
MR. ALFONSO ORTIZ 594-5527
- TIME WARNER COMMUNICATIONS (CABLE)**
7010 AIRPORT ROAD
EL PASO, TEXAS 79906
775-7414
- EL PASO ELECTRIC COMPANY (ELECTRIC)**
501 WEST SAN ANTONIO STREET
EL PASO, TEXAS 79901
MR. PAT KEITH, 543-2917

WARNING! BEFORE YOU DIG
TEXAS LAW REQUIRES TWO (2) WORKING DAYS NOTICE PRIOR TO ANY EXCAVATION
CALL TEXAS EXCAVATION SAFETY SYSTEM ANYWHERE IN TEXAS 1-800-344-8377
TEXAS EXCAVATION SAFETY SYSTEM DIG CONFIRMATION NUMBER (#XXX-XXX-XXX) TO BE UPDATED EVERY 10 DAYS

CITY DEVELOPMENT DEPARTMENT REVIEWED

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3761.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	HOR: _____ VER: _____ FILE NAME: C03-VC 3_GP.DWG W.O. 111411-3_VCS DATE: DECEMBER, 2013 DESIGN BY: LAJ/HP DRAWN BY: L.A.J./S.R. CHKD. BY: H.P. APPD. BY: BR




VALLEY CREEK UNIT FIVE DRAINAGE PLAN

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3,792 acres more or less.

RoE Engineering, L.C.
601 N. Cotton St. Suite No. 6 El Paso, Tx. 79902
(915) 533-1418 - FAX: (915) 533-4972
e-mail: roeeng@swbell.net

ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C-4 OF C-15

C:\p\p\p\111411-3 VALLEY CREEK UNIT 5 AND 10\VALLEY CREEK UNIT 5_VCS_REVIEWED_GROUND PLAN.DWG 12/15/13 3:00PM



TYPICAL GRADING LAYOUT (CUL-DE-SAC)




SCALE: 1" = 20'


EACH LOT WITHIN VALLEY CREEK UNIT FIVE WILL BE IN COMPLIANCE WITH THE STREET IMPROVEMENT PACKAGE. FINISH FLOOR ELEVATIONS ARE TO BE EQUAL TO OR ABOVE SUGGESTED ELEVATION INDICATED ON PLANS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPORT SUITABLE FILL UNDER THE BUILDING FOOTPRINT TO THE FINISH GRADES THAT ARE IN THE APPROVED SET OF DRAWINGS ON FILE AT THE ENGINEERING DEPARTMENT OF THE CITY OF EL PASO, TEXAS. EXPANSIVE SOILS HAVE BEEN ENCOUNTERED AT THE SITE AND PAD PREPARATION AND SLAB DESIGN SHOULD BE COORDINATED WITH THE BUILDERS, ENGINEER AND GEOTECHNICAL CONSULTANT, TO COMPLY WITH EXISTING AND MODIFIED SOILS CONDITIONS.

WATERSHED DESIGNATION	WATERSHED AREAS (ACRES)	RAINFALL (in)	AVERAGE RUNOFF COEFF.	REQUIRED CAPACITY (AC - FT)
LOT 8 WS	0.4614	4.0	0.60	0.0623

POND	BOTTOM AREA (SQ. FT.)	TOP AREA (SQ. FT.)	BOTTOM ELEVATION	TOP ELEVATION	HIGH WATER ELEVATION	CAPACITY (AC - FT)
1 (FRONT)	851.41	1282.39	3709.44	3710.44	3710.36	0.0116
2 (BACK)	2173.93	2877.46	3709.44	3710.44	3710.36	0.0891
TOTAL AVAILABLE CAPACITY (AC - FT) =						0.1007



KEY MAP



TYPICAL GRADING LAYOUT (TYPICAL LOT)




SCALE: 1" = 20'


EACH LOT WITHIN VALLEY CREEK UNIT FIVE WILL BE IN COMPLIANCE WITH THE STREET IMPROVEMENT PACKAGE. FINISH FLOOR ELEVATIONS ARE TO BE EQUAL TO OR ABOVE SUGGESTED ELEVATION INDICATED ON PLANS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPORT SUITABLE FILL UNDER THE BUILDING FOOTPRINT TO THE FINISH GRADES THAT ARE IN THE APPROVED SET OF DRAWINGS ON FILE AT THE ENGINEERING DEPARTMENT OF THE CITY OF EL PASO, TEXAS. EXPANSIVE SOILS HAVE BEEN ENCOUNTERED AT THE SITE AND PAD PREPARATION AND SLAB DESIGN SHOULD BE COORDINATED WITH THE BUILDERS, ENGINEER AND GEOTECHNICAL CONSULTANT, TO COMPLY WITH EXISTING AND MODIFIED SOILS CONDITIONS.

WATERSHED DESIGNATION	WATERSHED AREAS (ACRES)	RAINFALL (in)	AVERAGE RUNOFF COEFF.	REQUIRED CAPACITY (AC - FT)
LOT 10 WS	0.3461	4.0	0.60	0.0692


POND	BOTTOM AREA (SQ. FT.)	TOP AREA (SQ. FT.)	BOTTOM ELEVATION	TOP ELEVATION	HIGH WATER ELEVATION	CAPACITY (AC - FT)
1 (FRONT)	851.41	1282.39	3708.79	3709.79	3708.74	0.0159
2 (BACK)	2173.93	2877.46	3708.79	3709.79	3708.74	0.0665
TOTAL AVAILABLE CAPACITY (AC - FT) =						0.0724



KEY MAP



TYPICAL GRADING LAYOUT (CORNER LOT)




SCALE: 1" = 20'


EACH LOT WITHIN VALLEY CREEK UNIT FIVE WILL BE IN COMPLIANCE WITH THE STREET IMPROVEMENT PACKAGE. FINISH FLOOR ELEVATIONS ARE TO BE EQUAL TO OR ABOVE SUGGESTED ELEVATION INDICATED ON PLANS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPORT SUITABLE FILL UNDER THE BUILDING FOOTPRINT TO THE FINISH GRADES THAT ARE IN THE APPROVED SET OF DRAWINGS ON FILE AT THE ENGINEERING DEPARTMENT OF THE CITY OF EL PASO, TEXAS. EXPANSIVE SOILS HAVE BEEN ENCOUNTERED AT THE SITE AND PAD PREPARATION AND SLAB DESIGN SHOULD BE COORDINATED WITH THE BUILDERS, ENGINEER AND GEOTECHNICAL CONSULTANT, TO COMPLY WITH EXISTING AND MODIFIED SOILS CONDITIONS.

WATERSHED DESIGNATION	WATERSHED AREAS (ACRES)	RAINFALL (in)	AVERAGE RUNOFF COEFF.	REQUIRED CAPACITY (AC - FT)
LOT 1 WS	0.4109	4.0	0.60	0.0622

POND	BOTTOM AREA (SQ. FT.)	TOP AREA (SQ. FT.)	BOTTOM ELEVATION	TOP ELEVATION	HIGH WATER ELEVATION	CAPACITY (AC - FT)
1 (FRONT)	606.65	1029.54	3707.70	3708.70	3708.67	0.0188
2 (BACK)	2526.75	3223.35	3707.70	3708.70	3708.67	0.0660
TOTAL AVAILABLE CAPACITY (AC - FT) =						0.0848



KEY MAP



TYPICAL GRADING LAYOUT (CORNER LOT)




SCALE: 1" = 20'

EACH LOT WITHIN VALLEY CREEK UNIT FIVE WILL BE IN COMPLIANCE WITH THE STREET IMPROVEMENT PACKAGE. FINISH FLOOR ELEVATIONS ARE TO BE EQUAL TO OR ABOVE SUGGESTED ELEVATION INDICATED ON PLANS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPORT SUITABLE FILL UNDER THE BUILDING FOOTPRINT TO THE FINISH GRADES THAT ARE IN THE APPROVED SET OF DRAWINGS ON FILE AT THE ENGINEERING DEPARTMENT OF THE CITY OF EL PASO, TEXAS. EXPANSIVE SOILS HAVE BEEN ENCOUNTERED AT THE SITE AND PAD PREPARATION AND SLAB DESIGN SHOULD BE COORDINATED WITH THE BUILDERS, ENGINEER AND GEOTECHNICAL CONSULTANT, TO COMPLY WITH EXISTING AND MODIFIED SOILS CONDITIONS.

WATERSHED DESIGNATION	WATERSHED AREAS (ACRES)	RAINFALL (in)	AVERAGE RUNOFF COEFF.	REQUIRED CAPACITY (AC - FT)
LOT 11 WS	0.4439	4.0	0.60	0.0888

POND	BOTTOM AREA (SQ. FT.)	TOP AREA (SQ. FT.)	BOTTOM ELEVATION	TOP ELEVATION	HIGH WATER ELEVATION	CAPACITY (AC - FT)
1 (FRONT)	851.41	1282.39	3707.29	3708.29	3708.79	0.0170
2 (BACK)	2173.93	2877.46	3707.29	3708.29	3708.79	0.0719
TOTAL AVAILABLE CAPACITY (AC - FT) =						0.0889



KEY MAP


C:\p\p\11111-3 VALLEY CREEK UNIT 5 AND VALLEY CREEK UNIT 6 VALLEY TYP GRADING LOT LAYOUT.DWG 12/17/13 8:10PM

FLOOD NOTE:
This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and an instrument of services in respect to the project for which it was prepared. This document is not intended or authorized for reuse by any party on extensions of such project or any other project. Any reuse, including copying and/or modifying the document, without written permission from Roe Engineering, L.C., for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.

VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REF" (NGS PID C60422) NAVD 88 DATUM AND REFERENCED TO NAD83 HAYING AND ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 354501.733)

DATE	REVISIONS	BY	PRIMARY BENCHMARK
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES
			ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2

SCALE
HOR: _____ VER: _____
FILE NAME: 111411-3 VCS
W.O.: 11411-3 VCS
DATE: DECEMBER, 2013
DESIGN BY: LAJ/HP
DRAWN BY: L.A.J./S.R.
CHKD. BY: H.P.
APPD. BY: BR



VALLEY CREEK UNIT FIVE
TYPICAL LOT GRADING
BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

hmp Roe Engineering, L.C.
601 N. Cotton St. Suite No. 6 El Paso, TX 79902
(915) 533-1418 - FAX: (915) 533-4972
e-mail: roeeng@hmpbell.net
ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C-6 OF C-15



CITY DEVELOPMENT DEPARTMENT

REVIEWED




THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

NOTE:
THE UNDERGROUND STORAGE CHAMBER DETAIL IS AN ALTERNATE DESIGN IF CONVENTIONAL ON SITE PONDING IS INSUFFICIENT.

**CULTEC RECHARGER 330XLHD CHAMBER SYSTEM
TYPICAL CROSS SECTION DETAIL OR APPROVED EQUAL**




REFER TO CULTEC, INC.'S CURRENT RECOMMENDED INSTALLATION GUIDELINES. ALL RECHARGER 330XLHD HEAVY DUTY UNITS ARE MARKED WITH A COLOR STRIPE FORMED INTO THE PART ALONG THE LENGTH OF THE CHAMBER.



GENERAL NOTES
RECHARGER 330XLHD BY CULTEC, INC. OF BROOKFIELD, CT.

CULTEC, Inc.
P.O. Box 280
878 Federal Road
Brookfield, CT 06804 USA

PH: (203) 775-4416
PH: (800) 4-CULTEC
FX: (203) 775-1462
www.cultec.com




CULTEC RECHARGER 330 SECTION VIEW

CULTEC Contactor® and Recharger® Plastic Septic and Stormwater Chambers		
DATE	SCALE	FILENAME
3/23/05	N/S	


NOTES:

- ALL RECHARGER 330 XLHD STORAGE CHAMBERS OR APPROVED EQUAL MUST BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.
- ALL RECHARGER 330 XLHD STORAGE CHAMBERS OR APPROVED EQUAL TO BE OWNED, OPERATED AND MAINTAINED BY THE PROPERTY OWNER.
- ALL RECHARGER 330 XLHD STORAGE CHAMBERS OR APPROVED EQUAL MUST BE DESIGNED BY A LICENSED PROFESSIONAL ENGINEER. ENGINEER TO DETERMINE THE AMOUNT OF STORAGE CHAMBERS NEEDED TO COMPLY WITH THE CITY OF EL PASO 72 HOUR STANDING WATER ORDINANCE, 12" MAXIMUM PONDING AND THE REQUIRED CAPACITY FOR THE LOT BEING DEVELOPED.
- STORAGE CHAMBERS SHALL ONLY BE USED IF ONSITE PONDING IS NOT SUFFICIENT TO HANDLE THE REQUIRED CAPACITY.



PEDESTRIAN (H-10) RATED
DRAINAREA = 79.3 SQ. INCH
MATERIAL: NYLOPLAST, CAST IRON
QUALITY: MATERIAL SHALL CONFORM TO ASTM A48 - CLASS 30B
PAINT: CASTINGS ARE FURNISHED WITH A BLACK PAINT


15" CAST IRON GRATE



15" INLINE DRAIN

CITY DEVELOPMENT DEPARTMENT
REVIEWED

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013, ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



**VALLEY CREEK UNIT FIVE
UNDERGROUND STORAGE
CHAMBERS FOR ADDED CAPACITY**

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS,
CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS
CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

RoE Engineering, L.C.
801 N. Cotton St. Suite No. 8 El Paso, Tx. 79902
(915) 533-1418 - FAX (915) 533-4972
e-mail: roeeng@bellsouth.net

ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C7 OF C-15


C:\p\p\p\11411-3 VALLEY CREEK UNIT 5 AND VALLEY CREEK UNIT 6 CHAMBERS.DWG 12/05/13 10:17AM

This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and an instrument of services in respect to the project for which it was prepared. This document is not intended or authorized for reuse by any party on extensions of such project or any other project. Any reuse, including copying, use, or modifying the document, without written permission from Roe Engineering, L.C. for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.

FLOOD NOTE:
NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X" (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B. DATED SEPTEMBER 4, 1995.




VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 RFB" (NGS PID CD442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36 (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 364501.733)

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES ELEVATION: 3708.40 CITY DATUM) (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	HOR: AS SHOWN VER: AS SHOWN FILE NAME: C07_VALLEY_CREEK_UNITS W.O. 111411-3 VCS DATE: DECEMBER ,2013 DESIGN BY: LAJ/HP DRAWN BY: L.A.J./S.R. CHKD. BY: H.P. APPD. BY: BR



HORIZONTAL SCALE: 1" = 30'
VERTICAL SCALE: 1" = 5'

Gomez Road Extension
(60' WIDE RIGHT-OF-WAY)



HORIZONTAL SCALE: 1" = 30'
VERTICAL SCALE: 1" = 5'

LEGEND

- △ PROPOSED CITY MONUMENT
- ◊ EXISTING CITY MONUMENT
- DENOTES SET 5/8" REBAR WITH YELLOW PLASTIC CAP STAMPED TX 848, ROE ENGR, L.C. UNLESS OTHERWISE NOTED.
- 3711.14 FF FINISHED FLOOR ELEVATION
- 3710.64 FG FINISHED GROUND ELEVATION
- 10.44 THC TOP OF HEADER CURB ELEVATION
- 10.98 PV PAVEMENT ELEVATION
- PROPOSED DRAINAGE FLOW


LINE TABLE

LINE	BEARING	LENGTH
L1	N 00°02'29" W	30.00'
L3	N 88°47'29" W	32.99'

CURVE TABLE

CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
C1	58.00	87.72'	55.78'	79.02'	S 44°54'59" E	89°45'00"
C2	29.50	46.47'	28.83'	41.81'	S 45°05'01" W	90°15'00"
C3	300.56	169.02'	86.81'	168.80'	N 24°44'03" E	321°31'44"
C4	39.50	61.87'	39.33'	55.74'	S 44°54'59" E	89°45'00"
C5	37.50	62.34'	37.25'	57.54'	S 65°30'08" E	49°24'47"
C6	45.50	62.29'	37.14'	57.54'	S 80°00'57" W	78°26'25"
C7	45.50	48.22'	26.65'	46.00'	N 30°24'10" W	60°43'22"
C8	45.50	48.17'	26.62'	45.95'	N 30°17'10" E	60°39'18"
C9	45.50	62.74'	37.51'	57.89'	S 79°52'57" E	79°00'29"
C10	37.50	32.34'	17.25'	31.35'	N 65°05'06" W	42°24'47"
C11	38.19	28.64'	15.03'	27.98'	S 68°38'39" W	42°58'22"
C12	65.50	39.09'	20.15'	38.51'	N 72°21'03" E	341°13'33"
C13	65.50	63.79'	34.68'	61.30'	S 62°39'14" E	55°47'52"
C14	65.50	65.41'	35.72'	62.72'	S 06°08'54" E	57°12'48"
C15	65.50	18.47'	9.29'	18.40'	S 30°32'04" W	16°09'09"
C16	39.50	28.65'	13.85'	28.14'	N 19°17'05" E	38°39'08"
C17	29.50	46.21'	29.37'	41.63'	N 44°54'59" W	89°45'00"

NOTE:
1. ALL HANDICAP RAMPS WITHIN SUBDIVISION ARE TO BE BUILT BY DEVELOPER UNLESS OTHERWISE NOTED. SEE DETAILS SHEET C-10 OF C-20.
2. ALL SIDEWALKS WITHIN SUBDIVISION ARE TO BE BUILT BY BUILDER UNLESS OTHERWISE NOTED. SEE DETAILS SHEET C-9 OF C-15.



FLOOD NOTE:
THE ABOVE REFERENCED SUBDIVISION IS WITHIN ZONE "X" (EXPLANATION: ZONE "X" AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 250 B, DATED SEPTEMBER 4, 1991.

VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REE" (NGS PID C0442) NAVD 88 DATUM AND REFERENCED TO NAD83. HAVING AN ELEVATION OF 3754.36 (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 354501.733)

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON OCT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

LEGEND


- × 10.08 THC PROPOSED TOP OF HEADER CURB
- × 11.08 FG PROPOSED FINISHED GRADE ELEVATION
- × 10.40 PV PROPOSED TOP OF PAVEMENT
- × 11.58 FF PROPOSED TOP OF PAD ELEVATION
- PROPOSED DRAINAGE FLOW
- PROPOSED STREET CENTERLINE
- SUBDIVISION BOUNDARY LINE
- △ PROPOSED CITY MONUMENT
- ◊ PROPOSED HIGH POINT
- PROPOSED LOW POINT

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	HOR: 1" = 30' VER: 1" = 5' FILE NAME: C08-VC-5-VALLEY PINE-PP.DWG W.O. 111411-3 VCS DATE: DECEMBER 2013 DESIGN BY: LAJ/HP DRAWN BY: L.A.J./S.R. CHKD. BY: H.P. APPD. BY: BR

VALLEY CREEK UNIT FIVE

VALLEY PINE DRIVE
STATION 0+00.00 TO 3+87.51

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SUBDIVISION, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.




ROE ENGINEERING, L.C.
TEXAS REGISTERED ENGINEERING FIRM F-2103

brnp Roe Engineering, L.C.
601 N. Cotton St., Suite No. 2 El Paso, TX, 79902
(915) 838-1418 - FAX (915) 558-4972
e-mail: roeeng@bnp.net


ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING

SHEET C-8 OF C-15

C:\Projects\11411-3 VALLEY CREEK UNIT FIVE - AND P.DWG 12/17/13 5:20PM




**(EXISTING GOMEZ ROAD)
60' RIGHT-OF-WAY TYPICAL CROWN STREET SECTION ALREADY IMPROVED**
SCALE 1" = 5'



**52' RIGHT-OF-WAY TYPICAL CROWN STREET SECTION
VALLEY SPRUCE DRIVE**
SCALE 1" = 5'

NOTES FOR STREETS:


- BASE TO BE COMPACTED TO 100% COMPACTION BY A.S.T.M. D1557
- H.M.A.C., BASE, AND SUBGRADE WILL BE IN STRICT ACCORDANCE WITH THE LATEST CITY OF EL PASO SPECIFICATIONS
- SUBGRADE TO BE COMPACTED TO 95% COMPACTION BY A.S.T.M. D1557
- PRIME COAT TO BE 0.25 GALLON PER SQUARE YARD (MIN. COVERAGE)
- ALL ELEVATIONS ON PLANS BASED ON CITY DATUM.
- SUBGRADE UNDER CURB MUST BE FORMED AND COMPACTED AS SHOWN OR EXCESS CUT MUST BE BACKFILLED WITH CONCRETE.
- COMPACTION BEHIND CURB
 - ONE FOOT MIN. ON CUTS
 - TWO FOOT MIN. ON FILLS
- C.B.R. TEST TO BE APPROVED BY DEVELOPMENT SERVICES PRIOR TO PAVING.
- COMPACTION TEST WHERE REQUIRED BY THE CITY ENGINEER MUST BE PAID FOR BY THE DEVELOPER. THIS INCLUDES BUT IS NOT LIMITED TO SUBGRADE AND BASE COURSE.
- ALL PLANS MUST BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF EL PASO SUBDIVISION DESIGN AND IMPROVEMENT STANDARDS.
- C.B.R. TEST REQUIRED AT EVERY 500' AFTER SUBGRADE IS IN PLACE OR A MIN. OF TWO TESTS IF STREET IS LESS THAN 500'
- STREET VERTICAL CONTROL OF ALL CURB AND GUTTER ELEVATIONS WILL BE MAINTAINED. (BLUE TOPPING REQUIRED THROUGHOUT)




**LOTS ABUTTING THE COMBINED LA UNION WASTEWAY / INTERCEPTING DRAIN / SCHULTZ LATERAL AND GOMEZ ROAD
ROCKWALL W/ WROUGHT IRON FENCE**
SCALE: 1" = 2'

NOTES FOR ROCKWALL:

- STONE FOR ROCKWALL SHALL BE AS NEARLY UNIFORM IN SECTIONS AS IS PRACTICABLE. THE STONE SHALL BE DENSE AND RESISTANT TO AIR AND WATER.
- MORTAR SHALL BE TYPE "S" 1800 P.S.I. AS PER ASTM C270.
- MASONRY WALLS OVER SIX (6) FEET IN HEIGHT AND THOSE USED FOR EARTH RETENTION OVER TWO (2) FEET SHALL BE DESIGNED AS STRUCTURAL WALLS.
- WALLS ADJACENT TO PONDING AREAS OR DRAINAGE DITCHES MAY BE CONSTRUCTED OF BRICK OR CINDER BLOCK AND SHALL NOT BE LESS THAN SIX (6) FEET HIGH.
- ROCKWALL MORTAR JOINTS SHALL NOT EXCEED TWO (2) INCHES.
- PROVIDE ONE (1) INCH EXPANSION JOINTS AT EVERY 100 FEET.
- ALL STONE SHALL BE THOROUGHLY SOAKED BEFORE BEING PLACED.
- NO RIVER ROCK SHALL BE ALLOWED FOR ROCKWALLS.




ROCKWALL DETAIL
SCALE: 1" = 2'



ALTERNATE ROCKWALL DETAIL
SCALE: 1" = 2'


**EXISTING GOMEZ ROAD (ALREADY IMPROVED)
PAVEMENT SECTION**
SCALE: 1" = 1'



**52' STREET RIGHT-OF-WAY
TYPICAL PAVEMENT SECTION**
SCALE: 1" = 1'




WALL SCHEDULE		
HEIGHT (H)	BASE (B)	FOOTING (F)
3' - 0"	2' - 0"	0' - 6"
4' - 0"	2' - 6"	0' - 6"



RETAINING ROCKWALL DETAIL
SCALE: 1" = 3'

- GENERAL ROCKWALL NOTES**
- NATURAL STONE SHALL BE SOUND AND FREE FROM LOOSE OR FRIBLE INCLUSIONS AND SHALL MEET REQUIRED STRENGTH AND DURABILITY FOR PROPOSED USE.
 - MORTAR SHALL BE ASTM-C270 TYPE S PROPORTION BY VOLUME - MIN 1800 P.S.I.
PORTLAND CEMENT 1 PART
LIME 1/4 PART
SAND 3-1/2 PARTS
 - CONCRETE F'C=3000 PSI @ 28 DAYS.
 - REINFORCING STEEL ASTM A615 GRADE 40, Fy=40,000 PSI.
 - ALLOWABLE SOIL BEARING PRESSURE 2500 P.S.I. MINIMUM.
 - WALL FOOTING SHALL BEAR ON COMPACTED OR FIRM UNDISTURBED GROUND.
 - CHANGES IN WALL DIRECTION, WALL HEIGHT OR FOOTING ELEVATION WILL REQUIRE ADDITIONAL DESIGN.
 - BACKFILL MATERIAL SHALL CONSIST OF WELL-DRAINED, COARSE DRAINED SOILS, OR FINE SILTY SANDS WITH NO CLAY CONTENT. BACKFILL MATERIAL SHALL EXERT A HORIZONTAL FORCE OF AN EQUIVALENT FLUID PRESSURE NOT TO EXCEED 30#/F+3.
 - SURCHARGE WILL REQUIRE ADDITIONAL DESIGN. YES NO. IF SURCHARGED, DETAILS MUST BE SUBMITTED FOR REVIEW AND APPROVAL TO BUILDING INSPECTION DEPARTMENT AT THE TIME BUILDING CONSTRUCTION PLANS ARE SUBMITTED.
 - RETAINING WALL (S) WILL BE REQUIRED WHERE THE GRADE DIFFERENCE BETWEEN THE FINISHED GRADE OF ANY LOT WITHIN THIS SUBDIVISION AND/OR ADJOINING PROPERTY IS TWO (2) FEET OR GREATER.
 - ROCKWALL HEIGHTS IN EXCESS OF FOUR (4) FEET WILL REQUIRE ADDITIONAL DESIGN ANALYSIS AND COMPUTATIONS TO INCLUDE ASSOCIATED DETAILS.




JUNCTURE OF NEW FLEXIBLE AND EXISTING FLEXIBLE PAVEMENT AT GOMEZ ROAD AND VALLEY SPRUCE DRIVE
SCALE: N.T.S.

SIZE AND CONSTRUCTION.
THE STANDARD CITY MONUMENT SHALL BE POURED-IN-PLACE CONCRETE CONE, EIGHT (8) INCHES MINIMUM DIAMETER AT THE TOP, EIGHTEEN (18) INCHES MINIMUM DIAMETER AT THE BOTTOM, THIRTY-SIX (36) INCHES MINIMUM IN DEPTH WITH THE MONUMENT CAP IN PLACE ON TOP.
THE MONUMENT SHALL BE COVERED WITH A CAST IRON BOX AND COVER.

NUMBER AND LOCATIONS.
THE MONUMENTS SHALL BE INSTALLED WHERE SHOWN ON THE SUBDIVISION PLAT AS APPROVED BY THE CITY ENGINEER.


ANY MONUMENT MUST BE WITHIN THE LINE OF SIGHT OF ANY OTHER MONUMENT (2000 FEET MAXIMUM DISTANCE BETWEEN MONUMENTS).
THE SIZE, TOPOGRAPHY AND LAYOUT OF THE SUBDIVISION SHALL GOVERN THE NUMBER OF MONUMENTS REQUIRED.

NO FEWER THAN TWO MONUMENTS SHALL BE PLACED IN A ONE STREET SUB-DIVISION.
AT LEAST ONE (1) MONUMENT SHALL BE PLACED ON EACH HORIZONTAL CURVE. TWO SHALL BE PLACED IF THE POINT OF INTERSECTION (P.I.) OF THE TANGENTS LEADING INTO THE CURVE FALLS OUTSIDE OF CITY RIGHT-OF-WAY. MONUMENTS SHALL BE INSTALLED SO THAT ALL FRONT PROPERTY CORNERS OF ALL LOTS IN THE SUBDIVISION ARE WITHIN LINE OF SIGHT OF A MONUMENT, OR WITHIN SIGHT OF LINE BETWEEN TWO ADJACENT MONUMENTS.




COUNTERSUNK DETAIL
SCALE: 1" = 3'


FRAME SECTION
SCALE: 1" = 6"



BRONZE MONUMENT CAP
SCALE: 1" = 4"



SECTION A - A




REVIEWED

CITY MONUMENT DETAIL

SEE PLATE 3-52 OF THE CITY OF EL PASO DESIGN STANDARDS FOR CONSTRUCTION

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



VALLEY CREEK UNIT FIVE
TYPICAL DETAILS
BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS
CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.


RoE Engineering, L.C.
601 N. Cotton St. Suite No. 8 El Paso, TX 79902
(915) 633-1418 - FAX (915) 633-4972
e-mail: roeeng@bellsouth.net
ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C09 OF C-15

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES	
			ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	


FLOOD NOTE:
NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X" (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B. DATED SEPTEMBER 4, 1995.

VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID CE0442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHEING 10700302.594, EASTING 354501.735)

C:\p\11411-3 VALLEY CREEK UNIT 5 AND DIVERSIFIED Eng. 12/05/13 10:10AM




HANDICAP RAMP
SCALE 1" = 5'




SECTION C - C
SCALE: 1" = 2'

- NOTES FOR HEADER CURB:**
- EXPANSION JOINTS WILL BE REQUIRED AT THE END OF CURB RETURNS, AT 50' O.C. & POINT OF TANGENCY WITH STRAIGHT RUNS OF CURB AT EVERY INTERSECTION
 - CONTRACTION JOINTS (1/2 INCH MIN. SCORED JOINTS) MUST BE INSTALLED EVERY 10 FEET IN CURB OR CURB AND GUTTER.
 - ALL EXPANSION JOINTS WILL BE PERFORMED BITUMINOUS FIBER 1/2 INCH THICK.
 - CONCRETE TO BE CLASS "A", 3000 P.S.I.




HEADER CURB
SCALE 1/2" = 1'




PLAN VIEW
SCALE: 1" = 10'

DRIVEWAY WIDTH RESIDENTIAL	MIN. 10'	MAX. 20'
DRIVEWAY THICKNESS RESIDENTIAL	6" CONC. WITHOUT W.W.F. 4" CONC. WITH 6X6-10/10 W.W.F.	




SECTION A - A
SCALE: 1" = 2'



TYPICAL SIDEWALK AT CUL-DE-SAC AND HEELS WITH HEADER CURB
SCALE: 1" = 1'

- NOTE**
- CONCRETE TO BE CLASS "A", 3000 P.S.I.
 - EXPANSION JOINTS EVERY 20 FEET AND AT ALL P.C. AND P.T. OF CURVES WITH 1/2 INCH MIN. SCORED JOINTS MUST BE INSTALLED EVERY 5 FEET ALONG CONCRETE SIDEWALK.
 - ALL EXPANSION JOINTS WILL BE PERFORMED



SECTION B - B
SCALE: 1" = 2'

TYPICAL CONCRETE DRIVEWAY

* CONCRETE DRIVEWAYS INSTALLED BY INDIVIDUAL PROPERTY OWNERS / BUILDERS *

ALL LOTS WITHIN VALLEY CREEK UNIT FOUR WILL REQUIRE TWO (1 EACH) PERMANENT ELEVATION MARKERS TO BE PLACED AT THE LOWEST POINT OF FRONT AND BACK YARDS. TO BE INSTALLED BY BUILDER / CONTRACTOR AND COORDINATED WITH ENGINEER / SURVEYOR.

TYPICAL PERMANENT ELEVATION MARKER
SCALE 1" = 1'

ENGINEERING DEPARTMENT
DESIGN STANDARDS
FOR CONSTRUCTION
TITLE 19 - SUBDIVISION ORDINANCE
2-19

CONCRETE APRON FOR CIRCULAR PENETRATIONS IN ASPHALT PAVEMENTS				
"D" DIAMETER OF PENETRATION (INCHES)	"A" CONCRETE HORIZONTAL DIMENSION FROM PENETRATION (INCHES)	NUMBER OF NO. 3 REINFORCING STEEL BARS (INCHES)	"B" MINIMUM CLEARANCE FROM EDGE OF CONCRETE APRON TO CENTER OF NEAREST REBAR (INCHES)	"C" MINIMUM CLEARANCE FROM PENETRATION EDGE TO CENTER OF NEAREST REBAR (INCHES)
0 TO 6.01	6	1	1 1/2	1 1/2
6.01 TO 18.01	8	2	1 1/2	1 1/2
18.01 AND OVER	12	3	1 1/2	1 1/2

CONSTRUCTION NOTES:

- ANY DISTURBED SUBGRADE UNDER THE CONCRETE APRON SHALL BE COMPACTED TO 95% DENSITY & 2% MAXIMUM MOISTURE CONTENT IN ACCORDANCE WITH ASTM D-1557.
- ANY DISTURBED COURSE UNDER THE CONCRETE APRON SHALL BE COMPACTED TO 100% DENSITY & 2% MAXIMUM MOISTURE CONTENT IN ACCORDANCE WITH ASTM D-1557.
- PROVIDE A MINIMUM OF 1 1/2" OF CONCRETE COVER FOR ALL REINFORCEMENT STEEL.
- REINFORCING SHALL MEET ASTM C-478 AND TRAFFIC LOADING (HS-20).
- NO. 3 REINFORCING STEEL HOOPS SHALL BE SPACED EQUALLY.

GENERAL NOTES:

- THE PENETRATION APRON SHOULD BE CAST IN-PLACE CONCRETE (MINIMUM 28 DAY COMPRESSIVE STRENGTH 4000 PSI. HIGH EARLY CONCRETE IS REQUIRED).
- TOPS OF PENETRATION APRON SHALL BE FLUSH WITH ROADWAY SURFACE OR FINISHED GRADE UNLESS OTHERWISE SPECIFIED BY THE CITY ENGINEER.

Pedestrian Facilities General Notes

- ALL SLOPES ARE MAXIMUM ALLOWABLE. THE LEAST POSSIBLE SLOPE THAT WILL STILL DRAIN PROPERLY SHOULD BE USED. ADJUST CURB RAMP LENGTH OR GRADE OF APPROACH SIDEWALKS AS DIRECTED.
- LANDINGS SHALL BE 5'X 5' MINIMUM WITH A MAXIMUM 2% SLOPE IN ANY DIRECTION.
- MANEUVERING SPACE AT THE BOTTOM OF CURB RAMP SHALL BE A MINIMUM OF 4'X 4' WHOLLY CONTAINED WITHIN THE CROSSWALK AND WHOLLY OUTSIDE THE PARALLEL VEHICULAR TRAVEL PATH.
- MAXIMUM ALLOWABLE CROSS SLOPE ON SIDEWALK AND CURB RAMP SURFACES IS 2%.
- CURB RAMP WITH RETURNED CURBS MAY BE USED ONLY WHERE PEDESTRIANS WOULD NOT NORMALLY WALK ACROSS THE RAMP. EITHER BECAUSE THE ADJACENT SURFACE IS PLANTING OR OTHER NON-WALKING SURFACE OR BECAUSE THE SIDE APPROACH IS SUBSTANTIALLY OBSTRUCTED. OTHERWISE, PROVIDE FLARED SIDES.
- ADDITIONAL INFORMATION ON CURB RAMP LOCATION, DESIGN, LIGHT REFLECTIVE VALUE AND TEXTURE MAY BE FOUND IN THE CURRENT EDITION OF THE TEXAS ACCESSIBILITY STANDARDS (TAS) AND 16 TAC 68.102.
- SEPARATE CURB RAMP AND LANDINGS FROM ADJACENT SIDEWALK AND ANY OTHER ELEMENTS WITH PREMIUM BITUMINOUS EXP. JOINT OR BOARD JOINT OF 3/4" UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- PROVIDE A SMOOTH TRANSITION WHERE THE CURB RAMP CONNECTS TO THE STREET.
- FLARE SLOPE SHALL NOT EXCEED 10% MEASURED ALONG CURB LINE.

General Notes for Detectable Warnings

- CURB RAMP MUST CONTAIN A DETECTABLE WARNING SURFACE THAT CONSISTS OF RAISED TRUNCATED DOMES COMPLYING WITH SECTION 4.29 OF THE TEXAS ACCESSIBILITY STANDARDS (TAS). THE SURFACE MUST CONTRAST VISUALLY WITH ADJOINING SURFACES, INCLUDING SIDE FLARES. FURNISH DARK BROWN OR DARK RED DETECTABLE WARNING SURFACE ADJACENT TO UNCOLORED CONCRETE, UNLESS SPECIFIED ELSEWHERE IN THE PLANS.
- DETECTABLE WARNING SURFACES MUST BE SLIP RESISTANT AND NOT ALLOW WATER TO ACCUMULATE.
- ALIGN TRUNCATED DOMES IN THE DIRECTION OF PEDESTRIAN TRAVEL WHEN ENTERING THE STREET.
- DETECTABLE WARNING SURFACES SHALL BE A MINIMUM OF 24" IN DEPTH IN THE DIRECTION OF PEDESTRIAN TRAVEL, AND EXTEND THE FULL WIDTH OF THE CURB RAMP OR LANDING WHERE THE PEDESTRIAN ACCESS ROUTE ENTERS THE STREET.
- DETECTABLE WARNING SURFACES SHALL BE LOCATED SO THAT THE EDGE NEAREST THE CURB LINE IS A MINIMUM OF 6" AND A MAXIMUM OF 10" FROM THE EXTENSION OF THE FACE OF CURB. DETECTABLE WARNING SURFACES MAY BE CURVED ALONG THE CORNER RADII.

CITY DEVELOPMENT DEPARTMENT
REVIEWED

This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and an instrument of services in respect to the project for which it was prepared. This document is not intended or authorized for reuse by any party on extensions of such project or any other project. Any reuse, including copying and/or modifying the document, without written permission from Roe Engineering, L.C. for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.

FLOOD NOTE:
NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X". (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD.) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B, DATED SEPTEMBER 4, 1995.


VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID CED442) NAVD 88 DATUM AND REFERENCED TO NAD83. HAVING AN ELEVATION OF 3754.96. (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 354501.733)

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES	HOR: _____ VER: _____ FILE NAME: 19E.DWG W.O. 111411-3 VC5 DATE: DECEMBER, 2013 DESIGN BY: LAJ/HP DRAWN BY: L.A.J./S.R. CHKD. BY: H.P. APPD. BY: BR
			ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	


THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

VALLEY CREEK UNIT FIVE
TYPICAL DETAILS
BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

Roe Engineering, L.C.
601 N. Cotton St. Suite No. 8 El Paso, TX 79902
(915) 533-1418 - FAX: (915) 533-4972
e-mail: roeeng@swbell.net
ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C10 OF C-15




GRAPHIC SCALE



(IN FEET)
1 inch = 50 ft.

CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
C1	56.00	87.72'	55.76'	79.02'	S 44°54'59" E	89°45'00"
C2	20.00	31.33'	19.91'	28.22'	N 44°54'59" W	89°45'00"
C3	300.56	169.02'	85.81'	168.80'	N 24°44'03" E	32°13'14"
C4	30.00	18.28'	9.43'	18.00'	N 17°24'58" E	34°54'55"
C5	70.00	17.02'	8.55'	16.98'	S 27°54'26" W	13°55'59"
C6	70.00	68.05'	36.98'	65.40'	S 06°54'26" E	55°41'45"
C7	70.00	66.97'	35.67'	63.56'	S 61°45'15" E	53°59'54"
C8	70.00	43.93'	22.71'	43.21'	N 73°16'12" E	35°57'12"
C9	30.00	18.28'	9.43'	18.00'	S 72°45'04" W	34°54'55"
C10	30.00	23.86'	12.60'	23.24'	N 87°00'18" W	45°34'23"
C11	50.00	66.53'	39.23'	61.73'	S 82°20'17" E	78°14'22"
C12	50.00	52.00'	28.63'	49.68'	N 29°45'01" E	59°35'01"
C13	50.00	51.99'	28.62'	49.68'	N 29°45'01" W	59°34'51"
C14	50.00	66.10'	38.88'	61.39'	S 82°30'24" W	75°44'32"
C15	30.00	23.86'	12.60'	23.24'	N 67°25'20" E	45°34'23"
C16	30.00	46.99'	29.87'	42.33'	S 44°54'59" E	89°45'00"
C17	20.00	31.33'	20.09'	28.35'	S 45°05'01" W	90°15'00"

LINE	BEARING	LENGTH
L1	N 21°50'31" E	67.91'
L2	N 00°02'29" W	30.00'
L3	N 89°47'29" W	32.99'
L4	S 81°22'34" E	40.00'



- DENOTES LOCATION OF EXISTING LIGHT POLE
- DENOTES LOCATION OF PROPOSED LIGHT POLE (3 POLES TOTAL)
- DENOTES LOCATION OF NDCBU (4' X 6'-2 SITES TOTAL)
- DENOTES LOCATION OF PROPOSED 30" X 30" SIGNS
- DENOTES LOCATION OF PROPOSED 9" SNS WITH 30" STS

NEMEXAS DRAIN
(120' WIDE RIGHT-OF-WAY)


UPPER VALLEY ROAD

CITY DEVELOPMENT DEPARTMENT

REVIEWED

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013, ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES.	HOR: AS SHOWN, VER: AS SHOWN FILE NAME: VC_5_ILLDWG W.O. 111411-3_VCS DATE: DECEMBER, 2013 DESIGN BY: L.A.J./HP DRAWN BY: L.A.J./S.R. CHKD BY: H.P. APPD BY: BR
			ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	



VALLEY CREEK UNIT FIVE
ILLUMINATION PLAN
BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.


bnpRoe Engineering, L.C.
601 N. Cotton St. Suite No. 6 El Paso, Tx. 79902
(915) 633-1418 - FAX: (915) 633-4972
e-mail: roeeng@bnpnet.net
ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C11 OF C-15

C:\Projects\114111-3 VALLEY CREEK UNIT 5 AND 5A\Drawings\01-CH_VCS_ILLDWG_12/17/13_5:28PM

This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and an instrument of services in respect to the project for which it was prepared. This document is not intended or authorized for reuse by any party on extensions of such project or any other project. Any reuse, including copying and/or modifying the document, without written permission from Roe Engineering, L.C., for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.

FLOOD NOTE:
NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X". (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD.) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B, DATED SEPTEMBER 4, 1995.

VERTICAL DATUM NOTE:
NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID CE0442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHERN 1070302.594, EASTING 354501.735)



ALTERNATE RESIDENTIAL STREET LIGHT WOOD POLE

NOT TO SCALE


ITEM No.	DISCRIPTION	STOCK No.	QTY.
1	POLE, 35 FT. - CLASS IV	009-035	1
2	SCHEDULE 80 - 1" CONDUIT	017-280	3
3	PIPE STRAP FOR 1" CONDUIT, 2 - HOLE	017-334	7
4	LAG BOLT, 1/4" X 2"	002-330	6
5	WEATHERHEAD, 1" CONDUIT	017-293	1
6	PHOTOCELL, 240V - SEE NOTE 1	021-225	1
7	LAG BOLT, 1/2" X 4"	002-370	2
8	MACHINE BOLT, 5/8" X 8"	002-450	1
9	SQUARE GALV. WASHER, 2 - 1/4" X 2 - 1/4"	002-760	1
10	COIL-SPRING WASHER, 5/8"	002-786	1
11	LOCKNUT, 5/8"	002-705	1
12	LUMINAIRE, 100W H.P.S.	021-335	1
13	HPS LAMP, 100W	021-085	1
14	MAST ARM, 6' X 1-1/4"	021-200	1
15	COPPER CABLE, #12, 19 STRAND, 600 V	013-665	
16	COPPER CABLE, #12, SOLID, 600 V, GREEN	013-701	
17	CABLE, #10, 2 CONDUCTOR, 600 V, UF	013-600	8
18	SLEEVES, #12-10	005-140	2
19	GROUNDING CLAMP	021-215	1

KEYNOTES:

1. MOUNT SO THAT CONTROL FACES NORTH.
2. ITEM 17 SHALL NOT BE SPLICED INSIDE ITEM 14.

DESIGN NOTES:

1. INSTALLATION SHALL COMPLY WITH ALL LOCAL CODE REQUIREMENTS.
2. FOR ANY CLARIFICATION, EXCEPTIONS TO QUESTIONS REGARDING CODE INTERPRETATION, CALL EL PASO ELECTRIC CO. DISTRIBUTION DEVELOPMENT DEPARTMENT.
3. THE LUMINAIRE SHALL BE DARK SKY COMPLIANT.



KEYNOTES:

1. 1/2" GALVANIZED RIGID CONDUIT
2. REDUCER 1" TO 1/2" BUSHING
3. 1" PVC FEMALE ADAPTER
4. 1" PVC 90° ELBOW
5. 1" PVC CONDUIT
6. 1" PVC 45° ELBOW
7. 1" PVC COUPLING
8. TAPE 1/2" RIGID CONDUIT (6")


ALTERNATE RESIDENTIAL STREET LIGHT WOOD POLE CONNECTION TO SERVICE ENCLOSURE

NOT TO SCALE

ITEM No.	DIRECT EMBEDDED SL STANDARD	STOCK / DSU No.	QTY.	C/U CODE	MACRO CODE
1	PHOTO CELL, 240 V - SEE NOTE 1	21-225	1		
2	HPS LAMP, 100W	21-085	1	LCOBRAHD	
3	LUMINAIRE, 100W H.P.S.	21-335	1		
4	D.E. STANDARD, 34' 6" WITH 4' MAST ARM	09-310	1	L34STLUG	
5	FUSE 10A	21-240	2	LFUSE10A	
6	FUSEHOLDER - 30A SUBMERSIBLE	21-246	2	LFUSEHSB	
7	COPPER CABLE, #12, SOLID, 600V, RED	13-702	70'	LC#12CU	
8	BUTT SPLICE, #12 - #12	5-140	2	LSLV1210	
9	5/8" X 10' CU BONDED GROUND ROD	08-626	1		LSTLDEUG
	5/8" GROUND ROD CLAMP	07-461	1		
	TRANSFORMER GROUND CLAMP	04-100	1	LGRNDROD	
	#4 BARE COPPER-CLAD	12-106	6'		
10	1" PVC FLEX CONDUIT	21-257	6'	LPVCFX1	
11	1" PVC FLEX CONDUIT FITTING	21-214	1	LFLEXFIT1	
12	1" PVC FEMALE ADAPTER	17-295	1	LFADAPT1	
13	1" PVC 45 DEGREE ELBOW	17-298	1	LEL451	
14	1" PVC COUPLING	17-296	1	LCPLG1	
15	1" PVC CONDUIT	17-299	AS REQ	LPVC1	
16	COPPER CABLE, #12, SOLID, 600V, RED	13-702	AS REQ	LC#12CU	

NOTES:


1. MOUNT SO THAT PHOTO CELL IS FACING NORTH.
2. INSTALLATION MUST COMPLY WITH LOCAL CODE REQUIREMENTS.
3. FOR ANY CLARIFICATION, EXCEPTIONS OR QUESTIONS REGARDING THIS STANDARD, CALL THE EL PASO ELECTRIC COMPANY DISTRIBUTION DESIGN DEPARTMENT.
4. ON STREET WHERE SIDEWALK IS ADJACENT TO CURB, STREET LIGHT POLE SHALL BE INSTALLED IN THE SIDEWALK NEXT TO PROPERTY LINE. 36 INCHES REQUIRED FROM BACK OF CURVE TO COMPLY WITH AMERICAN DISABILITY'S ACT AND LOCAL CODES.
5. THE LUMINAIRE SHALL BE DARK SKY COMPLIANT.



DIRECT EMBEDDED STANDARD FOR RESIDENTIAL STREET LIGHTING



THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



HOR: AS SHOWN VER: AS SHOWN
 FILE NAME: VC_5_ILLDWG
 W.O.: 111411-3_VCS
 DATE: DECEMBER 2013
 DESIGN BY: LAJ/HP
 DRAWN BY: L.A.J./S.R.
 CHKD. BY: H.P.
 APPD. BY: BR

VALLEY CREEK UNIT FIVE ILLUMINATION DETAILS

BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

RoE Engineering, L.C.
 601 N. Cotton St. Suite No. 8 El Paso, Tx. 79902
 (915) 533-1418 - FAX (915) 533-4972
 e-mail: roeeng@roebell.net

ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING

SHEET C12 OF C-15

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES ELEVATION: 3708.40 CITY DATUM) (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	

FLOOD NOTE:

NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X" (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE, AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B. DATED SEPTEMBER 4, 1995.


VERTICAL DATUM NOTE:

NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 RFB" (NGS PID CE0442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 354501.735)


C:\Projects\111411-3 VALLEY CREEK UNIT 5 AND 5 Views\111411-3 VALLEY CREEK UNIT 5.dwg 12/16/13 10:21 AM

Specifications for Reflectorized Street Name Signs

- Color of Sign:** The finished sign must have a reflectorized green background. The green must conform with the Bureau of Public Roads Highway Green. The legend must be reflectorized silver white (green reverse screened background with silver copy).
- Letter Design:** The lettering of all legends must be upper case letters in accordance with "standard alphabets for highway sign" published by the Federal Highway Administration.
- Letter Spacing:** The control for the spacing values in traffic layout is the distance recognized as aesthetic spacing between two straight letters (H). A spacing control of two times the width of the stroke of the letter series to be used must be the aesthetic control (100%). Two and one-half times (2-1/2) this control must be used as the aesthetic word space between elements in the primary legend.
- Layout:** The maximum number of letters to be accommodated on a given length street name face must be determined by widest letter series possible for that legend and the spacing control (100%) for the series used must be expanded or condensed up to 25% in 5% increments.
- The spacing control (100%) for the series used must be expanded or condensed up to 25% in 5% increments for the end margin with minimum of 1".
- The word space must be expanded up to 25% in 5% increments but not condensed.
- Space between primary and block number area must be 1/2 the aesthetic work space used in the primary legend.
- Suffix letter size for all lengths must be 2" Capitals, "C" series except that series "A" or "B" where suffix abbreviations exceeds two letters, may be used.
- Size of Legend:** For 9" street name signs, the primary legend, or street name must have capital letters six inches (6") high and all secondary legends, including the suffix, block numbers, must have upper case letters two and one-half inches (2-1/2") high.
- Suffix letter size for all lengths must be 2-1/2" capitals, "C" series, except that series A and B where suffix abbreviation exceeds two letters, may be used.
- Position of Legend:** Each sign face will consist of the street name, suffix and two zeros of the block number. The additional numbers of the block number will be applied by the city of El Paso. The suffix will be located in the upper right corner and the block number in the lower right corner of the sign face and the street name centered in the remaining space.
- Sign Fabrication:** The sign face must be fabricated by reverse screening green transparent color over silver reflective sheeting. Transparent process colors must be as recommended by the sheeting manufacturer. Cut-out or applied legends are not permitted. Sign face must be comprised of one piece or panel of reflective sheeting.
- Type of sheeting:** High intensity reflective sheeting must be used in the fabrication of the street name sign faces.




SIGN CLASS	SIGN LENGTH	PRIMARY LETTERS SIZE & SERIES	SUFFIX & BLOCK NUMBER SIZE AND SERIES
6" ARTERIAL STREETS	24" 30" 36"	4" C.D. SERIES 4" C.D. SERIES 4" A,B,C,D. SERIES	2" C SERIES 2" C SERIES 2" C SERIES



LAYOUT FOR 6" STREET NAME SIGN

SCALE: 1" = 1'


SIGN CLASS	SIGN LENGTH	PRIMARY LETTERS SIZE & SERIES	SUFFIX & BLOCK NUMBER SIZE AND SERIES
9" ARTERIAL STREETS	36" 42" 48"	6" C.D. SERIES 6" C.D. SERIES 6" A,B,C,D. SERIES	3" C SERIES 3" C SERIES 3" C SERIES



LAYOUT FOR 9" STREET NAME SIGN


SCALE: 1" = 1'

SIGN CLASS	SIGN LENGTH	PRIMARY LETTERS SIZE & SERIES	SUFFIX & BLOCK NUMBER SIZE AND SERIES
9" ARTERIAL STREETS	36" 42" 48"	6" B,C,D. SERIES 6" B,C,D. SERIES 6" A,B,C,D. SERIES	3" C SERIES 3" C SERIES 3" C SERIES



LAYOUT FOR 9" STREET NAME SIGN

SCALE: 1" = 1'




R1-1

A	B	C	D	E
30	.75	10	10	12.5

COLORS LEGEND - WHITE (RETROREFLECTIVE)
BACKGROUND - RED (RETROREFLECTIVE)

STOP SIGN DETAIL

SCALE: NOT TO SCALE



W1-1

A	B	C	D	E	F	G	H	J	K	L	M	N
30	.5	.75	12	3.75	4.375	6.688	6.25	3	1.875	1	4.063	1.875

COLORS LEGEND - BLACK
BACKGROUND - YELLOW (RETROREFLECTIVE)

W1-1R(L) SIGN DETAIL

SCALE: NOT TO SCALE


STANDARD ARROW DETAIL

SCALE: NOT TO SCALE

A	B	C	D	E
4.375	5	8.875	6.688	8.875

STANDARD ARROW DETAIL

SCALE: NOT TO SCALE



W14-1P


SCALE: NOT TO SCALE

COLORS LEGEND - BLACK
BACKGROUND - YELLOW (RETROREFLECTIVE)

A	B	C	D	E	F
9	.5	.75	6	36	1.875

W14-1P

SCALE: NOT TO SCALE




W14-2

A	B	C	D	E	F	G	H	J	K	L
30	.5	.75	6D	4	.938	5	5.375	13.938	14.5	1.875

COLORS LEGEND - BLACK
BACKGROUND - YELLOW (RETROREFLECTIVE)

W14-2 NO OUTLET SIGN DETAIL


SCALE: NOT TO SCALE



- NOTES:
- FILL HOLES 3/8" PUNCH
 - FILLETS AND ROUNDS 1/16" = R
 - FURNISH THE FOLLOWING HARDWARE FOR EACH BRACKET:
1 - 5/16" X 3/4" BOLTS
1 - 5/16" X 1 1/4" BOLT
2 - 5/16" NUTS & LOCK WASHERS
2 - 5/16" X FLAT WASHERS
 - THE BRACKET IS TO BE MADE FROM HIGH STRENGTH ALUMINUM ALLOY. THE BRACKET IS TO EMPLOY AN EXTRUDED INTERLOCKING FEATURE OFFERING A RIGID MEANS OF ATTACHING A FLAT SIGN TO A STANDARD 2" (3/8" O.D.) TUBULAR POST.

ALUMINUM SIGN CLAMP BRACKET FOR TRAFFIC CONTROL SIGNS


SCALE: 1" = 1'



- NOTES:
- WELD ALONG ITS LENGTH TO FORM VIRTUALLY SEAMLESS.
 - POST SHALL BE HOT-DIPPED ZINC GALVANIZED UNIFORMLY ON THE OUTSIDE WITH A NOMINAL ZINC WEIGHT OF 1.0 OUNCE PER SQUARE FOOT.
 - THE ZINC COATING IS TO BE OVER-COATED WITH A CHROMITE CONVERSION AND ACRYLIC COATING TO PROVIDE RESISTANCE TO RUSTING AND CORROSION.
 - THE INSIDE OF THE POST SHALL BE COATED WITH AN ORGANIC MATERIAL FOR PROTECTION AGAINST RUST.
 - BOTH ENDS ARE TO BE SQUARELY CUT WITHOUT FLARES.
 - POST SHALL BE FREE WARPS, CORROSION, OR OTHER DEFECTS.
 - RING WELDS OR SPLICES WILL NOT BE ACCEPTABLE.
 - BENDING STRENGTH AS SPECIFIED BY AASHTO FOR SCHEDULE 40 PIPE.
 - POST SHALL BE BUNDLE WITH METAL STRAPS AND SHALL NOT EXCEED 37 POST PER BUNDLE.

SIGN POST SPECIFICATIONS

SCALE: NOT TO SCALE



SOLID DOUBLE YELLOW LINE STRIPING

SCALE: 1" = 1'



REVIEWED

VALLEY CREEK UNIT FIVE

STREET SIGN DETAILS AND SPECIFICATIONS


BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3,752 acres more or less.

bnp Roe Engineering, L.C.
601 N. Cotton St. Suite No. 8 El Paso, Tx. 79902
(915) 633-1416 - FAX: (915) 633-4972
e-mail: roeeng@bnpbell.net

ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING

SHEET C13 OF C-15

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY BRADLEY ROE, P.E. 31886 ON SEPT. 2013. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.



HOR: AS SHOWN VER: AS SHOWN
FILE NAME: VC_5_ILLDWG
W.O. 111411-3 VCS
DATE: DECEMBER 2013
DESIGN BY: LAJ/HP
DRAWN BY: L.A.J./S.R.
CHKD. BY: H.P.
APPD. BY: BR

EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES
ELEVATION: 3708.40 CITY DATUM
(ELEVATION: 3751.05 NAVD 85)
STATE PLANE COORDINATES:
N 10693708.719 E 349632.2

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE

FLOOD NOTE:


NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X" (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212 0125 B. DATED SEPTEMBER 4, 1995.


VERTICAL DATUM NOTE:

NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID C80442) NAVD 88 DATUM AND REFERENCED TO NAD83 HAVING AN ELEVATION OF 3754.36 (STATE PLANE COORDINATES OF NORTING 10700302.594, EASTING 364501.733)


SIGN POST INSTALLATION

NOT TO SCALE






GRAPHIC SCALE



LINE TABLE		
LINE	BEARING	LENGTH
L1	N 21°50'31" E	67.91'



LEGEND

	Proposed Stabilized Entrance / Exit
	Silt Fencing
	Existing Berm
	Existing Rockwall

THIS SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY
 BRADLEY ROE, P.E. 31886 ON SEPT. 2013, ALTERATION OF A SEALED
 DOCUMENT WITHOUT PROPER NOTIFICATION TO RESPONSIBLE ENGINEER IS
 AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT.

CITY DEVELOPMENT DEPARTMENT
REVIEWED

C:\Projects\11411-3 VALLEY CREEK UNITS 4 AND 5\wp\VC5 Eng Postgraph\VC4-C14 VCL_WXP.DWG 12/12/13 8:39PM

This document, whether in hard copy or machine readable format, is owned by Roe Engineering, L.C. and no part of it may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Roe Engineering, L.C. for the specific purpose intended may be a violation of law. Unauthorized use of this material may result in civil and/or criminal penalties.


FLOOD NOTE:
 NOTE: THE ABOVE REFERENCED PROPERTY IS WITHIN ZONE "X". (EXPLANATION: AREAS OF 500-YEAR FLOOD; AREAS OF 100-YEAR FLOOD WITH AVERAGE DEPTHS OF LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS THAN 1 SQUARE MILE; AND AREAS PROTECTED BY LEVEES FROM 100-YEAR FLOOD.) ACCORDING TO THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAPS, AS PER THE UNINCORPORATED AREAS COMMUNITY PANEL NO. 480212.0125 B, DATED SEPTEMBER 4, 1995.

VERTICAL DATUM NOTE:
 NOTE: VERTICAL DATUM BASED ON DESIGNATION "5 REB" (NGS PID CR0442) NAVD 88 DATUM AND REFERENCED TO NAD83. HAVING AN ELEVATION OF 3754.36. (STATE PLANE COORDINATES OF NORTHING 10700302.594, EASTING 364501.733)

DATE	REVISIONS	BY	PRIMARY BENCHMARK	SCALE
			EXISTING CITY MONUMENT LOCATED ALONG THE CENTERLINE OF COUNTY OAKS DRIVE AT THE NORTH HEEL OPPOSITE LOT 9, BLOCK 2, RIVER RUN ESTATES ELEVATION: 3708.40 CITY DATUM (ELEVATION: 3751.05 NAVD 88) STATE PLANE COORDINATES: N 10693708.719 E 349632.2	HOR: AS SHOWN VER: AS SHOWN FILE NAME: VC 4_SW3P.DWG W.O. 111411-3 VC5 DATE: DECEMBER 2013 DESIGN BY: LAJ/HP DRAWN BY: L.A.J./S.R. CHKD. BY: H.P. APPD. BY: BR

SCALE

HOR: AS SHOWN VER: AS SHOWN
 FILE NAME: VC 4_SW3P.DWG
 W.O. 111411-3 VC5
 DATE: DECEMBER 2013
 DESIGN BY: LAJ/HP
 DRAWN BY: L.A.J./S.R.
 CHKD. BY: H.P.
 APPD. BY: BR



VALLEY CREEK UNIT FIVE
STORM WATER POLLUTION PREVENTION PLAN
 BEING A PORTION OF TRACT 10, BLOCK 7, UPPER VALLEY SURVEYS, CITY OF EL PASO, TEXAS, EL PASO COUNTY, TEXAS CONTAINING IN ALL 163,753.62 sq. ft. OR 3.7592 acres more or less.

bnp Roe Engineering, L.C.
 601 N. Cotton St. Suite No. 6 El Paso, TX, 79902
 (915) 533-1418 - FAX: (915) 533-4978
 e-mail: roeeng@swbell.net
 ENGINEERING/LAND DEVELOPMENT/PLANNING/SURVEYING
SHEET C14 OF C-15

